

United States Department of the Interior National Park Service
NATIONAL REGISTER OF HISTORIC PLACES REGISTRATION FORM

1. Name of Property

historic name: "Ravenswood"

other name/site number: Ravenswood "Old Town" Historic District (preferred)

2. Location

street & number: Bounded by Sandy Creek; the Ohio River; Sycamore St. and adjoining properties; and the city limits to the east. not for publication: N/A

city/town: Ravenswood vicinity: N/A

state: West Virginia code: WV county: Jackson code: 035 zip code: 26164

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property meets does not meet the National Register Criteria. I recommend that this property be considered significant nationally statewide locally. (See continuation sheet.)

Susan M. Pierce

Susan M. Pierce, Deputy State Historic Preservation Officer

9/5/07
Date

West Virginia Division of Culture and History
State or Federal agency and bureau

In my opinion, the property meets does not meet the National Register criteria.
(See continuation sheet for additional comments.)

Signature of Certifying Official/Title

Date

State or Federal agency and bureau

4. National Park Service Certification

I, hereby certify that this property is: Signature of Keeper Date of Action

_____ entered in the National Register _____ _____
_____ See continuation sheet.

_____ determined eligible for the _____ _____
National Register

_____ See continuation sheet.

_____ determined not eligible for the _____ _____
National Register

_____ removed from the National Register _____ _____

_____ other (explain): _____

5. Classification

Ownership of Property:
(Check as many boxes as apply)

Category of Property:
(Check only one box)

- private
- public-local
- public-State
- public-Federal

- building(s)
- district
- site
- structure
- object

Number of Resources within Property
(Do not include previously listed resources in the count.)

Contributing	Non-contributing	
313	296	buildings
		sites
2		structures
		objects
315	296	TOTAL

Name of related multiple property listing N/A
(Enter "N/A" if property is not part of a multiple property listing.)

Number of contributing resources previously listed in the National Register 4

=====

6. Function or Use

=====

Historic Functions

Current Functions

DOMESTIC/single dwelling
COMMERCE/business

DOMESTIC/single dwelling
COMMERCE/business

=====

7. Description

=====

Architectural Classification

MID-19TH CENTURY: Greek Revival, Gothic Revival

LATE VICTORIAN: Italianate, Second Empire, Queen Anne

LATE 19th AND 20th CENTURY REVIVALS: Colonial Revival, Classical, Neo-Classical Revival, Tudor Revival

LATE 19th AND EARLY 20th CENTURY AMERICAN MOVEMENTS: Commercial Style, Craftsman Four Square, Craftsman, Bungalow

MODERN MOVEMENT: Ranch Style, Moderne, Art Deco

OTHER: Ohio River Rail Road Steel Pratt-through truss Bridge and Concrete bridge on State Route 68 over Sandy Creek

Materials

Foundation: brick, sandstone, concrete, steel

Walls: wood (weatherboard, shingle, T1), vinyl, brick, aluminum, stucco, concrete (asbestos) shingles, asphalt shingles

Roof: asphalt, steel, slate, ceramic tile, rubber

Other: brick, sandstone, concrete, wood, vinyl, aluminum, stucco

Narrative Description
(See continuation sheets)

=====

8. Statement of Significance

=====

Applicable National Register Criteria

(Mark "X" in one or more boxes for the criteria qualifying the property for National Register listing.)

A Property is associated with events that have made a significant contribution to the broad patterns of our history.

B Property is associated with the lives of persons significant in our past.

C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.

D Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

Property is:

A owned by a religious institution or used for religious purposes.

B removed from its original location.

C a birthplace or grave.

D a cemetery.

E a reconstructed building, object, or structure.

F a commemorative property.

G less than 50 years of age or achieved significance within the past 50 years.

Areas of Significance

Architecture

Commerce

Community Planning and Development

Period of Significance

c. 1830-1957

Significant Dates

Significant Person

N/A

Cultural Affiliation

N/A

Architect/Builder

Brown, Tanzy (Builder)

Glover, Richard (Builder)

Pruden, William (Builder)

Taylor, J.W. (Builder)

Shockey, Jacob (Builder)

Narrative Statement of Significance

(See continuation sheets)

=====
9. Major Bibliographical References
=====

Bibliography

(See continuation sheets)

Previous documentation on file (NPS):

_____ preliminary determination of individual listing (36 CFR 67) has been requested.

_____ previously listed in the National Register

_____ previously determined eligible by the National Register

_____ designated a National Historic Landmark

_____ recorded by Historic American Buildings Survey # _____

_____ recorded by Historic American Engineering Record # _____

Primary location of additional data:

State Historic Preservation Office

_____ Other State agency

_____ Federal agency

Local government (**Ravenswood City Hall and Jackson County Court House**)

_____ University

Other (**Ravenswood Historic Landmark Commission, Jackson County Libraries and the Washington Lands Museum in Ravenswood.**)

Name of Repository: see above

=====
10. Geographical Data

Ravenswood's "Old Town" Historic District

Name of Property

Jackson, WV

County and State

=====
Acreage of Property: 125

UTM References (Place additional UTM references on a continuation sheet.)

Quad Map Name: Ravenswood West Virginia-Ohio Quadrangle

Vertex	Zone	Easting	Northing
1	17	433689	4311113
2	17	433863	4311212
3	17	434840	4311529
4	17	434802	4311158
5	17	434914	4310874
6	17	434837	4310772
7	17	434382	4310959
8	17	434131	4310931
9	17	434167	4310860
10	17	434065	4310799
11	17	434029	4310860
12	17	433963	4310799

Verbal Boundary Description

(See attached Topographic Map and District Map)

Boundary Justification

(See continuation sheet.)

=====
11. Form Prepared By

=====
Name/Title: Mark Gorman / President with Fox Engineering and Michael Gioulis,
Historic Preservation Consultant

Organization: Ravenswood Historic Landmark Commission Date: 06 October 2006

Street & Number: 212 Walnut Street Telephone: (304) 273.2878

City or Town: Ravenswood State: WV ZIP: 26164

=====
Property Owner

=====
Name: Multiple Owners

Street & Number: _____ Telephone: _____

City or Town: _____ State: _____ Zip: _____
=====

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 1**Description**

Present-day Ravenswood sits on the eastern (left) bank of the Ohio River between mile points 220 and 221, approximately mid-way between Pittsburgh and Cincinnati. The Ohio River, a product of the last ice age in North America, marks the southern and eastern most advance of the glaciers. As the glaciers melted, the sand, gravel, cobbles and boulders that they had transported were deposited as glacial till and moraine. Ravenswood rests on these deposits. The Ohio River began to carve its channel through these deposits and continues to do so today.

The benches and plains of the Ohio River Valley are characterized by fertile, well-drained soils. These lowlands were a favorite hunting ground of Native Americans and were some of the most sought after lands by the area's early European settlers. The majority of Ravenswood rests on a bench of these soils that lies out of the 100-year floodplain.

The northern boundary of the district is Sycamore Street; the eastern boundary is the residential properties to the east of Preston and Bedford Streets (the town's eastern, corporate limits); the southern boundary is Sandy Creek; and the western boundary is the Ohio River.

The "Old Town" section of the City of Ravenswood lies at the confluence of Sandy Creek and the Ohio River. The CSX Railroad (successor to the Ohio River Rail Road and the B&O) bisects the western portion of the historic district along Broadway Street. Washington Street (State Route 68) runs north-south through the historic district. The commercial resources are located primarily along Washington Street with scattered locations for about two blocks along Sand, Walnut and Mulberry Streets and a block on either side of Sycamore Street.

Historically, the older commercial section of the town focused on the river, and it was centered along Broadway and Water Streets. However, due to repeated flooding, a shift was made for dryer locations to the east. The residential portion of the "Old Town" is located primarily east of Washington Street. The residences are not densely packed as in some other urban areas and each lot is a generous size with front, side and/or rear yards. The streets are wide avenues that are a typical riverfront-town feature.

The district contains primarily mid to late 19th and early 20th century resources. Due to the age of the town and its resources, some modifications have been made, but they are not found in great numbers. Homes and businesses are generally well maintained. Forced or voluntary demolition of homes or business buildings is an infrequent occurrence. When it does occur, it will typically be the result of fire damage. Modern intrusions are not found in great numbers. For the most part, modern intrusions are located to the north of the "Old Town" district. Within

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 2

the district, most modern intrusions are located close to the Ohio River, due to reconstruction following flood events. Thus, the historic district area maintains much of its original ambience and character.

The town of Ravenswood adopted a Comprehensive Plan for Development and Planning and Zoning Ordinances in the 1950s, in anticipation of the development that was expected to follow the Kaiser Aluminum and Chemical Corporation's decision to build the world's largest integrated aluminum reduction and fabrication mill in the Ravenswood vicinity. The majority of the property within the district was zoned as a "C-Commercial District" or a "R2 Multiple-Family Residential District". Of course, the R-2 zoning also allows for single-family dwellings. In fact, most of the homes in the district are single-family residences. A small proportion are homes that have been divided into multiple apartments and a still smaller proportion are structures that were constructed as multi-family units or were commercial buildings that have been converted into multi-family housing units.

In the "C" district, buildings are limited to a maximum height of 2 stories or 30 feet; however, a handful of commercial buildings that were constructed before enactment of the ordinance are three-stories tall. In the "C" district, buildings may be built up to the front property line (typically, to the sidewalk). In the commercial area along Washington, Walnut, and Sand Streets, most commercial buildings do extend to the sidewalk line and most are two stories tall. As one moves away from these areas, commercial buildings often occupy buildings originally constructed as houses, or are situated on former residential lots. Such business buildings are located some distance (less than 30 feet, typically) off of the sidewalk line.

In the R-2 districts, residences may be 3 stories or 35 feet tall. They must have front and rear yards that are at least 20 feet deep and side yards that vary in width from 6 to 15 feet, depending on the height of the building.

Historic District Resources

An intensive survey of the district identified 313 buildings that contribute to its integrity, 122 that were considered to be non-contributing because of modifications and 174 that are currently considered non-contributing because of their age (i.e., they are less than 50 years old).

These resources are discussed, in detail, in the following pages. Photographs of many of the contributing buildings and structures are presented as well.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 3

Downtown Commercial District

Fronting on Walnut Street, and located at its intersection with Washington Street, one of the more elaborate buildings within the historic district is the McIntosh Building (JA-0010-0037). It represents the Classical Revival style in a commercial building. It illustrates the style with its elaborate cornice with a central cartouche with the date "1901" in the center and "J.A. McIntosh" in a panel below the cartouche flanked by paneled newel posts; the newel posts are also located at each end. Below the dentiled frieze are recessed divided glazed openings. The upper floor is divided by engaged brick pilasters with Ionic caps. The first floor has been covered with a metal veneer but the building overall retains its defining characteristics.

One of the more common styles for the commercial buildings in Ravenswood is the Commercial style. As the name implies this is a very simple style of architecture where form follows function. Commercial style buildings include: JA-0010-0038; JA-0010-0040; JA-0204; JA-0218; JA-0219; JA-0231; JA-0235; JA-0240; JA-0296; and JA-0297.

Located on Washington Street, JA-0010-0044 is an example of an Art Deco Style commercial building. It illustrates the style through its flat roof, the horizontal lines of the primary and secondary cornices, and especially with the brick accents on the upper floor between the windows.

There is also one Second Empire Style commercial building (JA-0010-0045, ca. 1890) within the historic district although it was built originally as a residence. Located on Washington Street, historically, the building was used as a hospital and is currently a dentist's office. The Second Empire style was typically used in the mid to late 19th century and was prevalent in river towns although it was usually a residential style. The style is illustrated through the mansard roof with dormers on the lower slope, the bracketed eave and often, arched windows with keystones.

One Washington Street commercial building within the historic district is Neo-Classical Revival (JA-0010-0051, ca. 1900). The style is illustrated through the large primary cornice with modillions and the heavy jack arches with large keystones over the vertically divided windows on the upper story. The three storefronts on the first floor have been modified through the years to suit the tenants but the building retains its character defining elements.

The remaining commercial buildings include Enframed Block, One Part Commercial Block, Two Part Commercial Block and modern buildings. These describe the configuration of the building overall rather than a style.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 4

One of the oldest commercial buildings within "Old Town" is the Victoria Inn (JA-0010-0031, ca. 1865). The building originally had a shallow hip roof but it currently has a gable roof over both portions of the building; the building was built in two sections. It served many people when the railroad was booming and it is located on Broadway Street, facing the railroad tracks.

Churches

There are five churches within the historic district and three of the five are Gothic Revival style. The five churches are the First Christian Church (JA-0122, c. 1895); the First Baptist Church (JA-0176, c. 1876); the Grace Episcopal Church (JA-0187, c. 1900); Our Savior Evangelical Lutheran Church (JA-0199, c. 1928) and the First Presbyterian Church (JA-0010-0068, c. 1850).

Community Building / NYA Hall

There is a unique building within the historic district, the Ravenswood Community Center (JA-0177 and JA-177A), located at 212 Henrietta Street. It was constructed by the National Youth Administration, a program under the "New Deal" program of Franklin Delano Roosevelt during the Great Depression.

The "NYA Hall" was built in 1938 in the Art Deco Style with the cooperation of the City of Ravenswood and the program was geared towards employing younger adults. At some point, it was connected to the McIntosh House via an elevated, brick hyphen. The McIntosh House was built c. 1890 and is Colonial Revival style.

Structures of Note

There are two structures located within the historic district. One is the Ohio River Rail Road bridge/trestle that spans Sandy Creek (JA-0010-0004, ca. 1885). The other is the bridge spanning Sandy Creek along State Route 68/Washington Street (JA-0293, 1953). These are the only two structures within the survey boundaries.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 5

Residential Properties

The residences within the historic district reflect the time period of significance, mid 19th century to mid 20th century, and the architectural styles and house types of the period. The oldest known residence in the historic district is the Fitzhugh House (JA-0010-0011, c. 1830), located at 18 Walnut Street. It is representative of the Greek Revival style and the only Greek Revival style building within the historic district.

Late 19th century architectural styles are represented within the historic district by Queen Anne, Queen Anne Cottage, Folk Victorian, Italianate and Second Empire styles.

Revival style architecture is represented within the historic district with Colonial Revival, Dutch Colonial Revival and Tudor Revival styles. These styles date to the early 20th century.

There are also residences within the historic district that represent the architectural styles and house types of the teens and twenties of the early 20th century. These styles and types include Craftsman Four Square, Craftsman Bungalow and Craftsman.

The mid 20th century is represented by a few homes within the historic district that are Ranch types and Modern styles. In addition to true architectural styles, there are house types and plans that are "Vernacular" in nature, regional architecture. These types include "I" houses, Side Gable Cottage, One-story cube, Gable-Front houses, and Gabled-Ell houses. Gable-Front and Gabled-Ell houses are the most numerous within the historic district.

Contributing, Non-Contributing and National Register Resources within the District

In the following descriptions, outbuildings are denoted "A", "B", "C", etc. and are also classified as to whether they contribute to the district, are non-contributing resources or are part of a property already listed on the National Register.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 6

JA-0010-0001. (171425) 6 1/2 WALNUT STREET, commercial
Randolph Building/Caldwell Building

date: 1907

description: Three-story, flat roof, commercial warehouse building. Stone roof cap. Rock-faced concrete block façade and foundation. Vertical 2/2 windows with smooth stone lintels and sills on the upper stories. Arched transoms windows on the first floor; openings have been infilled at the top with wood. Diagonal corner entrance. Plaque on the side of the building marks the height of the 1937 flood. Romanesque style. 4 X 5 bays. One Contributing building.

JA-0010-0002. (171423) 115 BROADWAY STREET, residential

Bogess House

date: c. 1915

description: One-story, front facing "L" house. Asphalt shingle roof. Exposed concrete block end chimney. Vinyl siding. Modern 1/1 windows. One-story, shed roof, front porch with square paired posts with "X" work between the posts on a concrete deck. Faux stone veneer covers foundation. 3 X 3 bays. Side Gable Cottage. One Contributing building.

JA-0010-0003. (171420) 10 SAND STREET, residential

Campbell House

date: c. 1920

description: Two-story, side gable house with central large end gable dormer on the front. Exposed rafter tails on dormer; knee braces on dormer and in gable ends. Asphalt shingle roof. Engaged red brick end chimney. Vinyl siding. Modern 1/1 windows. One-story, shed roof, full length, front porch with square brick columns and an enclosed brick balustrade with concrete cap; stucco panels in balustrade. Large wood cap at the top of the brick columns that have scrolled edges. Rock-faced concrete block foundation. 3 X 4 bays. Craftsman Bungalow style. One Contributing building.

A.

date: c. 1920

description: Large two-story, hip roof garage/apartment. Asphalt shingle roof. Asbestos shingle siding on second floor; concrete block and red brick on first floor. Novelty windows. Second floor overhangs first on the front and has knee braces. Concrete block foundation. 3 X 4 bays. One Contributing building.

JA-0010-0004. SAND CREEK, railroad trestle

Ohio River Rail Road bridge

date: c. 1885

description: Ohio River Rail Road bridge/trestle over Sandy Creek. Steel Pratt-through truss. One Contributing structure.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 7**JA-0010-0005. (181436) 38 SAND STREET, residential**date: c. 1840description: Two-story, end gable house. Asphalt shingle roof. T-111 siding. 1/1 and multi-paned windows. One-story, modified hip roof, wraparound front porch: right side of porch has been enclosed; remainder has turned posts with brackets and Eastlake vergework. It also appears as if some of the windows have been completely covered over. One-story, shed roof, rear porch with square posts. Stone foundation. 1 X 3 bays. Gable-Front house. Modified. One Non-Contributing building.**A.**date: Moderndescription: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 1 X 1 bays. One Non-Contributing building.**JA-0010-0006. (181437) 104 SAND STREET, residential****Pinder House**date: c. 1910description: One and one-half-story, side gable house. Central interior brick chimney. Standing seam metal roof. Aluminum siding. Modern 1/1 windows. One-story, flat roof metal canopy on the front supported by wrought iron posts and railing on a concrete deck. One-story, shed roof, full length, enclosed rear porch. Rock-faced concrete block foundation. 3 X 3 bays. Side Gable Cottage. One Contributing building.**JA-0010-0007. (181438) 116 SAND STREET, residential****Abel House**date: c. 1900description: Two-story, side gable house with central end gable dormer on the front. New metal roof. Engaged brick and terra cotta block end chimney. Aluminum siding. Modern 1/1 windows with shutters. One-story, modified hip roof, three-quarter length, front porch with battered square columns on an enclosed terra cotta block balustrade with concrete cap. Addition on side. Block foundation. 3 X 2 bays. Craftsman Bungalow style. One Contributing building.**JA-0010-0008. (171426.2) 102 RACE STREET, residential****Gould Apartment House**date: c. 1955description: Two-story, shallow hip roof apartment house with four units. Asphalt shingle roof. Stucco façade and foundation. Metal casement windows. Small shed roof metal canopy over entrance. 5 X 2 bays. Modern style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 8

JA-0010-0009. (171427.2(A) 115 RACE STREET, residential **Mullins/Queen House**
date: c. 1920

description: Two-story, end gable house. Asphalt shingle roof. Knee braces in gable ends. Glazed terra cotta block façade. Rock-faced concrete block belt course separates floors. Vertical 3/1 and 1/1 windows. One-story, hip roof, three-quarter length front porch with square brick columns and wrought iron railing. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman style. One Contributing building.

JA-0010-0010 is M65.

JA-0010-0011. (171426) 18 WALNUT STREET, residential **Merritt/Fitzhugh House**
date: c. 1830

description: Very large two-story, cross hipped roof house. Rear portion of house is log on the first story. Asphalt shingle roof. Large scrolled brackets. Vinyl siding. Original siding had corner boards with large caps – still can be seen. Original 6/6, 6/9 and novelty windows with leaded glass transom/upper sash. Entrance door has divided transom and sidelights. One-story, end gable entrance porch with modern Doric columns on a wood deck; side and rear porch the same. One-story, shed roof, enclosed wing on rear. Cut stone and concrete block foundation. Greek Revival style. One Contributing building.

JA-0010-0012. (161219) 204 RACE STREET, residential **Barbe House**
date: c. 1921

description: Twin to 214 and 208 Race Street. Two-story, clipped gable house with shed roof dormers. Exposed red brick chimney on the rear. Standing seam metal roof. Red brick façade. Modern 1/1 windows with shutters and smooth concrete lintels and sills; paired on the front. One-story, modified hip roof, full length, front porch with square brick columns and enclosed brick balustrade with concrete caps. Non-original one-story, end gable addition on rear with vinyl siding. Concrete foundation. 2 X 3 bays. Gable Front house. One Contributing building.
A.

date: Modern

description: One-story, gambrel roof outbuilding. Asphalt shingle roof. T-111 siding. Concrete block pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0010-0013. (161218) 208 RACE STREET, residential **Hunt House**
date: c. 1921

description: Twin to 214 Race Street, next door. Large two-story, clipped gable roof house with shed roof dormers. Asphalt shingle roof. Engaged corbelled red brick end chimney. Red

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 9

brick façade. Modern 1/1 windows with smooth concrete lintels and sills; many are paired. One-story, modified hip roof, three-quarter length, front porch with square brick columns and an enclosed brick balustrade with concrete cap. Concrete foundation. 3 X 2 bays. Gable Front house. One Contributing building.

A.

date: Modern

description: One-story, hip roof outbuilding. Asphalt shingle roof. Vinyl siding. 1/1 windows. 3 X 1 bays. One Non-Contributing building.

JA-0010-0014. (161217) 214 RACE STREET, residential

Titus House

date: c. 1921

description: Large two-story, clipped gable roof house with hip dormers. Asphalt shingle roof. Red brick façade. Modern 1/1 windows with smooth concrete lintels and sills. One-story, modified hip roof, three-quarter length, front porch with square brick columns and an enclosed brick balustrade with concrete cap. Concrete foundation. 3 X 3 bays. Gable Front house. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Metal roof. Metal siding. 1 X 1 bays. One Non-Contributing building.

JA-0010-0015. (161216) 220 RACE STREET, residential

Miller House

date: c. 1890

description: Large two-story, hip gable roof house. Two interior corbelled red brick chimneys. Standing seam metal roof. Brackets and dentils in frieze area. Scrolled brackets with dropped finials at the corners of the gable bays. Red brick façade. Herringbone board and batten siding in gable ends. 1/1 and picture windows with leaded glass headers and rusticated stone lintels and sills. One-story, modified hip roof, wraparound porch has been enclosed with brick and multi-paned windows. Stone foundation. 2 X 1 bays. Queen Anne style. One Contributing building.

A.

date: c. 1915

description: Tall one-story, end gable garage. Corrugated metal roof. German siding with frieze and corner boards. Vertical 2/2 windows. Stone foundation. 1 X 1 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 10

JA-0010-0015. (161216) 220 RACE STREET, residential (*continued*)

B. also assigned stand-alone designation JA-0010-0030.

date: c. 1910

description: One-story, flat roof, commercial building with stepped parapet on the sides. Concrete roof cap. Rock-faced concrete block façade and foundation. Diagonal corner entrance with large display window with transom on front. 2 X 2 bays. One Contributing building.

JA-0010-0016. (161241) 205 RACE STREET, residential

Litton House

date: c. 1900

description: Broad one-story, hip roof house with gable dormers. Asphalt shingle roof. Gable dormers have fish scale shingle siding. Vinyl siding. Wood 1/1 windows with shutters; tripartite on front. Wraparound porch within roof overhang has modern Doric columns on a wood deck. Stone foundation. Queen Anne Cottage style. One Contributing building.

JA-0010-0017. (161240) 215 RACE STREET, residential

(Old Funeral Home)

date: c. 1930

description: One-story, end gable house. Metal roof. Vinyl siding. Multi-paned windows. One-story, end gable, front porch with square brick columns on an enclosed brick balustrade; left side of porch is enclosed. Concrete block foundation. 2 X 2 bays. One Non-Contributing building.

JA-0010-0022. (151231) 235 RACE STREET, commercial

The Carpet Shop/Creamery Building

date: c. 1915

description: One-story, end gable, commercial building with front, stepped parapet wall. Concrete roof cap. Metal on front portion of roof; asphalt shingles on rear section. Wooden ventilators on roof. Brick veneer on front; concrete block elsewhere. Central flush entrance door flanked by display windows. Concrete block foundation. 3 X 10 bays. Modern style. One Contributing building.

JA-0010-0023. (151228) SYCAMORE STREET, residential

Clark House

date: c. 1910

description: One-story, hip roof house. Metal roof. Clapboard siding with wide frieze and corner boards. Vertical 2/2 windows. One-story, modified hip roof, three-quarter length, front porch with turned posts with spoked brackets and an enclosed rock-faced concrete block balustrade. Small gable hyphen connects house to a one-story, end gable cellar house of rock-

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 11

faced concrete block. Stone foundation. 4 X 3 bays. Queen Anne Cottage style. One Contributing building.

JA-0010-0024. (151212) 232 ½ RACE STREET, residential Poston/Murray House

date: c. 1850

description: Large two-story, front facing "L" house. Asphalt shingle roof. Clapboard siding with frieze and corner boards. Wood 1/1 windows. One-story, shed roof, entrance porch with wrought iron posts – non-original. Original porch was two stories. One-story, shed roof, side porch with wrought iron posts. One-story, shed roof, enclosed rear porch. Stone foundation. 3 X 3 bays. "I" house. One Contributing building.

A.

date: c. 1925

description: Two-story, side gable garage/apartment. Asphalt shingle roof. German siding on the second floor; terra cotta block first floor and foundation. Vertical 3/1 and metal casement windows. 3 X 1 bays. One Contributing building.

B.

date: c. 1925

description: Two-story, end gable garage/cellar house. Asphalt shingle roof. Terra cotta block façade. Rock-faced concrete block foundation. 1 X 1 bays. One Contributing building.

JA-0010-0025. (151213) 226 RACE STREET, residential Mullins House

date: c. 1850

description: Two-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern multi-paned 6/1 windows. One-story, modified hip roof, three-quarter length, front porch with slender square posts with scroll brackets and an enclosed rock-faced concrete block foundation. Stone foundation. 2 X 2 bays. Craftsman Four Square type. One Contributing building.

JA-0010-0027. (151211) MULBERRY STREET, vacant Old Institute Building

date: c. 1850

description: One-story, end gable building with one-story, shed roof addition on the front that wraps around to the side. Garage bay in front addition. "V" seam metal roof. Asphalt shingle siding. Vertical 2/2 windows. One-story, shed roof, enclosed rear wing. Brick foundation. 2 X 4 bays. Gable Front building. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 12

JA-0010-0028. (15128) 220 BROADWAY STREET, residential Poston/Murray House
date: c. 1870

description: Two-story, side gable house. Asphalt shingle roof. Clapboard siding with frieze and corner boards with caps. Vertical 2/2 windows with simple surrounds and shed roof metal canopies. One-story, modified hip roof, three-quarter length, front porch with square rock-faced concrete block posts on an enclosed rock-faced concrete block balustrade with caps. Block foundation. 3 X 1 bays. "I" house. One Contributing building.

A.

date: c. 1930

description: One-story, end gable storage building/apartment. "V" seam metal roof. Terra cotta block façade on the sides and rear; weatherboard siding and brick corners on the front. One-story, metal roof over entrance with wrought iron posts on a concrete deck. Terra cotta block foundation. 2 X 1 bays. One Contributing building.

JA-0010-0029. (151210) 224 BROADWAY STREET, commercial/ residential
Poston Building

date: c. 1915

description: Two-story, flat roof, commercial building converted to residential use. Corbeled brick primary cornice. Brick pilasters separate bays on first and second floor. Red brick façade on front; terra cotta tile elsewhere. Modern 1/1 windows. First floor storefront converted to residential entrance. One-story, shed roof, metal canopy/front porch with slender metal posts and lattice balustrade. Rock-faced concrete block foundation. 3 X 1 bays. Two-part commercial block type. One Contributing building.

JA-0010-0030 is an outbuilding and included as the "B" building with JA-0010-0015.

JA-0010-0031. (161214) 220 BROADWAY STREET, residential/commercial
Chovanec Building/Victoria Inn/Alpine Hotel

date: c. 1865

description: Long two-story, side gable house/boarding house/restaurant. Left side of building appears to be the original portion with the right side added later. Left side has metal roof; right side has asphalt shingle roof. Vinyl siding on all. Left side has wood 1/1 windows; right side has infilled the window openings with board, siding and smaller modern 1/1 windows. One-story, shed roof metal canopy over first floor with wrought iron posts. Covered foundation. 9 X 1 bays. "I" house. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 13

JA-0010-0032. (161215) 212 BROADWAY STREET, residential Owens House
date: c. 1910

description: Large two-story, end gable house/duplex. Interior corbelled red brick chimney. Roll roofing. Exposed rafter tails. Knee braces in the gable end. German siding with frieze and corner boards. Original 6/6 windows. One-story, modified hip roof, three-quarter length front porch with battered square columns on an enclosed parged balustrade. One-story, rear porch with square posts and slatted balustrade. Rock-faced concrete block water table and foundation. 4 X 3 bays. Gable Front house. One Contributing building.

JA-0010-0033. (16149) 20 BROADWAY STREET, residential Perrine House
date: c. 1910

description: Two-story, hip roof house. Standing seam metal roof. Two interior corbelled brick chimneys. Clapboard siding with wide frieze and corner boards. Vertical 2/2 windows. One-story, modified hip roof, full length, front porch with square posts on an enclosed concrete block balustrade. One-story, shed roof, entrance porch on the side. Block foundation. 2 X 2 bays. Craftsman Four Square type. One Contributing building.

A.

date: Modern

description: Two-story, gambrel roof garage/barn. Asphalt shingle roof. Vertical board siding on the second floor; concrete block first floor and foundation. 2 X 2 bays. One Non-Contributing building.

JA-0010-0034. (16147) 209 WATER STREET, residential Mace House
date: c. 1885

description: Large two-story, cross hipped roof house. Two interior corbelled red brick chimneys. Metal roof. Clapboard siding with frieze and corner boards. 1/1 windows. One-story, shed roof, front porch with slightly battered square columns on an enclosed balustrade. One-story, enclosed rear porch. Stone foundation. 4 X 3 bays. Gable- Ell house. One Contributing building.

A.

date: c. 1925

description: One-story, end gable garage. Corrugated metal roof. Terra cotta block façade. Molded concrete block foundation. 1 X 1 bays. One Contributing building.

JA-0010-0035. (111440) 200 SAND STREET, residential Stone House
date: c. 1890

description: Two-story, hip gable roof house. Asphalt shingle roof. Two interior brick chimneys. Wood shingles and diamond-shaped window in gable end. Vinyl siding. Modern 1/1

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 14

and novelty windows; novelty windows have leaded glass transoms. One-story, modified hip roof wraparound porch with square posts and slatted balustrade. One-story, shed roof, enclosed entrance bay on the side. One-story, shed roof, enclosed rear porch. Stone, rock-faced and molded concrete block foundation. 4 X 3 bays. Queen Anne style. One Contributing building.
A.

date: c. 1890

description: Two-story, end gable cellar house. Asphalt shingle roof. Rock-faced and molded concrete block façade and foundation. 1/1 windows on upper floor with rock-faced concrete block lintels and sills. 2 X 2 bays. One Contributing building.

JA-0010-0036. (141429) 103 WASHINGTON STREET, residential Yencha House

date: c. 1900

description: Two-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, front porch with Tuscan posts on an enclosed shingled balustrade. One-story, shed roof, enclosed and extended rear porch. Stone pier foundation. 3 X 2 bays. Gable-Front house. One Contributing building.

JA-0010-0037. (141280) 206 WALNUT STREET, commercial J.A. McIntosh Building

date: 1901

description: Large two-story, flat roof, commercial, corner building. Stone roof cap. Stepped parapet on the side; decorative parapet on the front with a central cartouche with "1901" on it. Front parapet has corner paneled newel posts with "X" balustrade and below the date is "J.A. McIntosh." Dentiled frieze below that. Front parapet and frieze is stone. Small divided windows below primary cornice. Red brick façade. Brick pilasters with Ionic caps divide second story on front. Recessed brick panels above second floor windows; windows have been infilled with wood and smaller modern windows. Windows have smooth stone lintels and sills. First floor has been covered with a metal veneer and a modern storefront. Stone and brick foundation. 3 X 6 bays. Classical Revival style. One Contributing building.

**JA-0010-0038. (131268) 201 WASHINGTON STREET, commercial
Gino's Pizza/Knights of Pythias Hall**

date: c. 1910

description: Three-story, flat roof, commercial building on a corner lot. Stepped parapet on the sides. Corbeled brick and stone primary cornice with two arched louvers above with stone sills. Red brick façade with brick quoins. Upper story windows are wood 1/1 with rusticated lintels and smooth sills: third floors window openings have been infilled with brick; second floor

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 15

windows have smooth stone sill course. Transom area of first floor infilled with siding. Non-original metal canopy over first floor; wraps to the side. First floor covered with non-original brick veneer and has arched window openings and a diagonal corner entrance. Upper story windows on the sides are arched. Brick foundation. 3 bays wide. Commercial style. One Contributing building.

JA-0010-0039. (131267) 205 WASHINGTON STREET, commercial

T. Stone & Company

date: c. 1910

description: One-story, flat roof, commercial building with parapet wall on the front. Faux stone veneer on the front with a modern storefront. Remainder of building is painted brick. Brick foundation. 1 bay wide. Modern style. Modified. One Non-Contributing building.

JA-0010-0040. (131265) 217 WASHINGTON STREET, commercial Ike's Recreation

date: c. 1910

description: Two-story, flat roof, commercial building with stepped parapet on the sides. Concrete roof cap. Corbeled brick primary cornice with brick louvers below. Wood 1/1 windows on the second floor with brick lintels and sills. Tan brick façade. First floor covered with metal veneer and has central recessed aluminum storefront. Brick foundation. 4 bays wide. Commercial style. One Contributing building.

JA-0010-0041. (131264) 219 WASHINGTON STREET, commercial

Riverbend Antique Mall

date: c. 1945

description: One-story, flat roof, commercial building. Concrete roof cap. Red brick façade. Flat roof metal canopy runs the length of the building. Two recessed storefronts; aluminum framing for all. Brick kickpanels. Brick foundation. 1 bay wide. Modern style. One Contributing building.

JA-0010-0042. (131263) 225 WASHINGTON STREET, commercial

Frontier Furniture & Carpet

date: c. 1950

description: One-story, flat roof, commercial building. Concrete roof cap. Red brick façade. Recessed double entrance doors with flanking display windows and metal kickpanels; right side of storefront has single display window. Brick foundation. 1 bay wide. Modern style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 16**JA-0010-0043. (131261) 231 WASHINGTON STREET, commercial****Top Notch Hair**date: c. 1950description: One-story, flat roof, commercial building – very small. Metal panel with signage in transom area. Flush aluminum framing center storefront. Concrete foundation. 1 bay wide. Modern style. One Contributing building.**JA-0010-0044. (131260) 235 WASHINGTON STREET, commercial****Affectionately Yours Floral & Gift Shop**date: c. 1925description: Two-story, flat roof, commercial building. Concrete roof cap. Corbeled brick primary cornice. Blonde brick accents with corbelling and corbelled brick dentils on the second floor with recessed brick panels. Modern fixed pane windows on the second floor with decorative brick belt course as a lintel and smooth concrete sill course. Three modern storefronts on the first floor with aluminum framing. Concrete foundation. 6 bays wide. Art Deco style. One Contributing building.**JA-0010-0045. (121258) 255 WASHINGTON STREET, commercial****Family & Cosmetic Dentistry/Priddy Hospital/Moore Home**date: c. 1890description: Large two and one-half-story, mansard roof building with arched dormers. Dormers have end brackets and vertical 2/2 arched windows. Asphalt shingle roof. Two red brick interior chimneys. Wide frieze board with brackets and modillions. Red brick façade. Vertical 2/2 arched windows with arched brick hoods with keystones and smooth stone sills. One-story, shed roof, enclosed porch/entrance. Stone water table course. Stone foundation. 3 X 2 bays. Second Empire style. One Contributing building.**JA-0010-0046 is M48.****JA-0010-0047 is M64.****JA-0010-0048. (171427(B-F) 122-130 WASHINGTON STREET, commercial****Miller/Ryder Building**date: c. 1910description: One-story, flat roof, commercial building with five storefronts and stepped parapet on the sides. Corbeled brick primary cornice. Brick pilasters with corbelled caps separate the

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 17

bays/storefronts. Brick louvers in the cornice area. Brick façade. Four out of the five storefronts are flush with aluminum framing. The last storefront on the south/corner is a recessed bay with display windows only; the corner bay has been parged. 5 bays wide. One-part commercial block type. One Contributing building.

JA-0010-0049. (171427(A) 100 WASHINGTON STREET, commercial**Proctor Building**date: 1956

description: Two-story, flat roof, commercial building. Overhanging ridged metal roof cap. Red brick façade. Metal horizontal 2/2 windows on the second floor; ribbon. Recessed entrance on side and on front with aluminum framing. Ridged metal canopy as a secondary cornice. Concrete foundation. 3 X 3 bays. Moderne style. One Contributing building.

JA-0010-0050. (161250) 202 WASHINGTON STREET, commercial**Diane's Beauty Salon**date: c. 1905

description: Two-story, flat roof, commercial building. Stone roof cap. Primary brick cornice with brick brackets, corbelling and brick crosses within recessed brick panels. Second floor windows are round-headed 1/1 with smooth sills. Painted brick façade. Central recessed storefront entrance with flanking display windows and brick kickpanels. Transom area covered with painted wood. Stone foundation. 3 bays wide. Italianate Commercial style. One Contributing building.

JA-0010-0051. (161249) 204-208 WASHINGTON STREET, commercial**SoSo Collectibles/The Wiz**date: c. 1900

description: Two-story, flat roof, commercial building with concrete cap. Wood primary cornice with modillions. Vertical 4/1 windows on the second floor with smooth concrete lintels with keystones and smooth concrete sills. Terra cotta block façade on second floor. Three storefronts on the first floor: all have been covered with modern veneers; the two storefronts on the right have central recessed entrance doors. Concrete block foundation. 7 bays wide. Neoclassical Revival style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 18

**JA-0010-0052. (161248) 220 WASHIGNTON STREET, commercial
Miller Building/S&B Computers**

date: 1957

description: Two-story, flat roof, commercial building. Parapet wall on the front with concrete cap; terra cotta tile roof cap on the side. Concrete cartouche panel with "MILLER BUILDING" on the first line; "1957" on the second line. Parged concrete block façade with brick veneer on the front. Metal horizontal 2/2 windows on the second floor. Flat roof canopy on first floor. Flush aluminum framing entrance system on first floor. 2 X 4 bays. Two-part commercial block type. One Contributing building.

**JA-0010-0053. (161247) 222 WASHINGTON STREET, commercial
All Star Sporting Goods**

date: c. 1955

description: Small one-story, flat roof, commercial building. Metal roof cap. Brick façade. Modern metal storefront entrance with flush entrance door and display window. 1 bay wide. One-part commercial block type. One Contributing building.

**JA-0010-0054. (161246) 224 WASHINGTON STREET, commercial
Icenhower Building**

date: c. 1910

description: Two-story, flat roof, commercial building. Simple primary cornice with scroll brackets. Vinyl siding on second floor. Metal casement windows on second floor. Bubble awning over first floor. Central display windows flanked by entrance doors on first floor. Brick end pilasters. Brick foundation. 2 bays wide. Italianate Commercial style. One Contributing building.

**JA-0010-0055. (161243) 234 WASHINGTON STREET, commercial
First Federal Savings & Loan Association**

date: c. 1930

description: Actually two buildings that have been combined into one business. Building on the left is a one-story, flat roof, commercial building with steeped parapet on the front. Painted brick façade. Modern aluminum storefront framing and metal veneer kickpanels. Building on the right is a tall one-story, flat roof, commercial building with stepped parapet on the front with central gable pediment. Concrete roof cap. Decorative louver in gable end. Primary brick cornice with brick accents. Painted brick façade. Flush entrance door with sidelights and large

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 19

display window. Rear one-story, concrete block addition. Brick foundation. One-part commercial block type. One Contributing building.

JA-0010-0056. (161242) 236 WASHINGTON STREET, commercial

Physical Therapy Providers

date: c. 1955

description: One-story, flat roof, commercial building. Upper portion of building covered with stucco panels. Flat roof metal canopy covered with stucco runs the length of the building. Blonde brick façade. Double entrance door recessed entrance with large display window area. Concrete foundation. 5 bays wide. One-part commercial block type. One Non-Contributing building.

JA-0010-0057. 238 WASHINGTON STREET, commercial

Almeda's Music & Photo Center

date: c. 1890

description: Three-story, end gable, commercial building with stepped parapet wall on the front. Corbeled brick cornice with corbelled brick brackets. Red brick façade on upper stories; painted on second story. Round-headed vertical 2/2 windows on the third floor with smooth stone sills; second story windows are arched vertical 2/2 with painted stone sills and brick arched hoods. Metal canopy over first floor. First floor covered in veneer and has non-original aluminum framed entrance. One-story, concrete block addition on rear. Stone foundation. 3 bays wide. Italianate Commercial style. Faded mural on the Mulberry Street elevation. One Contributing building.

JA-0010-0058. (141281) 208 WALNUT STREET, commercial

Murray Building

date: c. 1905

description: Two-story, flat roof, commercial building. Stone roof cap. Corbeled brick primary cornice. Second floor windows are wood 1/1 with smooth stone lintels and sills. Red brick façade. First floor covered with wood veneer and a residential style entrance door and window with shutters. Stone foundation. 1 bay wide. Two-part commercial block type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 20

JA-0010-0059. (141282) 212 WALNUT STREET, municipal Ravenswood City Hall

date: c. 1905

description: Two-story, flat roof, commercial building. Brick façade. Multi-paned windows. Flush aluminum framing entrance doors. Concrete foundation. 4 bays wide. One Non-Contributing building.

JA-0010-0060. (141283) 216-222 WALNUT STREET, commercial Staats Building

date: c. 1890

description: Two-story, flat roof, commercial building. Terra cotta tile roof cap. Interior chimney. Red brick façade. Second floor on front completely covered with wood shingles. Modern multi-paned windows on the second floor. Three recessed storefronts on the first floor: far left has arched transom over entrance door; far right has double entrance doors; all have paneled kickpanels. Windows on the side have rusticated stone lintels and smooth stone sills. Brick foundation. 3 bays wide. Two-part commercial block type. One Non-Contributing building.

JA-0010-0061. (131269) 213 WALNUT STREET, commercial Tidd Building

date: c. 1940

description: Very small one-story, flat roof, commercial building. Modern aluminum storefront with brick kickpanel. Boxed-in awning/roof over storefront. Brick foundation. 1 bay wide. Modern style. Modified. One Non-Contributing building.

JA-0010-0062. (131270) 217 WALNUT STREET, commercial

Slayton Building/Jackson County Bank

date: c. 1910

description: Two-story, flat roof, commercial building with stepped parapet on the front with brick corner newels. Terra cotta tile roof cap. Tan brick veneer on the front; red brick elsewhere. Modern 1/1 windows on the second floor. Paired wood 1/1 windows in cornice area with brick sill. Corbeled brick primary cornice. Corbeled brick secondary cornice with "Jackson County Bank" etched into the limestone frieze below. Limestone pilasters with caps and plinths define first floor openings. Flush double entrance doors flanked by display windows that have been partially infilled with glass block. Stone foundation. 3 bays wide. Enframed Block type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 21

**JA-0010-0063. (131276) 219 WALNUT STREET, commercial
Hupp's Ice Cream/Nowell Block**

date: c. 1910

description: Two-story, flat roof, commercial building with central end gable pediment with scroll end brackets and "Nowell Block" enscribed between the brackets. Parapet wall below that with recessed brick panels flanked by narrow brick pilasters. Interior corbelled brick chimney. Overhanging metal primary cornice with dentils, modillions and panels in the frieze area. Blonde brick façade. Modern 1/1 windows on the second floor with rusticated lintel and sill course. Simple secondary cornice with steel lintel below. Stone pilasters on the first floor. Entrance door to the upper floor on the right has limestone surround with keystone and fanlight over entrance. Main entrance recessed single door flanked by display windows with transom and brick kickpanels; all glazing has been painted over. Stone foundation. 2 bays wide. Classical Revival style. One Contributing building.

**JA-0010-0064. (131279) 206 VIRGINIA STREET, commercial
Rymer Building**

date: c. 1955

description: Semi-circular one-story, flat roof, commercial building with wood shingled mansard roof/canopy. Red brick façade. Modern fixed pane windows; some with a panel above – all have shutters. Aluminum framed entrance doors. Concrete foundation. 4 bays wide. One-part commercial block. One Non-Contributing building.

**JA-0010-0065. (131278) 208 VIRGINIA STREET, commercial
Lovell Building/Dojo/IOOF Building #15**

date: c. 1850

description: Very large end gable, commercial building with two-story, shed roof addition on the south. Metal roof. Asbestos shingle siding on the front; clapboard siding on the sides with wide frieze and corner boards. 1/1 wood windows with simple surrounds on the second floor. Addition has two entrance doors divided by vertical 2/2 windows on the first floor. End gable portion has central recessed entrance flanked by display windows and vertical board kickpanels. Stone foundation. 5 X 4 bays. Gable-Front building. One Contributing building.

JA-0010-0066. (131274) 224 VIRGINIA STREET, residential

Robinson House

date: c. 1905

description: Two-story, hip roof house with hip dormers. Dormer has fish scale shingle siding and a long multi-paned window. Asphalt shingle roof. Exposed corbelled brick and terra cotta

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 22

block end chimney. Red terra cotta block façade. Original multi-paned windows with smooth concrete lintels and sills; lintels are painted. One-story, end gable, three-quarter length, front porch with square blonde terra cotta block end columns on brick piers and square wood columns on brick piers frame the entrance; enclosed terra cotta block balustrade with concrete cap; gable end of porch has fish scale shingles. Concrete water table course. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

A.

date: c. 1925

description: Two-story, end gable apartment building. Asphalt shingle roof. Blonde terra cotta block façade and foundation. Modern side by side windows with smooth concrete sills. Metal canopy over entrance. 2 X 1 bays. One Contributing building.

JA-0010-0067. (131273) 230 VIRGINIA STREET, residential

Grimmett House

date: c. 1910

description: One-story, hip roof house with shallow hip dormer on the front. Exposed rafter tails on the dormer and on the main roof. Standing seam metal roof. Exposed painted stone end chimney. Very wide frieze board is covered with wood shingles. German siding with frieze and corner boards. Original 1/1 and multi-paned windows with simple surrounds. Corner porch within roof overhang has square post on an enclosed balustrade. Rock-faced concrete block pier foundation. 2 X 3 bays. Craftsman Bungalow style. One Contributing building.

JA-0010-0068. (131272) 238 VIRGINIA STREET, church

First Presbyterian Church/Church of God

date: c. 1850

description: One-story, end gable church building. Asphalt shingle roof. German siding with wide frieze and corner boards. Central arched entrance with arched stained glass transom with keystone, simple surround and double paneled entrance doors. The central entrance is flanked by stained glass arched windows with keystones and simple surrounds. Same windows on the sides. Basement entrance on the side. Stone foundation. 3 X 2 bays. Classical Revival style. One Contributing building.

JA-0010-0071. (141288) 126 VIRGINIA STREET, residential

Nelson House

date: c. 1915

description: Two-story, side gable house with large central end gable dormer on the front. Asphalt shingle roof. Exposed rafter tails on dormer. Knee braces on dormer and in gable ends. Dormer has asbestos shingle siding. Stucco façade and foundation. Modern 1/1 windows;

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 23

shutters in dormer. One-story, shed roof, full length, front porch within roof overhang with square stucco columns on an enclosed stucco balustrade. 2 X 2 bays. Craftsman Bungalow type. Shares a garage with JA-0010-0072. One Contributing building.

JA-0010-0072. (141431) 118 VIRGINIA STREET, residential

Stratton House

date: c. 1920

description: Two-story, side gable house with central, end gable dormer on the front and a central, shed roof dormer on the rear. Exposed rafter tails. Knee braces on the dormers and in the gable ends. Asphalt shingle roof. Stucco façade. Wood 1/1 windows with brick lintels and smooth concrete sills. One-story, full length, front porch within the roof overhang has large square stucco columns on an enclosed stucco balustrade. Rock-faced concrete block foundation. 2 X 3 bays. Craftsman Bungalow type. Shares a garage with JA-0010-0071. One Contributing building.

A.

date: c. 1920

description: One-story, side gable outbuilding. Asphalt shingle roof. Stucco façade and foundation. 2 X 1 bays. One Contributing building.

B.

date: c. 1940

description: One-story, side gable garage. Asphalt shingle roof. Concrete block façade and foundation. 2 garage bays on the front. 2 X 1 bays. One Contributing building.

JA-0028. (11380) 215 WILSON STREET, residential

Lemasters House

date: c. 1910

description: Two-story, cross gable house with one-story addition on rear. Asphalt shingle roof. Partial return cornice. Gable dormer on front with scalloped shingles. Two-story, three-sided, projecting bay on front. Vinyl siding. 1/1 windows with simple surrounds with decorative garland in hood area. One-story, entrance porch within roof overhang with turned posts and spindled balustrade. Rock-faced concrete block foundation. 3 X 5 bays. Queen Anne style. One Contributing building.

A.

date: c. 1930

description: Two-story, gambrel roof garage with exterior stair on the side. Asphalt shingle roof. Vinyl siding. 1/1 windows. Concrete foundation. 1 X 2 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 24

JA-0029. (11381) 213 WILSON STREET, residential

Casto House

date: c. 1920

description: Two-story, hip roof house with two-story, projecting, square bay on the front. Asphalt shingle roof. Central, interior, corbelled brick chimney. Vinyl siding. 1/1 windows with shutters. Small, hip roof, entrance porch with square posts on a wood deck. Rock-faced concrete block foundation. 2 X 1 bays. One Contributing building.

A.

date: c. 1920

description: One-story, end gable outbuilding. Metal roof. Vertical board siding partially covered with asphalt shingle siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0030. (11382) 209 WILSON STREET, residential

Callahan House

date: c. 1925

description: One and one-half-story, hip gable roof house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Asbestos shingle siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch has been fully enclosed with windows and siding. Rock-faced concrete block foundation. 2 X 3 bays. Queen Anne Cottage style. district One Contributing building.

JA-0031. (11384) 205 WILSON STREET, residential

Simon House

date: c. 1925

description: One and one-half-story, end gable house with attached, shed roof, one story, one bay garage on left. Asphalt shingle roof. Asbestos shingle siding. 1/1 windows. One-story, modified hip roof, front porch enclosed with 6/6 windows and terra cotta block veneer; original open porch had square brick columns on an enclosed balustrade. One-story, shed roof, entrance bay attached to original porch. Rock-faced concrete block foundation. 3 X 1 bays. Gable-Front house. One Contributing building.

A.

date: c. 1925

description: One-story, side gable outbuilding. Asphalt shingle roof. Wide clapboard siding. Six pane, paired windows. Pier foundation. Exposed rafter tails. One Contributing building.

JA-0032. (11385) 203 WILSON STREET, residential

Mosser House

date: c. 1915

description: Two-story, hip roof house. Asphalt shingle roof. Asbestos shingle siding with wide frieze board. 1/1 windows with simple surrounds. One-story, modified hip roof, full length,

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 25

front porch with turned posts with scrolled brackets on an enclosed balustrade. One-story, gable, rear, enclosed porch. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman Four Square type. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Metal roof. Metal siding. Pier foundation. Pressed board garage doors. 1 X 1 bays. One Non-Contributing building.

JA-0033. (11386) 201 WILSON STREET, residential

Palmer House

date: c. 1915

description: One-story, hip gable roof house. Asphalt shingle roof. Central, interior, corbelled brick chimney. Partial return cornice. Asbestos shingle siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with Doric columns on an enclosed, scallop shingled balustrade. Rock-faced concrete block foundation. 3 X 3 bays. Queen Anne Cottage style. One Contributing building.

JA-0034. (11387) 719 WALNUT STREET, residential

Mullins House

date: c. 1920

description: Two-story, hip roof house with central, shallow hip dormer on the front. Asphalt shingle roof. Exposed, red brick chimney on side. Vinyl siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch has been fully enclosed with siding. One-story, side gable wing on left with shed roof, entrance porch. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman Four Square type. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, flat roof outbuilding covered with weatherboard siding and attached to an open car port supported by round metal poles on a concrete pad. Metal roof. One Non-Contributing building.

B.

date: Modern

description: One-story, end gable garage. Metal roof. Metal siding. Pressed board garage doors. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 26**JA-0035. (11388) 200 BEDFORD STREET, residential****Tillman/Carr House**date: c. 1915

description: Very large, two-story, hip gable roof house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Vinyl siding. 1/1 windows with simple surrounds and hoods and shutters; on the front the upper sash is smaller than the lower sash. Some novelty windows on the side. One-story, modified hip roof, full length, front porch with rock-faced concrete block square columns on an enclosed rock-faced concrete block balustrade. One-story, modified hip roof, rear, entrance porch is fully enclosed and has an attached hip roof entrance porch with wrought iron posts and railing. The other side of the rear of the house also has a one-story, modified hip roof, enclosed, rear porch. Rock-faced concrete block foundation. 4 X 4 bays. Queen Anne style. One Contributing building.

A.date: c. 1915

description: Two-story, jerkinhead roof garage. Asphalt shingle roof. Jerkinhead projects out over the front. Rock-faced concrete block façade and foundation. 6/6 windows. 1 X 2 bays. One Contributing building.

JA-0036. (11390) 206 BEDFORD STREET, residential**Staats House**date: c. 1925

description: Two-story, end gable house with shed roof dormers on each side. Interior, blonde brick chimney. Asphalt shingle roof. Gable ends and dormers have wood shingle siding; weatherboard siding elsewhere. 1/1 windows. One-story, hip roof, three-quarter length, front porch with exposed rafter tails and slightly battered square posts on a shingled balustrade. One-story, shed roof, one bay garage attached on the left; side of garage is wall of 9/9 fixed windows. One-story, shed roof, enclosed, rear porch with attached ADA ramp. Painted rock-faced concrete block foundation. 4 X 2 bays. Craftsman style. One Contributing building.

JA-0037. (11391) 208 BEDFORD STREET, residential**Spear House**date: c. 1915

description: One-story, hip gable roof house with large, one-story, gable addition on rear. Two, interior, corbelled brick chimneys. Asphalt shingle roof. Vinyl siding. Modern 8/8 windows with shutters. One-story, shed roof, full length, front porch with modern Doric posts and wrought iron railing. Shed roof carport attached on side. Rock-faced concrete block and concrete block foundation. 3 X 5 bays. Queen Anne Cottage style. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 27

JA-0038. (11394) 216 BEDFORD STREET, residential

Williams House

date: c. 1925

description: One-story, hip gable roof house. Asphalt shingle roof. Asbestos shingle siding. 1/1 windows. One-story, shed roof, front porch with Doric posts on an enclosed balustrade. One-story, shed roof, enclosed, rear porch. Rock-faced concrete block foundation. 3 X 5 bays. Queen Anne Cottage style. One Contributing building.

JA-0039. (11395) 718 SYCAMORE, residential

Adkins House

date: c. 1935

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows. End gable, entrance porch supported by turned posts on a wood deck with ramp. One-story, shed roof, enclosed, rear porch. Faux stone veneer covers foundation. 3 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

JA-0040. (11397) 221 BEDFORD STREET, residential

Grimmett House

date: c. 1925

description: Small, two-story, end gable house with shed roof dormers on the side. Asphalt shingle roof. Clapboard siding with frieze and corner boards. 1/1 windows; ribbon of three in gable end. One-story, modified hip roof, full length, front porch with battered square columns and "X" balustrade. Rock-faced concrete block foundation. 3 X 3 bays. Gable-Front house. One Contributing building.

JA-0041. (11398) 219 BEDFORD STREET, residential

Cogar House

date: c. 1925

description: Similar to 221 Bedford Street. Small, two-story, end gable house with shed roof dormers on the side. Asphalt shingle roof. Partial return cornice. Aluminum siding. 1/1 windows with shutters; ribbon of three in gable end. One-story, modified hip roof, three-quarter length, front porch has been fully enclosed with modern 6/6 windows and siding. One-story, enclosed, rear porch. Rock-faced concrete block foundation. 3 X 2 bays. Gable-Front house. One Contributing building.

A.

date: c. 2005

description: Two-story, side gable garage. Currently under construction. Asphalt shingle roof. Plywood siding yet to be covered with a finish. Concrete foundation. 2 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 28

JA-0041. (11398) 219 BEDFORD STREET, residential (continued)

B.

date: c. 2000

description: One-story, gambrel roof outbuilding. Asphalt shingle roof. T-111 siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0042. (11399) 804 SYCAMORE, residential

Matics House

date: c. 1955

description: One and one-half-story, side gable house with one-story, projecting, end gable bay on the front. Central, end gable dormer on the front. Asphalt shingle roof. Exposed, red brick chimney on the end. Red brick façade. Metal casement windows. Recessed entrance porch within roof overhang has a picture window and a red brick pad. One-story, enclosed, rear porch; enclosed with screening and lattice. Attached, one bay, side gable garage on right. Concrete foundation. 4 X 2 bays. Ranch type. One Contributing building.

JA-0043. (113100) 217 BEDFORD STREET, residential

Jones House

date: c. 1925

description: Two-story, end gable house with shed roof dormers on each side. Asphalt shingle roof. Partial return cornice. Vinyl siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch is fully enclosed with windows and siding. Rock-faced concrete block foundation. 3 X 3 bays. Gable-Front house. One Contributing building.

JA-0044. (113102) 207 BEDFORD STREET, residential

Bibbee House

date: c. 1920

description: Two-story, hip roof house. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch has been fully enclosed. One-story, hip roof, three-sided, projecting bay on the side. One-story, shed roof, full length, enclosed, rear porch. Concrete block foundation. 3 X 4 bays. Craftsman Four Square type. Very modified. One Non-Contributing building.

JA-0045. (113104) 203 BEDFORD STREET, residential

Mullins House

date: c. 1925

description: One-story, side gable house. Asphalt shingle roof. Horizontal board siding partially covered with black board and roofing felt. Boarded windows. One-story, shed roof, full length, front porch with turned posts on red brick piers with concrete caps. One-story, hip

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 29

roof addition on north. Concrete block foundation. 3 X 1 bays. Side Gable Cottage. Modified.
One Non-Contributing building.

JA-0046. (113104.1) 201 BEDFORD STREET, residential

Mullins House

date: c. 1925

description: One and one-half-story, hip roof house with projecting, gable bay on front. Asphalt shingle roof. Central, interior, red brick chimney. Gable dormer on side. Front gable bay is three-sided and has scrolled brackets with dropped finials. Vinyl siding. Modern 1/1 windows. One-story, shed roof, entrance porch with square posts on an enclosed balustrade. One-story addition on rear. Rock-faced concrete block foundation. 2 X 4 bays. Queen Anne Cottage style. One Contributing building.

JA-0047. (213106) 802 WALNUT STREET, residential

Lacava House

date: c. 1904

description: Large, two-story, hip gable roof house. Curved tower with pyramidal slate roof on the right. Asphalt shingle roof. Gable ends have diagonal shingles and the front gable end has an arched opening. Wide frieze board. Red brick façade. 1/1 windows with rusticated stone lintels and sills; small novelty windows in upper portion of tower. One-story, front porch with gable pediment and square brick columns on an enclosed brick balustrade with concrete caps; attached to this porch on the right is a one-story, curved, enclosed porch with vertical 3/1 windows and red brick façade. Small, one-story, enclosed, entrance wing on the rear. One-story, gable wing on the side. Cut stone foundation. 6 X 5 bays. Queen Anne style. One Contributing building.

A.

date: c. 2005

description: Two-story, end gable, three bay garage. Asphalt shingle roof. Red brick façade with brick quoins. 6/6 windows with concrete keystones. Lunette windows in gable end. Garage bays have arched openings with keystones. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

JA-0048. (213107) 107 PRESTON STREET, residential

Taylor House

date: c. 1915

description: Large, two-story, hip gable roof house. Asphalt shingle roof. Vinyl siding. Scalloped shingles in gable end. Front gable projects and is two-story, three-sided. Modern 1/1 windows; picture window with leaded glass header in front gable bay. One-story, shed roof, front porch with square posts on an enclosed, rock-faced concrete block balustrade. One-story,

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 30

three-sided, projecting bay on side. One-story, rear porch with turned posts. One-story, shed roof porch attached to rear porch. Rock-faced concrete block foundation. 2 X 2 bays. Queen Anne style. Modified. One Non-Contributing building.

A.

date: Modern

description: Tall one-story, end gable garage/outbuilding. Metal roof. Metal siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0049. (213108) 105 PRESTON STREET, residential

Greathouse House

date: c. 1900

description: One-story, hip roof house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Aluminum siding. Modern 1/1 windows with shutters. One-story, shed roof, three-quarter length, front porch with turned posts on a wood deck supported by a pier foundation – non-original. One-story, gable addition on rear. Concrete block foundation. 3 X 3 bays. One-story Cube. One Contributing building.

JA-0050. (213109) 103 PRESTON STREET, residential

Adkins House

date: c. 1900

description: Twin to 105 Preston Street. One-story, hip roof house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with turned posts on an enclosed balustrade. One-story, full length, enclosed, rear porch with attached, shed roof, enclosed addition. Rock-faced concrete block foundation. 3 X 4 bays. One-story Cube. One Contributing building.

JA-0051. (213110) 101 PRESTON STREET, residential

Anderson House

date: c. 1900

description: Small one-story, side gable house with side gable wing on left. Central, interior, red brick chimney. Metal roof. Vinyl siding. 1/1 and 6/6 windows. One-story, modified hip roof, three-quarter length, front porch with central gable entrance pediment and turned posts with lattice balustrade. Rock-faced concrete block foundation. 4 X 1 bays. Side Gable Cottage. One Contributing building.

A.

date: c. 1970

description: One-story, end gable outbuilding. Metal roof. Vinyl siding. Block foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 31

JA-0052. (213111) 101 WILSON STREET, residential

Caldwell House

date: c. 1930

description: One and one-half-story, side gable house. Asphalt shingle roof. Vinyl siding. 6/6 windows. One-story, shed roof, metal canopy over concrete entrance deck with wrought iron posts. Rock-faced concrete block foundation. 4 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

A.

date: c. 1930

description: One-story, end gable garage. Metal roof. Metal board and batten siding. Concrete foundation. 2 X 1 bays. One Non-Contributing building.

JA-0053. (213112) 103 WILSON STREET, residential

Jarrett House

date: c. 1930

description: Twin to 101 Wilson Street. One and one-half-story, side gable house. Asphalt shingle roof. Weatherboard siding. 6/6 windows. Tripartite window in recessed portion of front – house next door has a porch in this location. One-story, shed roof, full length, rear porch has been enclosed with 2X4s and screening and has a concrete block pier foundation. Rock-faced concrete block elsewhere. 3 X 3 bays. Colonial Revival style. One Contributing building.

JA-0054. (213113.1) 150 WILSON STREET, residential

Hicks House

date: c. 1900

description: Large, two-story, hip gable roof house. Asphalt shingle roof. Interior, red brick chimney. Gingerbread in gable ends. Wide frieze board with scroll brackets. Vinyl siding. Modern 1/1 windows with tall hoods with dentils; picture windows with leaded glass headers also. One-story, modified hip roof, entrance porch with square slightly battered columns on a concrete deck supported by rock-faced concrete block. One-story, cross gable addition on rear. Painted brick foundation. 3 X 4 bays. Queen Anne style. One Contributing building.

A.

date: c. 1920

description: One-story, end gable garage with flanking, shed roof car ports. Roll roofing. Clapboard siding. Concrete block foundation. 3 X 1 bays. One Contributing building.

JA-0055. (213115) 113 WILSON STREET, residential

Bartley/Crunick House

date: c. 1900

description: Large, two-story, hip gable roof house. Central, interior, corbelled brick chimney. Slate roof. Partial return cornice. Vergeboards and gingerbread in gable ends. Wide frieze

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 32

board with scroll brackets. Clapboard siding with corner boards. 1/1 and fixed leaded glass windows. One-story, modified hip roof, full length, front porch with turned posts with Moorish arch panels above with brackets and spindled balustrade. Rear gable bay is flanked by porches: one side is shed roof and enclosed; the other is open on the first floor and has large, rock-faced concrete block columns and the second floor overhangs the porch. Shed roof dormer on rear. Cut stone foundation. 2 X 5 bays. Queen Anne style. One Contributing building.

A.

date: c. 1940

description: Two-story, shallow end gable garage with tall, one-story, shed roof garage attached on right. Asphalt shingle roof. German siding on second floor; concrete block first floor and foundation. Vertical 3/1 windows on second floor; three garage bays on first floor. 4X2 bays. One Contributing building.

JA-0056. (31523) 15 WILSON STREET, residential

Garrett House

date: c. 1930

description: One-story, side gable house with central, wall gable on the front. Asphalt shingle roof. Clapboard siding with corner boards. Vertical 2/2 windows. One-story, modified hip roof, three-quarter length, front porch with square posts with scrolled brackets and slatted balustrade. One-story, shed roof, enclosed, rear porch. Concrete block foundation. 3 X 3 bays. Side Gable Cottage. One Contributing building.

JA-0057. (31524) 11 WILSON STREET, residential

Moss/Miller House

date: c. 1915

description: One-story, front facing "L" house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows with shutters. One-story, shed roof porch in the corner of the ell with square posts on an enclosed balustrade. One-story, shed roof, full length, enclosed, rear porch/addition. Concrete block foundation. 4 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 33

JA-0058. (31525) 9 WILSON STREET, residential

Nuckles House

date: c. 1915

description: Large, two-story, side gable house with projecting, two-story, gable, three-sided bay on the front and a three-sided bay on the second floor with a pyramidal roof. Asphalt shingle roof. Clapboard siding with frieze and corner boards. 1/1 windows. Scrolled brackets with drop finials at top of front gable bay. One-story, modified hip roof, full length, front porch with decorative trim and turned posts and pilasters. Rock-faced concrete block foundation. 2 X 3 bays. Queen Anne style. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0059. (31526) 5 WILSON STREET, residential

Casto House

date: c. 1920

description: Large, two-story, front facing "L" house. Each end of the ell is a two-story, projecting, three-sided bay. Asphalt shingle roof. Aluminum siding. Modern 1/1 windows with shutters; novelty windows in gable bays. One-story, shed roof porch in the corner of the ell with square posts and turned pilasters on a concrete pad. One-story, shed roof, enclosed, rear porch. One-story, gable addition on the north. Rock-faced concrete block foundation. 3 X 2 bays. Gabled-Ell house. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding with shed roof wing on the right. Asphalt shingle roof. Painted plywood siding. Unknown foundation. 2 X 1 bays. One Non-Contributing building.

JA-0060. (31527) 717 ASHTON STREET, residential

Quillen House

date: c. 1920

description: Two-story, rear facing "L" house. Asphalt shingle roof. Vinyl siding. 1/1 windows with shutters. One-story, modified hip roof, full length, front porch has been fully enclosed. One-story, modified hip roof, rear porch with wrought iron posts. Rock-faced concrete block foundation. 2 X 3 bays. Gable-Ell house. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 34

JA-0060. (31527) 717 ASHTON STREET, residential (*continued*)

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. T-111 siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

JA-0061. (31528) 13 PRESTON STREET, residential

Bennett House

date: c. 1930

description: One-story, end gable garage with attached, one-story, side gable apartment units. Asphalt shingle roof. Garage portion is terra cotta block and concrete block façade with asbestos shingle siding in the gable end; apartment wing has concrete block façade. Combination of windows with metal canopies. Concrete block foundation. 8 X 1 bays. Modified. One Non-Contributing building.

JA-0062. (31529) 9 PRESTON STREET, residential

Smith House

date: c. 1940

description: One and one-half-story, end gable house. Gable dormers on the sides. Asphalt shingle roof. Aluminum siding. Metal casement windows. Entrance porch on the corner, recessed diagonally within the roof overhang: has wrought iron posts and railing and a metal canopy. Small gable, entrance porch on the side with wrought iron posts and railing. Attached gable, car port on the south side of the house with wrought iron posts and railing on a concrete deck. Concrete block foundation. 2 X 4 bays. Gable Front house. One Contributing building.

A.

date: c. 1940

description: One-story, end gable outbuilding. Corrugated metal roof. Aluminum siding. Concrete foundation. 1 X 1 bays. One Contributing building.

JA-0063. (31531) 7 PRESTON STREET, residential

Thompson House

date: c. 1900

description: Two-story, side gable house. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows. One-story, shed roof, entrance porch with square posts and slatted balustrade – non-original. One-story, shed roof, full length, enclosed, rear porch. Foundation is covered. 3 X 2 bays. Side Gable house. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 35

JA-0064. (31532) 5 PRESTON STREET, residential

McKay House

date: c. 1930

description: Two-story, cross gable house. Asphalt shingle roof. Vinyl siding. Replacement 6/6 windows. One-story, modified hip roof, front porch in corner of ell with wrought iron posts on a concrete deck. One-story, modified hip roof, porch on the side with wrought iron posts on a concrete deck. One-story, shed roof, enclosed, rear porch. Foundation is covered. 3 X 3 bays. Gabled-Ell house. Modified. One Non-Contributing building.

JA-0065. (31534) 3 PRESTON STREET, residential

Kay/Price House

date: c. 1930

description: One-story, front facing "L" house. Metal roof. Vinyl siding. Modern 1/1 windows with shutters. Projecting front gable bay has brick veneer on lower half. One-story, shed roof, front porch in corner of ell with wrought iron posts on a concrete deck. Concrete block foundation. 4 X 2 bays. Gabled-Ell house. Modified. One Non-Contributing building.

JA-0066. (31535) 1 PRESTON STREET, residential

Lott House

date: c. 1915

description: Large, two-story, gabled-ell house with large two-story addition on rear. Two, interior, corbelled brick chimneys. Metal roof. Brackets in roof eave. Vinyl siding. Modern 1/1 and picture windows with leaded glass headers. First floor of projecting gable bays is three-sided and have cut out brackets with dropped finials. One-story, shed roof, front porch with turned posts. Foundation is covered. 3 X 2 bays. Gabled-Ell house. One Contributing building.
A.

date: c. 1915

description: One-story, shed roof outbuilding. Roll roofing. German siding with corner boards. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0067. (31536) 801 ASHTON STREET, residential

Skeens House

date: c. 1925

description: Two-story, end gable house. Asphalt shingle roof. Knee braces and shingles in gable end. Rock-faced concrete block and concrete block façade. 1/1 windows with concrete lintels. One-story, shed roof, full length, front porch is enclosed with vertical 3/1 windows and painted metal siding in a diagonal shingle pattern. Concrete block foundation. 3 X 2 bays. Craftsman style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 36

JA-0068. (31537) 803 ASHTON STREET, residential

Quillen House

date: c. 1930

description: One and one-half-story, end gable house. Asphalt shingle roof. German siding with frieze and corner boards. Vertical 3/1 windows; many are paired. One-story, modified hip roof, three-quarter length, front porch with exposed rafter tails and battered square columns on a wood deck. One-story, rear porch. Rock-faced concrete block foundation. 3 X 2 bays. Gable-Front house. One Contributing building.

A.

date: Modern

description: One-story, shed roof outbuilding. Metal roof. Metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0069. (31538) 805 ASHTON STREET, residential

Bennett House

date: c. 1915

description: One-story, front facing "L" house. Asphalt shingle roof. Vinyl siding with narrow frieze and corner boards. Vertical 2/2 windows. One-story, shed roof, front porch in corner of ell with square posts and slatted balustrade. One-story, shed roof, rear porch has been enclosed and a one-story, shed roof addition attached to it. Parged foundation. 4 X 4 bays. Gabled-Ell house. One Non-Contributing building.

JA-0070. (313153) 712 SAND STREET, residential

Taylor House

date: c. 1930

description: Two-story, side gable house. Asphalt shingle roof. Weatherboard siding. Modern slider and horizontal 2/2 metal windows. One-story, full length, shed roof, front porch: east side is fully enclosed; west side has turned posts on a concrete deck. Concrete block foundation. 4 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

A.

date: c. 1930

description: Small, one-story, end gable outbuilding with open, shed roof bay on right supported by wrought iron posts. Asphalt shingle roof. Weatherboard siding. Concrete foundation. 2 X 1 bays. One Non-Contributing building.

JA-0071. (313154) 29 WILSON STREET, residential

Elkins House

date: c. 1930

description: One-story, side gable house with rear gable addition. Asphalt shingle roof. Partial return cornice. Asbestos shingle siding. Horizontal 2/2 windows. One-story, modified hip roof,

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 37

three-quarter length, front porch with slightly battered square posts on an enclosed balustrade – balustrade is rock-faced concrete block. Small, one-story, shed roof, enclosed entrance bay on the rear. Rock-faced concrete block foundation. 4 X 3 bays. Side Gable Cottage. One Contributing building.

JA-0072. (313155) 27 WILSON STREET, residential**Bennett House**date: c. 1900description: One-story, side gable house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Partial return cornice. Vinyl siding. Vertical 2/2, 1/1 and horizontal 2/2 windows. One-story, shed roof, entrance porch with square posts and scrolled brackets. One-story, shed roof, enclosed, full length, rear porch. Rock-faced concrete block foundation. 3 X 3 bays. Side Gable Cottage. Modified. One Non-Contributing building.**JA-0073. (313156) 25 WILSON STREET, residential****Stephens House**date: c. 1920description: Two-story, shallow hip roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, shed roof, side porch with 2X4 supports on a concrete pad. One-story, hip roof addition attached to the rear of the porch and it has a one-story, shed roof addition attached to it. Rock-faced concrete block foundation. 4 X 2 bays. Pyramidal house type. Very modified. One Non-Contributing building.**JA-0074. (313159) 19 WILSON STREET, residential****Dow House**date: c. 1900description: One-story, side gable house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Asbestos shingle siding. Vertical 2/2 windows. One-story, end gable, entrance porch with square brick columns on an enclosed brick balustrade with concrete caps. One-story, hip roof addition on north. One-story, shed roof, enclosed rear porch. Concrete block foundation. 3 X 1 bays. Side Gable Cottage. One Contributing building.**JA-0075. (313161) PRESTON STREET, residential****Harris House**date: c. 1925description: One-story, side gable house. Central, interior, corbelled brick chimney. Metal roof. German siding with frieze and corner boards. Window glazing completely gone. One-story, shed roof, entrance porch with turned posts on a wood deck supported by concrete block pier foundation. One-story, shed roof, full length, enclosed, rear porch. Red brick and concrete block foundation. 2 X 3 bays. Side Gable Cottage. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 38

JA-0076. (313162) 29 PRESTON STREET, residential **Linicome/Heugatter House**
date: c. 1915

description: One and one-half-story, side gable house. Metal roof. Central, interior, red brick chimney has been partially parged. Clapboard siding with frieze and corner boards. Vertical 2/2 windows. One-story, modified hip roof, entrance porch with square posts on a wood deck. One-story, shed roof, enclosed, full length, rear porch. Pier foundation. 3 X 3 bays. Side Gable Cottage. One Contributing building.

A.

date: c. 1915

description: One-story, hip roof outbuilding/well house. Roll roofing. German siding with corner boards. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0077. (313167) 19 PRESTON STREET, residential **Bennett House**
date: c. 1915

description: One-story, side gable house. Roll roofing. Clapboard siding with frieze and corner boards. Vertical 2/2 windows. One-story, shed roof, entrance porch with turned posts and slatted balustrade. One-story, shed roof, full length, rear, enclosed porch. Pier foundation. 2 X 1 bays. Side Gable Cottage. One Contributing building.

A.

date: Modern

description: One-story, side gable house. Asphalt shingle roof. T-111 siding and wood shingles in gable ends. 4/4 windows. Parged foundation. Unknown bays. One Non-Contributing building.

JA-0078. (313168) 17 PRESTON STREET, residential **Bennett House**
date: c. 1915

description: One and one-half-story, side gable house. Asphalt shingle roof. Clapboard siding with frieze and corner boards with caps. Wood shingles in gable ends. 1/1 and vertical 2/1 windows. One-story, shed roof, entrance porch with square posts on a concrete deck supported by concrete block foundation. One-story, shed roof, rear, enclosed porch with concrete block foundation. Pier foundation elsewhere. 3 X 3 bays. Side Gable Cottage. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 39

JA-0079. (41358) 219 GALLATIN STREET, residential

Vannest House

date: c. 1930

description: Two-story, front gable house. Two, interior, corbelled brick chimneys. Corrugated metal roof. Vinyl siding; faux stone veneer on lower half of front. Modern 1/1 windows. One-story, modified hip roof, entrance porch with modern Doric columns. One-story, shed roof, rear porch. One-story, shed roof addition attached on the south. Concrete foundation. 2 X 2 bays. Gable-Front house. Modified. One Non-Contributing building.

A.

date: Modern

description: Gazebo. One Non-Contributing building.

JA-0080. (41359) 217 GALLATIN STREET, residential

Stanley House

date: c. 1920

description: Two-story, hip roof house. Corrugated metal roof. Vinyl siding. Faux 6/6 windows with shutters. One-story, end gable, three-quarter length, front porch with Tuscan columns on a concrete deck. One-story, gable, rear porch with Doric columns. Brick foundation. 2 X 1 bays. Craftsman Four Square type. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, side gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 3 X 1 bays. One Non-Contributing building.

JA-0081. (41360) 215 GALLATIN STREET, residential

Cobb House

date: c. 1915

description: Large, two-story, hip gable roof house. Two-story, rear addition. Interior, corbelled brick chimney. Asphalt shingle roof. Vinyl siding. 1/1 and picture windows with leaded glass headers. One-story, modified hip roof, front porch with decorative trim and turned posts with brackets and a spindled balustrade on a wood deck. Brick foundation. 2 X 3 bays. Queen Anne style. One Contributing building.

JA-0082. (41362) 211 GALLATIN STREET, residential

Cedar House

date: c. 1910

description: One-story, front facing "L" house with one-story, gable wing on the rear. Two, interior, corbelled brick chimneys. Asphalt shingle roof. Vinyl siding. Modern 1/1 and

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 40

replacement 6/6 windows. One-story, shed roof, front porch with square posts on a concrete deck. Brick foundation. 3 X 4 bays. Gabled-Ell house. One Non-Contributing building.

A.

date: c. 1930

description: One-story, end gable garage/outbuilding. Metal roof. Asphalt shingle siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0083. (41363) 209 GALLATIN STREET, residential

Ray House

date: c. 1915

description: One-story, hip roof house with flat section on roof top. Asphalt shingle roof. Vinyl siding. Variety of modern windows. One-story, shed roof, front porch fully enclosed and incorporated into the main body of the house. One-story, gable addition on rear. One-story, shed roof addition on rear. 3 X 4 bays. One-story Cube. Modified. One Non-Contributing building.

A.

date: c. 1990

description: One-story, shed roof outbuilding. Roof currently being replaced. Plywood and vinyl siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0084. (41364) 207 GALLATIN STREET, residential

Mullins House

date: c. 1920

description: One-story, front facing "L" house. Asphalt shingle roof. Vinyl siding; chevron siding in the gable ends. 1/1 windows. One-story, shed roof, front porch in the corner of the ell fully enclosed with vertical 3/1 windows and rock-faced concrete block. One-story, modified hip roof, three-sided, projecting bays on the front and on the side. One-story, shed roof, enclosed, rear porch. Rock-faced concrete block foundation. 3 X 3 bays. Gabled-Ell house. One Contributing building.

JA-0085. (41365) 205 GALLATIN STREET, residential

Davis House

date: c. 1900

description: Two-story, hip roof house. Metal roof. Central, interior, corbelled brick chimney. Clapboard siding with frieze and corner boards. Vertical 2/2 windows. One-story wraparound porch: partially enclosed on the far right; remainder has Tuscan columns on a wood deck. Cut stone foundation. 4 X 1 bays. Craftsman Four Square type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 41

JA-0085. (41365) 205 GALLATIN STREET, residential (*continued*)

A.

date: c. 1965

description: One-story, side gable garage. Metal roof. Metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0086. (41366) 201 GALLATIN STREET, residential

Mandrake House

date: c. 1915

description: Two-story, side gable house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Asbestos shingle siding. 1/1 and faux 9/9 windows. One-story, modified hip roof, three-quarter length, front porch with large central pediment: porch enclosed on the right; large battered square posts on an enclosed balustrade on the left. Attached, one-story, end gable, one bay garage on the rear. One-story, enclosed, rear porch. Brick and parged foundation. 3 X 3 bays. Side Gable house. One Contributing building.

JA-0087. (41367) 200 WILSON STREET, residential

Woodburn House

date: c. 1900

description: Two-story, hip gable roof house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Leaded glass windows and scalloped shingles in gable ends. Wide frieze board with brackets and dropped finials at the corners. Red brick façade. All windows have a leaded glass upper sash and undivided lower sash with rusticated stone lintels and sills. One-story, modified hip roof, full length, front porch with a roof balustrade and square brick columns and a brick enclosed balustrade with stone caps – non-original. One-story, shed roof, rear porch. Cut stone foundation. 4 X 3 bays. Queen Anne style. One Contributing building.

A.

date: c. 1925

description: Two-story, end gable garage. Asphalt shingle roof. Exposed rafter tails. Asbestos shingle siding on second floor; parged first floor and foundation. Exterior stair to upper floor. 2 X 1 bays. One Contributing building.

JA-0088. (41368) 202 WILSON STREET, residential

Woodburn House

date: c. 1915

description: One-story, hip roof house with flat section on roof top. Central, gable dormer on front with narrow 6/6 window. Asphalt shingle roof. Vinyl siding. Faux 9/9 windows; windows on front have a single lower undivided lower sash with a narrow undivided upper sash. One-

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 42

story, modified hip roof, three-quarter length, front porch with wrought iron posts on a concrete deck. Brick foundation. 3 X 3 bays. One-story Cube. One Contributing building.

JA-0089. (41369) 204 WILSON STREET, residential

Anderson House

date: c. 1915

description: Large two-story, front facing "L" house. Asphalt shingle roof. Clapboard siding with frieze and corner boards. 1/1 windows with simple surrounds and hoods. One-story, modified hip roof, three-quarter length, front porch with one portion on the right that projects and porch has Tuscan posts on an enclosed molded concrete block balustrade. Brick foundation. 3 X 1 bays. Gabled-Ell house. One Contributing building.

A.

date: c. 1940

description: Tall one-story, shed roof garage/outbuilding with attached shed roof, car port. Corrugated metal and fiberglass roof. Weatherboard siding. Pier foundation. 4 X 1 bays. One Contributing building.

JA-0090. (41370) 206 WILSON STREET, residential

Simms House

date: c. 1940

description: One-story, end gable house. Asphalt shingle roof. Weatherboard siding. Faux 8/8 and 4/4 windows. One-story, end gable, entrance porch with wrought iron posts and railing. Concrete block foundation. 3 X 2 bays. Gable-Front house. One Non-Contributing building.

A.

date: c. 1990

description: One-story, end gable outbuilding. Asphalt shingle roof. Plywood siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0091. (41372) 210 WILSON STREET, residential

Kiser House

date: c. 1910

description: Two-story, hip roof, front facing "L" house. Asphalt shingle roof. Clapboard siding with frieze and corner boards. 1/1 windows. One-story, modified hip roof, full length, front porch with square columns on an enclosed balustrade. One-story, shed roof, enclosed, rear porch. Brick pier foundation. 2 X 2 bays. Cross Hipped house. One Contributing building.

A.

date: c. 1930

description: One-story, shed roof outbuilding. Metal roof. Asphalt shingle siding. Six pane windows. Pier foundation. 3 X 1 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 43

JA-0092. (41373) 212 WILSON STREET, residential

Craigo House

date: c. 1945

description: One and one-half-story, cross gable house. Asphalt shingle roof. Vinyl siding. Faux 6/6 windows. One-story, modified hip roof, entrance porch with turned posts and a spindled balustrade on a concrete deck. Concrete block foundation. 4 X 2 bays. Colonial Revival style. Modified. One Non-Contributing building.

A.

date: c. 1945

description: One-story, end gable garage. Asphalt shingle roof. Exposed rafter tails. Concrete block façade and foundation. Asbestos shingle siding in gable end. Attached shed roof, car port on the front. 1 X 1 bays. One Non-Contributing building.

JA-0093. (41374) 214 WILSON STREET, residential

Divers House

date: c. 1920

description: Two-story, truncated hip roof house. Asphalt shingle roof. Brackets in roof eave. Vinyl siding on the front; asbestos shingle siding elsewhere. Replacement 9/9 windows. One-story, modified hip roof, front porch has been fully enclosed with windows and siding; two bow windows on the front. Attached car port on the side. One-story, rear wing with asbestos shingle siding. Brick pier foundation. 3 X 3 bays. Craftsman Four Square type. Modified. One Non-Contributing building.

A.

date: c. 1990

description: One-story, side gable outbuilding. Asphalt shingle roof. Pressed board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0094. (41375) 216 WILSON STREET, residential

Adkins House

date: c. 1920

description: Two-story, side gable house. Interior, corbelled brick chimney. Corrugated metal roof. Asbestos shingle siding. 1/1 windows; paired on the front. One-story, modified hip roof, three-quarter length, front porch with slightly battered square columns on an enclosed balustrade. One-story, shed roof, rear porch with square posts. Concrete block foundation. 3 X 2 bays. Side Gable house. One Contributing building.

A.

date: c. 1920

description: One-story, end gable outbuilding. Asphalt shingle siding. German siding. Concrete block foundation. 1 X 1 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 44

JA-0095. (412226) 207 HENRY STREET, residential

Palmer House

date: c. 1910

description: Two-story, hip gable roof house. Two, interior, brick chimneys. Asphalt shingle roof. Light brown brick façade. Replacement 6/1 windows with rusticated lintels and sills. One-story, hip roof, front porch with square painted brick columns and a slatted painted brick balustrade with painted stone caps. Cut stone foundation. 3 X 3 bays. Queen Anne style. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0096. (412227) 205 HENRY STREET, residential

Hughey House

date: c. 1910

description: Two-story, cross gable house. Asphalt shingle roof. Interior, brick chimney. Original portion of house has weatherboard siding; front addition has wood shingles. 1/1, replacement 6/6 and leaded glass windows. Front addition is located where original porch would have been. One-story, modified hip roof, wraparound recessed porch with non-original square posts on an enclosed shingled balustrade. One-story, shed roof, rear porch with square posts and a slatted balustrade. Parged foundation. 4 X 3 bays. Queen Anne Cottage style. Very modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Roll roofing. Metal siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0097. (412229) 201 HENRY STREET, residential

Imperio House

date: c. 1910

description: Two-story, hip roof house with hip dormers. Asphalt shingle roof. Interior, corbelled brick chimney. Vinyl siding. Replacement 4/4 windows with metal canopies. One-story, modified hip roof, front porch with square rock-faced concrete block columns on an enclosed rock-faced concrete block balustrade. One-story, shed roof, rear porch. Rock-faced concrete block foundation. 2 X 3 bays. Craftsman Four Square type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 45

JA-0098. (412231) 218 GALLATIN STREET, residential

Hughes House

date: c. 1920

description: Two-story, hip roof house with hip dormers. Metal roof. Vinyl siding with corner boards. 1/1 and multi-pane windows with shutters. One-story, modified hip roof, front porch has been fully enclosed: the rock-faced concrete block balustrade was infilled with T-111 siding and windows. One-story, rear porch with square posts. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. Modified. One Non-Contributing building.

A.

date: c. 1920

description: One-story, end gable garage with attached shed roof, car port. Metal roof. Board and batten siding. Pier and concrete foundation. 4 X 1 bays. One Non-Contributing building.

JA-0099. (412233) 214 GALLATIN STREET, residential

Cadle House

date: c. 1920

description: Two-story, side gable house with central, end gable dormer. Metal roof. Zig-zag shingles in gable ends. German siding with corner boards. Variety of window types. One-story, shed roof, full length, front porch within roof overhang has battered square columns on an enclosed asbestos shingle sided balustrade. One-story, enclosed, rear porch. Molded concrete block foundation. 3 X 3 bays. Craftsman Bungalow style. One Contributing building.

A.

date: c. 1930

description: Two-story, hip roof garage/apartment. Asphalt shingle roof. Asbestos shingle siding on the second floor; concrete block first floor and foundation. Horizontal 2/2 windows. 3 X 1 bays. One Contributing building.

JA-0100. (412234) 212 GALLATIN STREET, residential

Stagg House

date: c. 1925

description: Large two-story, hip gable roof house. Asphalt shingle roof. Interior, brick chimney. Aluminum and metal board and batten siding. 1/1 windows. One-story, modified hip roof, full length, front porch with Tuscan columns on a concrete deck supported by a molded concrete block foundation. Molded concrete block foundation. 3 X 3 bays. Gabled-Ell house. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 46

JA-0100. (412234) 212 GALLATIN STREET, residential (continued)

A.

date: c. 1925

description: One-story, end gable apartment. Asphalt shingle roof. T-111 siding. One-story, shed roof addition added on left. Garage converted to residence. Block foundation. 2 X 1 bays. Modified. One Non-Contributing building.

JA-0101. (412235) 210 GALLATIN STREET, residential

Pease House

date: c. 1915

description: Large, two-story, side facing "T" house. Interior, corbelled brick chimney. Asphalt shingle roof. Partial return cornice. Vinyl siding. 1/1 windows with metal canopies. One-story, shed roof, front porch has been fully enclosed with siding and bow window. One-story, shed roof, enclosed, rear porch. Brick foundation. 3 X 3 bays. Gabled-Ell house. Modified. One Non-Contributing building.

A.

date: c. 1920

description: One-story, end gable garage with one-story, shed roof wing on left. Asphalt shingle roof. Exposed rafter tails. Metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0102. (412236) 208 GALLATIN STREET, residential

Adkins House

date: c. 1910

description: One-story, hip roof house. Metal roof. Vinyl siding. Vertical 2/2 windows. One-story shed roof, entrance porch with square posts on a concrete deck. One-story enclosed, rear porch. Foundation is covered. 3 X 3 bays. One-story Cube. Modified. One Non-Contributing building.

JA-0103. (412236.1) 208A GALLATIN STREET, residential

Cedar House

date: c. 1930

description: Two-story end gable garage/apartment. Asphalt shingle roof. Asbestos shingle siding, aluminum siding, painted T-111 and shingle siding on the second floor; concrete block and T-111 siding on the first floor. 1/1 and small modern windows. First floor has been converted to two apartment entrances and the second floor porch has been enclosed. One-story wing on left. 3 X 2 bays. Gable Front building. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 47

JA-0104. (412237) 206 GALLATIN STREET, residential

Staats House

date: c. 1915

description: Two-story, hip roof house. Central, interior, corbelled brick chimney. Asphalt shingle roof. Vinyl siding. 1/1 windows with shutters. One-story, shed roof, front porch with modern Doric columns on an enclosed rock-faced concrete block foundation. One-story, open rear porch. Rock-faced concrete block foundation. 3 X 2 bays. Craftsman Four Square type. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, gable, free standing car port. Metal roof and supports on a concrete pad. One Non-Contributing building.

JA-0105. (412238) 204 GALLATIN STREET, residential

Shumaker House

date: c. 1910

description: Two-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, end gable, entrance porch with square columns on a concrete deck. One-story enclosed, rear porch. Cut stone foundation. 2 X 3 bays. Pyramidal house type. Modified. One Non-Contributing building.

JA-0106. (412239) 202 GALLATIN STREET, residential

Bennett House

date: c. 1920

description: Two-story, truncated hip roof house. Asphalt shingle roof. Asbestos shingle siding. Replacement 6/6 windows. One-story, shed roof, entrance porch with square posts with brackets and picket fence style balustrade. Steep shed roof, full length, enclosed, rear addition. Foundation is covered. 3 X 3 bays. Pyramidal house type. One Contributing building.

A.

date: c. 1920

description: One-story end gable outbuilding. Asphalt shingle roof. Exposed rafter tails. Painted terra cotta block façade and foundation. 1 X 2 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 48

JA-0107. (412240) 200 GALLATIN STREET, residential

McKay House

date: c. 1910

description: Unusual two-story, side gable house. Front gable bay projects above the roof line to create a large dormer on the upper story. Metal and asphalt shingle roof. Vinyl siding. Vertical 2/2 and 1/1 windows. One-story modified hip roof, front porch with turned posts, decorative trim and a concrete deck/pad. One-story gable, rear addition. Pier and concrete block foundation. 3 X 3 bays. Folk Victorian style. One Contributing building.

JA-0108. (512241) 113 HENRY STREET, residential

Shinn House

date: c. 1930

description: One and one-half-story, rear facing "L" house with gabled entrance bay on the front. Asphalt shingle roof. Exposed, red brick chimney next to entrance bay on the front. Sloping roof of entrance bay surrounds chimney. Red brick façade. 6/6 and 8/8 windows with brick sills. Concrete foundation. 3 X 3 bays. Tudor Revival style. One Contributing building.

A.

date: c. 1930

description: Two-story, hip roof garage/apartment. Asphalt shingle roof. Asbestos shingle siding on second floor; concrete block façade and foundation on first floor. 3 X 2 bays. One Contributing building.

JA-0109. (512242) 111 HENRY STREET, residential

Shinn House

date: c. 1930

description: Twin to 113 Henry Street. One and one-half-story, rear facing "L" house with gabled entrance bay on the front. Asphalt shingle roof. Exposed, red brick chimney next to entrance bay on the front. Sloping roof of entrance bay surrounds chimney. Red brick façade. 6/6 and 8/8 windows with brick sills. Concrete foundation. 3 X 3 bays. Tudor Revival style. One Contributing building.

JA-0110. (512243) 109 HENRY STREET, residential

Miller House

date: c. 1930

description: One-story, cross gable house. Asphalt shingle roof. Central, interior brick chimney. T-111 siding. 1/1 windows. One-story, modified hip roof, entrance porch with square blonde brick columns on an enclosed blonde brick balustrade with concrete caps; the porch has been enclosed with windows. Faux stone veneer covers the foundation. 4 X 1 bays. Side Gable Cottage. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 49

JA-0110. (512243) 109 HENRY STREET (continued)

A.

date: Modern

description: One-story, end gable shed with shed roof, enclosed wing on the side. Metal roof. Metal siding. Pier foundation. 2 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, end gable garage. Metal roof. Metal siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

JA-0111. (512244) 107 HENRY STREET, residential

Ginther House

date: c. 1900

description: Large two-story, hip roof house with hip dormers and a corner three-story tower with pyramidal roof and a two-story, three-sided, projecting bay on the side. Asphalt shingle roof. Wide frieze board with modillions. Leaded glass windows on the third story of the tower. Red brick façade. 1/1 windows with rusticated stone sills. Large arched window on the side. One-story, modified hip roof, full length, front porch with Doric columns and pilasters on a wood deck supported by a stone pier foundation. Entrance door has divided transom and sidelights. Cut stone foundation. 4 X 3 bays. Queen Anne style. One Contributing building.

JA-0112. (512245) 105 HENRY STREET, residential

Bird House

date: c. 1910

description: One and one-half-story, end gable house. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows with shutters. One-story, modified hip roof, three-quarter length, front porch with turned posts on an enclosed balustrade. Undivided transom over entrance door. One-story, shed roof, enclosed rear porch. Concrete block foundation. 3 X 3 bays. Gable Front house. Modified. One Non-Contributing building.

A.

date: c. 1910

description: One-story, side gable outbuilding. Asphalt shingle roof. Vertical board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0113. (513116) 709 SAND STREET, residential

Barker House

date: c. 1910

description: One-story, hip roof house. Asphalt shingle roof. Vinyl siding. 1/1 windows with shutters; paired on the front. One-story, shed roof, front porch with Tuscan columns on an

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 50

enclosed molded concrete block balustrade. One-story, shed roof wing on the right. Stone foundation. 6 X 2 bays. One-story Cube house. One Contributing building.

A.

date: c. 1925

description: One-story, end gable garage. Metal roof. Asbestos shingle siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0114. (513117) 104 WILSON STREET, residential

Norman House

date: c. 1910

description: One-story, front facing "L" house with a one-story, gable wing on the rear. Asphalt shingle roof. Two, interior, corbelled brick chimneys. Clapboard siding with frieze and corner boards with simple plinths. Vertical 2/2 windows with shutters. One-story, shed roof, entrance porch with square posts and scrolled brackets. Rock-faced concrete block foundation. 4 X 2 bays. Gabled-Ell house. One Contributing building.

JA-0115. (513119) 108 WILSON STREET, residential

Fisher/Starks House

date: c. 1920

description: One-story, hip roof house with projecting, gable bay on the front. Gable end has diagonal siding. Asphalt shingle roof. Vinyl siding. 1/1 windows. Entrance door has undivided transom. One-story, modified hip roof, front porch with chamfered posts on a wood deck. Small side entrance. One-story, rear porch. Rock-faced concrete block foundation. 3 X 4 bays. Queen Anne Cottage style. One Contributing building.

JA-0116. (513120) 710 WALNUT STREET, residential

Fox House

date: c. 1900

description: Large, two-story, hip roof house with two-story tower on the rear with pyramidal roof. Asphalt shingle roof. Interior corbelled brick chimney. Brackets and dentils in roof eave. Red brick façade. 1/1 and leaded glass windows with rusticated stone lintels and sills. One-story, shed roof, front porch with turned posts on a wood deck supported by a pier foundation. One-story, modified hip roof sunroom on the side that wraps to the rear with red brick façade and modern 9/6 windows. One-story, hip roof wing on the rear that attaches to an enclosed rear entrance. Cut stone foundation. 3 X 3 bays. Queen Anne style. One Contributing building.

A.

date: Modern

description: Two-story, gambrel roof garage/barn. Asphalt shingle roof. Board and batten siding. Concrete block foundation. 1 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 51

JA-0117. (513121) 113 GALLATIN STREET, residential

Morton House

date: c. 1920

description: One-story, hip gable roof house. Metal roof. Two interior, red brick chimneys. Exposed, brick chimney on the front, next to the Tudor Revival style entrance bay. Vinyl siding. 1/1 windows with shutters. Entrance bay is a steep gable and has vergework with a dropped finial in the gable end. One-story, hip roof, rear, enclosed wing on the side wraps around to the rear. Brick foundation. 4 X 4 bays. Tudor Revival style. Modified. One Non-Contributing building.

A.

date: c. 1920

description: One-story, end gable outbuilding. Roll roofing. Exposed rafter tails. German siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

B.

date: c. 1920

description: One-story, jerkinhead garage. Asphalt shingle roof. Exposed rafter tails. Stucco façade and foundation. 1 X 1 bays. Paneled and glazed garage doors. One Non-Contributing building.

JA-0118. (513122) 111 GALLATIN STREET, residential

McKay House

date: c. 1910

description: Large, two-story, hip gable roof house. Two, interior, corbelled brick chimneys. Metal roof. Diagonal siding in gable ends. Modillions in frieze area. Vinyl siding. Modern 1/1 windows. One-story, wraparound porch with turned posts with scroll and cut-out brackets. Cut stone foundation. 2 X 2 bays. Queen Anne style. One Contributing building.

A.

date: c. 1930

description: One-story, end gable garage. Metal roof. Concrete block façade and foundation. Vertical board siding in gable end. 1 X 1 bays. One Contributing building.

JA-0119. (513123) 109 GALLATIN STREET, residential

Dale House

date: c. 1920

description: Two-story, hip gable roof house with the hip portion of the roof in the center and rather small in proportion to the gable portion. Central, interior, corbelled brick chimney. Asphalt shingle roof. Diagonal siding in the gable ends. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with Tuscan columns on an

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 52

enclosed rock-faced concrete block balustrade. Rock-faced concrete block foundation. 3 X 1 bays. "I" house. One Contributing building.

A.

date: c. 1920

description: One-story, end gable garage/outbuilding. Metal roof. Exposed rafter tails. Metal siding. Pier foundation. 2 X 1 bays. One Contributing building.

JA-0120. (513124) 107 GALLATIN STREET, residential

Miller House

date: c. 1945

description: One-story, front facing "L" house: the short projecting bay has a gable roof and the remaining is a hip. Asphalt shingle roof. Red brick, asbestos shingle and wood shingle siding. Variety of windows. Steps and a concrete landing lead to the entrance and have wrought iron railing. Attached garage converted to living space. Brick foundation. 4 X 2 bays. Ranch style. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Metal roof. T-111 siding. Concrete foundation. 2 X 1 bays. One Non-Contributing building.

JA-0121. (513127) 703 SAND STREET, residential

Roush House

date: c. 1925

description: One-story, side gable house with rear gable addition. Asphalt shingle roof. Clapboard siding with frieze and corner boards. 1/1 windows; paired on the front. One-story, shed roof, entrance porch with square columns on a wood deck supported by concrete block foundation. Rock-faced concrete block foundation. 3 X 3 bays. Side Gable Cottage. One Contributing building.

JA-0122. (513128) 701 SAND STREET, church

First Christian Church

date: c. 1895

description: Two-story, front facing "L" church building with three-story, square tower with spire set diagonally on the corner. Asphalt shingle roof. Interior, red brick chimney on the newer wing. Red brick façade. The end gable portion of the building was most likely the original church with the truncated hip roof addition on the west added later. The end gable section has Gothic Revival style stained glass windows with stone sills while the other section has metal casement windows. The second floor of the tower has arched stained glass windows and wooden louvers on the third floor. Addition has asphalt shingle roof, interior brick chimney,

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 53

painted concrete block façade and foundation and metal casement windows. Double entrance doors with metal canopy overhead. Cut stone and concrete foundation. 5 X 3 bays. Gothic Revival style. One Contributing building.

JA-0123. (513130) 108 GALLATIN STREET, residential**Cooper House**date: c. 1915

description: Two-story, hip roof house with hip dormer on front and two-story, square three-sided, projecting bay on the side. Central, interior chimney; exposed, red brick chimney on the side. Metal roof. German siding with frieze and corner boards with caps. Small leaded glass windows on the side and in the dormer; picture windows with leaded glass headers elsewhere. One-story, modified hip roof, three-quarter length, front porch with square rock-faced concrete block columns on an enclosed rock-faced concrete block enclosed balustrade. Undivided transom over entrance door. 3 X 4 bays. Craftsman Four Square type. One Contributing building.

A.date: Modern

description: One-story, end gable garage. Metal roof. Concrete block façade and foundation. 2 X 1 bays. One Non-Contributing building.

JA-0124. (513132) 104 GALLATIN STREET, residential**Harmon House**date: c. 1920

description: One-story, hip roof house. Asphalt shingle roof. Wood shingle and red brick siding; asbestos shingle siding on front and rear porches. Variety of modern windows; windows on main body of house have rusticated concrete lintels and sills. One-story, shed roof, entrance porch with square posts and lattice balustrade. One-story, shed roof, enclosed rear porch. Rock-faced concrete block foundation. 3 X 5 bays. One-story Cube. Modified. One Non-Contributing building.

A.date: Modern

description: One-story, end gable garage. Corrugated metal roof. Corrugated metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0125. (513133) 102 GALLATIN STREET, residential**Lehew House**date: c. 1930

description: One-story, side gable house with large central wall gable on the front. Asphalt shingle roof. Asbestos shingle siding. 3/1 windows. One-story, modified hip roof, entrance

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 54

porch with Tuscan columns on an enclosed balustrade. One-story, hip roof, three-sided, projecting bay on the side. Rock-faced concrete block foundation. 3 X 2 bays. Side Gable Cottage. One Contributing building.

A.

date: Modern

description: Two-story, side gable garage. Asphalt shingle roof. Vinyl siding on second floor; concrete block first floor and foundation. 1/1 windows. Exterior stairway on one end. 3 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: Two-story, side gable play house. Roof covered with fabric awning. T-111 siding. Concrete block foundation. Wraparound deck on second floor. 1 X 1 bays. One Non-Contributing building.

JA-0126. (513134) 611 SAND STREET, residential

Marinez House

date: c. 1930

description: One and one-half-story, side gable house with gable entrance pediment with partial return on end gable portion. Asphalt shingle roof. Exposed, red brick corbelled chimney on front next to entrance. Red brick façade. Modern 1/1 and 4/4 windows. Partial return of entrance pediment overhangs entrance and has scrolled brackets. One-story, shed roof with parapet walls on ends wing on the right. Rock-faced concrete block foundation. 5 X 1 bays. Tudor Revival style. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. T-111 siding. Concrete block foundation. 1 X 2 bays. One Non-Contributing building.

JA-0127. (6151) 5 HENRY STREET, residential

Miller House

date: c. 1940

description: One-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows. One-story, shed roof, full length, front porch with modern square posts on a concrete pad. Large one-story, shed roof, enclosed rear porch/addition. Concrete block foundation. 3 X 4 bays. Minimal Traditional house. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 55

JA-0127. (6151) 5 HENRY STREET, residential (*continued*)

A.

date: c. 1940

description: One-story, side gable garage/barn. Corrugated metal roof. Vertical board siding and concrete block façade. One-story, shed roof, attached open car port on left side. Concrete block foundation. 3 X 1 bays. One Non-Contributing building.

JA-0128. (6153) 1 HENRY STREET, residential

Cedar Apartments

date: c. 1925

description: Believe that originally this was a two-story, front gable house with the large side gable portion added to it as well as a two-story, gable addition on the rear that attaches to a one-story, gable building in the rear. Tall one-story, cross gable building. Asphalt shingle roof. Partial return cornice on end gable portion. Vinyl siding. Modern 1/1 and multi-paned windows. Two-story, end gable portion on the left has a one-story, modified hip roof, full length, front porch with wrought iron posts and slatted balustrade. End gable portion of large side gable has a one-story, gable entrance bay. Another entrance is centered on the side gable long wall. Can not see foundation. 6 X 2 bays. Originally a Gable-Front house. Modified. One Non-Contributing building.

JA-0129. (6154) 605 ASHTON STREET, residential

Cedar House

date: c. 1920

description: Large two-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows; were originally paired on the front and taller. One-story, modified hip roof, three-quarter length front porch with Tuscan columns on an enclosed balustrade. One-story, shed roof, enclosed rear porch. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

JA-0130. (6155) 2 GALLATIN STREET, residential

Moore House

date: c. 1930

description: One-story, cross gable house with one-story, gable addition on the rear. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows with shutters. One-story, shed roof entrance porch with modern round columns on a concrete deck on the left; right side is enclosed. One-story, shed roof, enclosed rear porch. Brick, stone pier and concrete block foundation. 2 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 56

JA-0130. (6155) 2 GALLATIN STREET, residential (continued)

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0131. (6157) 6 GALLATIN STREET, residential

Simmons House

date: c. 1910

description: Two-story, side gable house with very large central wall gable on the front. Metal roof. Brick veneer on first floor of front façade; vinyl siding elsewhere. Vertical 2/2 windows. One-story, flat roof canopy/front porch with wrought iron posts and railing. One-story enclosed rear porch. Concrete block foundation. 3 X 2 bays. Side Gable house. Modified. One Non-Contributing building.

JA-0132. (6158) 8 GALLATIN STREET, residential

Stagg House

date: c. 1910

description: One-story, hip roof house with one-story gable addition on rear and one-story shed roof addition on rear. Asphalt shingle roof. Vinyl siding. Vertical 2/2 and modern 1/1 windows. One-story, shed roof, three-quarter length, front porch with turned posts with scrolled brackets. Pier and concrete block foundation. 3 X 4 bays. One-story Cube. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Roll roofing. Painted plywood siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0133. (6159) 9 GALLATIN STREET, residential

Wells House

date: c. 1955

description: One-story, side gable house. Asphalt shingle roof. Stucco façade and foundation. Metal casement windows. Metal canopy over entrance door and stoop. Minimal Traditional style. One Contributing building.

JA-0134. (61510) 7 GALLATIN STREET, residential

Ewing House

date: c. 1925

description: One and one-half-story, jerkinhead roof house. One-story, gable addition on rear. Partial return cornice. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows; paired. One-

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 57

story, modified hip roof, three-quarter length, front porch with large slightly battered square columns on an enclosed balustrade. Rock-faced concrete block foundation. 3 X 2 bays. Craftsman style. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Metal roof. Metal siding. Concrete block pier foundation. 1 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, gambrel roof outbuilding. Asphalt shingle roof. Painted pressed board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0135. (61511) 5 GALLATIN STREET, residential

Moore House

date: c. 1900

description: Small two-story, side gable house. Central interior corbelled brick chimney. Standing seam metal roof. Clapboard siding over vertical board siding. Vertical 2/2 windows. One-story, flat roof, entrance porch with turned posts with scrolled and cut-out brackets on a wood deck. Stone pier foundation. 3 X 1 bays. "I" house. May have a log interior. One Contributing building.

A.

date: c. 1920

description: One-story, end gable garage. Corrugated metal roof. Exposed rafter tails. Horizontal board siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0136. (61513) 703 ASHTON STREET, residential

Gill House

date: c. 1915

description: One-story, side gable house with one-story, shed roof addition on the rear. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows. One-story, modified hip roof, three-quarter length, front porch with slightly battered square columns on an enclosed balustrade. Molded concrete block foundation on main house; brick foundation on front porch. 3 X 3 bays. Side Gable Cottage. One Contributing building.

A.

date: Modern

description: One-story, flat roof outbuilding. Roll roofing. Pressed board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 58

JA-0137. (61516) 715 ASHTON STREET, residential

Haid House

date: c. 1930

description: One-story, hip roof house with shed roof dormers. Dormers have scalloped shingle siding. Asphalt shingle roof. Terra cotta block façade. 1/1 windows. Recessed porch on corner enclosed with 1/1 windows. Rear porch enclosed. Rock-faced concrete block foundation. 2 X 4 bays. Craftsman style. One Contributing building.

A.

date: Modern

description: One-story, side gable garage. Asphalt shingle roof. Vinyl siding. Two garage bays. One-story, shed roof, open wing on the right. Concrete block foundation. 3 X 1 bays. One Non-Contributing building.

JA-0138. (61518) 10 WILSON STREET, residential

Shockey House

date: c. 1910

description: One and one-half-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with turned posts and slatted balustrade. One-story, shed roof, full length, enclosed rear porch with attached, enclosed, shed roof wing. Concrete block foundation. 3 X 4 bays. Gable-Front house. Modified. One Non-Contributing building.

A.

date: c. 1920

description: One-story, end gable shed. Asphalt shingle roof. Exposed rafter tails. Asbestos shingle siding. Can not see foundation. 1 X 1 bays. One Non-Contributing building.

JA-0139. (61518.1) 12 WILSON STREET, residential

Clem House

date: c. 1910

description: Twin to JA-0138. One and one-half-story, end gable house. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows. One-story, shed roof, three-quarter length, front porch with modern square posts on a concrete pad. One-story, shed roof, full length, enclosed rear porch. Concrete block foundation. 3 X 2 bays. Gable-Front house. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 59

JA-0139. (61518.1) 12 WILSON STREET, residential (continued)

A.

date: Modern

description: One-story, side gable outbuilding. Asphalt shingle roof. Pressed board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0140. (61521) 18 WILSON STREET, residential

date: c. 1925

description: One-story, end gable house. Asphalt shingle roof. Vinyl and T-111 siding. 1/1 and fixed pane windows. Small entrance porch recessed within the roof overhang with square posts and "X" lattice between the posts. One-story, shed roof addition on the rear attaches to a one-story, gable cellar house/addition. Rock-faced concrete block and concrete block foundation. 2 X 3 bays. Gable-Front house. Modified. One Non-Contributing building.

A.

date: 1930

description: One-story, end gable garage with attached, one-story, shed roof, open wing on the right. Asphalt shingle roof. Concrete block façade and foundation. 2 X 2 bays. One Non-Contributing building.

JA-0141. (613135) 11 HENRY STREET, residential

Shadd/Smith House

date: c. 1910

description: Two-story, rear facing "L" house. Metal roof. Red brick, end chimneys. Vinyl siding. Vertical 2/2 windows with shutters. One-story, modified hip roof, three-quarter length, front porch with square columns on an enclosed balustrade. Transom over entrance door. Cut stone foundation. 3 X 2 bays. "I" house. One Contributing building.

A.

date: c. 1930

description: Two-story, hip roof garage/apartment. Asphalt shingle roof. Asbestos shingle siding on the second floor; concrete block first floor and foundation. Metal casement windows with metal canopies. Central entrance door on first floor with metal canopy. 3 X 2 bays. One Contributing building.

JA-0142. (613136) 9 HENRY STREET, residential

Dunlap House

date: c. 1915

description: Large two-story, hip roof house. Asphalt shingle roof. Vinyl siding. Vertical 2/2 and 1/1 windows; front porch windows have a narrow upper sash. Transom over entrance door.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 60

One-story, shed roof, three-quarter length, front porch with square posts on an enclosed balustrade. One-story, shed roof, full length, rear addition. Concrete block foundation. 3 X 2 bays. Craftsman Four Square type. Modified. One Non-Contributing building.

A.

date: c. 1915

description: One-story, end gable shed with attached shed roof, enclosed wing on the left. Corrugated metal roof. German siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0143. (613137) 7 HENRY STREET, residential

Smith House

date: c. 1920

description: One-story, truncated hip roof house. Asphalt shingle roof. Vinyl siding. Variety of modern windows. One-story, modified hip roof, entrance porch with Tuscan columns on an enclosed rock-faced concrete block balustrade. Rock-faced concrete block foundation. 3 X 3 bays. One-story Cube. Modified. One Non-Contributing building.

JA-0144. (613138) 608 SAND STREET, residential

Hartley House

date: c. 1900

description: Large two-story, side facing "T" house with one-story, side gable wing on the west. Two interior corbelled brick chimneys. Asphalt shingle roof. Vinyl siding. Vertical 2/2 and modern 1/1 windows with shutters. Two-story tall square columns on front porch; wing has square columns also. Narrow entrance door on the side with a divided transom. Rock-faced concrete block foundation. 5 X 2 bays. Gabled-Ell house. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. One garage bay. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0145. (613139) 14 GALLATIN STREET, residential

Cedar House

date: c. 1925

description: One-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 and slider windows with shutters. One-story, shed roof, entrance porch with Tuscan columns on an enclosed molded and rock-faced concrete block balustrade. One-story, shed roof, enclosed rear porch. Foundation presumed to be molded and/or rock-faced concrete block. 3 X 3 bays. One-story Cube. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 61

JA-0145. (613139) 14 GALLATIN STREET, residential (*continued*)

A.

date: c. 1930

description: One-story, side gable outbuilding with attached, shed roof, enclosed wing on the rear. Corrugated metal roof. Asbestos shingle siding. Pier foundation. 2 X 1 bays. One Contributing building.

JA-0146. (613140) 12 GALLATIN STREET, residential

Taylor House

date: c. 1925

description: One-story, front facing "L" house. Asphalt shingle roof. Vinyl siding and faux stone veneer façade. Modern metal windows with shutters. Shed roof, entrance porch with wrought iron posts and railing on a concrete deck. Rock-faced concrete block foundation; concrete block on front porch. 3 X 2 bays. Gabled-Ell house. Modified. One Non-Contributing building.

A.

date: c. 1935

description: One-story, end gable outbuilding. Asphalt shingle roof. Weatherboard siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

B.

date: c. 1935

description: One-story, end gable barn/outbuilding. Asphalt shingle roof. Metal siding and horizontal board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0147. (613141) 10 GALLATIN STREET, residential

Brown House

date: c. 1910

description: Two-story, front facing "L" house. Asphalt shingle roof. T-111 and clapboard siding with frieze and corner boards. Modern multi-paned windows; many of the window openings have been downsized. One-story, modified hip roof, front porch with gable pediment and it extends out to the north to form a carport; supported by non-original square posts. Cut stone foundation. 2 X 2 bays. Gabled-Ell house. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 62

JA-0147. (613141) 10 GALLATIN STREET, residential (continued)

A.

date: c. 1920

description: One-story, end gable barn/outbuilding. Asphalt shingle roof. Exposed rafter tails. Vertical board and painted plywood siding. Six pane window. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0148. (613142) 21 GALLATIN STREET, residential

Corley House

date: c. 1920

description: One-story, front facing "L" house. Asphalt shingle roof. Asbestos shingle siding. Modern 1/1 windows with shutters. One-story, modified hip roof, front porch in the corner of the ell has been fully enclosed with T-111 siding and windows. One-story, side gable wing/addition on the southeast in the rear. Stone pier and brick foundation. 3 X 3 bays. Gabled-Ell house. One Non-Contributing building.

A.

date: Modern

description: One-story, side gable garage. Asphalt shingle roof. Concrete block façade and foundation. Two garage bays and man door on front. 3 X 1 bays. One Non-Contributing building.

JA-0149. (613143) 17 GALLATIN STREET, residential

Radzyninski/Umpheby House

date: c. 1890

description: Large two-story, front facing "L" house. Two interior chimneys. Standing seam metal roof. Clapboard siding with frieze and corner boards. Vertical 2/2 windows. One-story front porch with turned posts. Stone pier foundation. 5 X 2 bays. Gabled-Ell house. One Contributing building.

A.

date: c. 1900

description: One-story, end gable outbuilding. Standing seam metal roof. Asbestos shingle siding; board and batten siding in gable ends. Pier foundation. 1 X 1 bays. One Contributing building.

B.

date: c. 1900

description: One-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays. Falling down. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 63

JA-0150. (613144) 15 GALLATIN STREET, residential

Sturm House

date: c. 1920

description: One-story, hip roof house with one-story, shed roof addition on the south side. Asphalt shingle roof. Clapboard siding with frieze and corner boards. Wood louver windows; with shutters on the front. One-story, shed roof canopy supported by wrought iron posts over the entrance. Rock-faced concrete block foundation. 4 X 2 bays. One-story Cube. One Contributing building.

A.

date: c. 1920

description: One and one-half-story, end gable barn/outbuilding. Asphalt shingle roof. Narrow vertical board siding. Vertical 2/2 window. Pier foundation. 1 X 1 bays. One Contributing building.

B.

date: c. 1930

description: Two-story, hip roof garage/apartment. Asphalt shingle roof. Weatherboard siding on the second floor; parged concrete block first floor and foundation. Horizontal 2/2 windows on the second floor. 2 X 1 bays. One Contributing building.

JA-0151. (613145) 13 GALLATIN STREET, residential

Cozart House

date: c. 1920

description: Two-story, low pitch front gable house with attached, two-story, shed roof addition on the rear and attached to that is a one-story, shed roof wing/addition. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, enclosed, full length front porch. Concrete block foundation. 3 X 3 bays. Gable-Front house. Modified. One Non-Contributing building.

A. 13 1/2 GALLATIN STREET, residential

date: c. 1930

description: One-story, end gable house with attached one-story, shed roof addition on the right. Asphalt shingle roof. Concrete block and vinyl siding façade. Metal casement windows. Small deck on the front operates as entrance. Concrete block foundation. 2 X 2 bays. One Non-Contributing building.

JA-0152. (613146) 11 GALLATIN STREET, residential

Cozart House

date: c. 1930

description: One-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows. One-story, modified hip roof, entrance porch with square columns on brick

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 64

piers and an enclosed terra cotta block balustrade. One-story, shed roof, enclosed rear porch. Concrete block foundation. 3 X 3 bays. One-story Cube. One Contributing building.

A.

date: Modern

description: One-story, side gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0153. (613147) 710 SAND STREET, residential

Shockey House

date: c. 1880

description: Very large two-story, hip roof, rear facing "L" house. Asphalt shingle roof. Aluminum siding. Vertical 2/1 windows. One-story, flat roof, entrance porch with modern Doric columns on the first floor; second floor has spindled roof balustrade with turned newel posts and is as a small balcony. One-story, modified hip roof, rear porch has been fully enclosed. One-story, shed roof, enclosed addition on the side. Stone and concrete block foundation. 3 X 4 bays. Gabled-Ell house. One Non-Contributing building.

JA-0154. (613149) 26 WILSON STREET, residential

Ruben House

date: c. 1910

description: Large two-story, hip roof house. Two interior corbelled brick chimneys. Standing seam metal roof. Vinyl siding. Wood 1/1 windows. One-story, shed roof, entrance porch with modern Doric columns on a wood deck. Two entrance doors/duplex. Block foundation. 4 X 2 bays. Early Colonial Revival style. One Contributing building.

JA-0155. (613150) 24 WILSON STREET, residential

Cummings House

date: c. 1920

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Modern 1/1 and multi-paned windows with shutters. One-story, shed roof, entrance porch with turned posts on a concrete deck. One-story, shed roof, enclosed rear porch added on to. Rock-faced concrete block foundation. 3 X 3 bays. Side Gable Cottage. Modified. One Non-Contributing building.

JA-0156. (613151) 22 WILSON STREET, residential

Stone House

date: c. 1920

description: One and one-half-story, cross gable house with gable wall dormer on the front. Modern metal roof. Vinyl siding. One-story, shed roof, three-quarter length, enclosed front porch. One-story, shed roof, enclosed rear porch. Concrete block foundation. 3 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 65

JA-0156. (613151) 22 WILSON STREET, residential (*continued*)

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0157. (613152) 20 WILSON STREET, residential

Hinkle House

date: c. 1915

description: Large two-story, front facing "L" house. Front projecting bay is three-sided and has a picture window with a leaded glass header on the second floor. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, entrance porch with turned posts on an enclosed balustrade. One-story, modified hip roof, rear enclosed porch with modern deck/entrance attached to it. Concrete block foundation. 3 X 1 bays. Gabled-Ell house. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle and roll roofing. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, hip roof outbuilding. Roll roofing. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0158. (71473) 602 ASHTON STREET, residential

Frum House

date: c. 1900

description: Large two-story, hip roof house with two-story, projecting, three-sided, gable bay on the front. Interior corbelled brick chimney. Asphalt shingle roof. Asbestos shingle siding. Wood 1/1 and vertical 2/2 windows. Small hip roof canopy supported by a large knee brace over entrance door. One-story, gable, entrance bay on the side with a partial return cornice. One-story, modified hip roof addition/porch on the rear. Stone foundation. 3 X 3 bays. Gabled-Ell house. One Contributing building.

JA-0159. (71539) 606 ASHTON STREET, residential

Skeen House

date: c. 1910

description: One-story, front gable house with projecting gable bays on each side: the west side bay is three-sided; the east side bay is square. Asphalt shingle roof. Vinyl siding. Wood 1/1

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 66

windows with decorative surrounds; picture window with leaded glass header in the west side bay. One-story, modified hip roof, three-quarter length front porch with Tuscan columns. One-story, gable enclosed rear porch. Gable addition on rear. Cut stone foundation. 2 X 5 bays. Gable-Front house. One Contributing building.

JA-0160. (71540) 608 ASHTON STREET, residential**King House**date: c. 1910

description: Two-story, gambrel roof house with gable dormers on the side with pediments. Asphalt shingle roof. Partial return cornice. Gable end has a Palladian window and wood scalloped shingles. Vinyl siding. 1/1 wood windows; picture window with leaded glass header on front porch. One-story, modified hip roof, front porch with Tuscan columns. Entrance door has undivided transom. One-story, shed roof wing on the left. Cut stone foundation. 3 X 2 bays. Dutch Colonial Revival style. One Contributing building.

JA-0161. (71541) 614 ASHTON STREET, residential**Gladden House**date: c. 1915

description: Large two-story, end gable house with two-story, gable, projecting bay on the west side. Central interior chimney. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows with shutters; picture window with leaded glass header on the front porch. One-story, modified hip roof, wraparound porch with central gable pediment: enclosed on the side; remainder has turned posts with cut-out brackets and slatted balustrade. One-story, shed roof, enclosed rear porch. Two-story addition on the rear with a one-story open porch attached to it. Exterior stair and second story deck on the rear. Rock-faced concrete block foundation. 2 X 3 bays. Gable-Front house. Modified. One Non-Contributing building.

A.date: c. 1915

description: One-story, end gable cellar house. Interior chimney. Standing seam metal roof. Vinyl siding. Stone foundation. 1 X 1 bays. One Non-Contributing building.

B.date: c. 1915

description: One-story, shed roof outbuilding. Corrugated metal roof. Vertical board siding. Cut stone foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 67

JA-0162. (71541.1) 610 ASHTON STREET, residential

Gladden House

date: c. 1930

description: Small one-story, side gable house. Asphalt shingle roof. Asbestos shingle siding. Wood 1/1 windows. Small shed roof over entrance door. Block foundation. 3 X 1 bays. Side Gable Cottage. One Contributing building.

A.

date: c. 1930

description: One-story, end gable garage. Asphalt shingle roof. Glazed terra cotta block façade and foundation. 1 X 1 bays. One Contributing building.

JA-0163. (71542) 700 ASHTON STREET, residential

Porter House

date: c. 1925

description: Two-story, cross gable house with gable dormers on the front. Central interior corbelled brick chimney. Metal roof. Vinyl siding. Vertical 2/2, 1/1 and novelty windows. End gable portion of house projects centrally and is flanked by shed roof porches. Each porch has Tuscan columns with entasis. Covered foundation. 3 X 3 bays. Colonial Revival style. One Contributing building.

A.

date: c. 1925

description: One-story, end gable garage. Metal roof. German siding with corner boards. Garage door is paneled below and has divided glazing above. Block foundation. 2 X 2 bays. One Contributing building.

JA-0164. (71545) 708 ASHTON STREET, residential

Bogges House

date: c. 1915

description: Large two-story, hip roof house. Asphalt shingle roof. Central interior corbelled brick chimney. Clapboard siding with frieze and corner boards. Vertical 2/2 windows with simple surrounds. One-story, modified hip roof, full length front porch with square rock-faced concrete block columns on an enclosed rock-faced concrete block balustrade. Two bay car port attached on the east. One-story, shed roof, enclosed rear porch; a partially screened-in, open shed roof porch is attached. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

A.

date: Modern

description: One-story, shed roof outbuilding. Corrugated metal roof. Plywood siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 68

JA-0164. (71545) 708 ASHTON STREET, residential (continued)

B.

date: c. 1915

description: One-story outbuilding. Metal roof. Clapboard siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0165. (71546) 710 ASHTON STREET, residential

Hennessy House

date: c. 1920

description: One-story, side gable house with jerkinhead ends and an off-set wall gable on the west. Asphalt shingle roof. Partial return cornice. Vinyl siding. Vertical 2/2 windows. One-story, modified hip roof, three-quarter length, front porch with square posts on an enclosed balustrade. Concrete block foundation. 3 X 2 bays. Side Gable Cottage. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Metal roof. Metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0166. (71549) 718 ASHTON STREET, residential

Black House

date: c. 1900

description: One-story, side gable house with rear gable addition. Standing seam metal roof. Vinyl siding. Vertical 3/1 windows. One-story, shed roof, entrance porch with turned posts with scroll brackets and decorative trim. One-story rear porch has been enclosed. Stone pier foundation. 3 X 5 bays. Center Passage house. One Contributing building.

A.

date: c. 1930

description: One-story, end gable garage. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0167. (71550) 722 ASHTON STREET, residential

Bowman House

date: c. 1920

description: One-story, hip roof house with large one-story, shed roof addition on the rear. Asphalt shingle roof. Clapboard siding with frieze and corner boards with caps. Modern 1/1 windows with shutters. One-story, modified hip roof, entrance porch with turned posts with scrolled brackets on a wood deck. Pier foundation. 3 X 5 bays. One-story Cube. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 69

JA-0167. (71550) 722 ASHTON STREET, residential (continued)

A.

date: c. 1920

description: One-story, shed roof outbuilding with attached, shed roof, partially enclosed wing on the rear. Metal roof. Metal and horizontal board siding. Pier foundation. 1 X 2 bays. One Contributing building.

JA-0168. (71551) 800 ASHTON STREET, residential

Tidd House

date: c. 1915

description: Large two-story, hip roof house. Single family home converted to a duplex. Asphalt shingle roof. Clapboard siding with frieze and corner boards. 1/1, horizontal 2/2 and 12/1 windows. Two-story, corner front porch enclosed for its full height and incorporated into the main body of the house to create the second entrance for the duplex conversion. One-story, shed roof, enclosed rear porch. Parged and modern stone veneer foundation. 4 X 1 bays. Craftsman Four Square type. One Contributing building.

JA-0169. (71552) 802 ASHTON STREET, residential

Nicholas House

date: c. 1920

description: Two-story, cross gable house. Interior corbelled brick chimney. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, end gable, enclosed entrance bay. One-story, shed roof, car port on the side. Rock-faced concrete block foundation. 2 X 2 bays. Tudor Revival style. Modified. One Non-Contributing building.

JA-0170. (71553) 804 ASHTON STREET, residential

Ashby House

date: c. 1920

description: One-story, hip roof house. Modern metal roof. Clapboard siding with frieze and corner boards. Modern 1/1 windows; some of the openings have been downsized and infilled. One-story, shed roof, three-quarter length, front porch with non-original square posts and lattice balustrade. One-story, shed roof, enclosed rear porch/addition. Pier foundation. 4 X 2 bays. One-story Cube. One Contributing building.

JA-0171. (71554) 806 ASHTON STREET, residential

Stephens House

date: c. 1925

description: Two-story, end gable house with gable dormer on the side. Exposed rafter tails. Asphalt shingle roof. Painted terra cotta block and rock-faced concrete block façade and foundation; there is a rock-faced concrete block belt course. 4/1 window and T-111 siding in

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 70

gable end. Modern 1/1 windows elsewhere. Two doors and picture window on front. Dormer has wood shingles and exposed rafter tails. One-story, open rear porch. 3 X 2 bays. Gable-Front house. One Contributing building.

JA-0172. (71555) 808 ASHTON STREET, residential**Warner House**date: c. 1910

description: One-story, hip roof house with hip dormers. Interior corbelled brick chimney. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, three-quarter length front porch with square posts and slatted balustrade. Front corners of the house are diagonal. Rock-faced concrete block foundation. 4 X 4 bays. One-story Cube house. One Contributing building.

A.date: c. 1910

description: One-story, end gable outbuilding with attached, shed roof, enclosed wing on the left. Asphalt shingle roof. German siding. 1/1 and vertical 2/2 windows. Pier foundation. 2 X 2 bays. One Contributing building.

JA-0173. (71556) 810 ASHTON STREET, residential**Gould House**date: c. 1920

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, three-quarter length front porch with non-original square posts and slatted balustrade. Rock-faced concrete block foundation. 3 X 2 bays. Gable-Front house. Modified. One Non-Contributing building.

JA-0174. (71557) 816 ASHTON STREET, residential**McKay House**date: c. 1915

description: One-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows with metal canopies. One-story front porch within roof overhang has been fully enclosed. One-story, shed roof, enclosed rear porch. Rock-faced concrete block and parged foundation. 3 X 5 bays. One-story Cube. Modified. One Non-Contributing building.

A.date: Modern

description: Two-story, end gable house. Asphalt shingle roof. Vinyl siding on the second floor; concrete block façade and foundation on first floor. Exterior stair on the left leads to a second story deck/entrance. 2 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 71**JA-0175. (812126) 217 ANN STREET, residential****Price House**date: c. 1920

description: One-story, hip roof house with hip dormer. Asphalt shingle roof. Molded concrete block façade and foundation. Small fixed pane windows. One-story, enclosed rear porch. One-story, modified hip roof, front porch has been fully enclosed with siding and windows. 3 X 6 bays. Craftsman Bungalow type. One Contributing building.

JA-0176. (812127) 215 ANN STREET, church**First Baptist Church**date: c. 1876

description: Very tall one-story, end gable church building with octagonal tower on the roof with a spire. The main church connects with a hyphen to a one-story, side gable addition on the south side. Asphalt shingle roof. Vinyl siding. 4/4 arched windows – original; the addition has multi-paned windows. Large two-story tall gable entrance portico with two-story tall Tuscan columns. Block foundation. 10 X 5 bays. Classical Revival style. One Non-Contributing building.

JA-0177. & JA-177A. (812128) 212 HENRIETTA STREET, community center**Ravenswood Community Center/McIntosh House**date: c. 1938/c. 1890

description: Two-story, flat roof, community building with stepped parapet with concrete cap on the front. Red brick façade. Metal casement windows. Red brick pilasters with concrete caps define the entrance bay on the front and rear. "N.Y.A." and a blonde brick diamond are outlined in the cornice area on the front. Double entrance doors with a end gable canopy. Raised brick "loggia" with concrete steps up serves as entrance. Second story brick hyphen connects community building to building next door which is a very elaborate two and one-half-story, hip gable roof building with gable dormers and a three-story, corner tower with a pyramidal roof. Tower has wood shingle siding on the upper most level and 12/1 windows. Dormers have partial return cornices with the returns supported by brackets which extend down into the primary cornice/frieze area. Connected building has an asphalt shingle roof. Central dormer on the front has tripartite 12/1 windows with an arched decorative cartouche hood. There is a two and one-half-story, three-sided, projecting bay on the right side with a dormer on the upper level with a round-headed arched windows with a divided upper sash. The primary frieze/cornice has decorative squares and scallops with end brackets below the dormers. Red brick façade. 1/1 windows with stone lintels and sills. One-story, flat roof, front porch with arcaded arched openings. Roof balustrade of wrought iron with brick square newel posts on front porch. Stone and concrete foundation. "NYA" building is 3 X 4 bays; connecting building is 5 X 4 bays. Art

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 72

Deco style for Community Center; Colonial Revival style for house. Two Contributing buildings.

JA-0178. (812151) 502 SYCAMORE STREET, residential**Chambers House**date: c. 1880

description: Large two-story, hip roof house with one-story, mansard roof wing. Asphalt shingle roof on hip portion; slate roof on mansard. Roof cresting. Wide frieze with brackets on hip portion. Four double chimneys on hip roof portion; one chimney with three chimney pots on mansard roof second. Painted brick façade. 1/1 recessed windows with brick lintels and stone sills on hip portion; gable dormers with 1/1 windows on mansard portion. One-story, flat roof entrance canopy with metal roof balustrade supported by decorative metal posts and railing with iron newel posts. One-story, modified hip roof, enclosed, full length rear porch that extends to the mansard section and is fully enclosed for that section. Mansard section connects to a two bay garage on the west. Cut stone foundation. 8 X 2 bays. Originally the house was built with a mansard roof with dormers on the current hip roof portion. Italianate style/Second Empire style. One Contributing building.

JA-0179. (812153) 505 MULBERRY STREET, residential**Ritz House**date: c. 1920

description: Large two-story, hip roof house with central end gable dormer on the front. Asphalt shingle roof. Dormer has scalloped shingle siding. Roman brick façade. Modern 1/1 windows. Two-story, modified hip roof, fully enclosed front porch with recessed entrance bay. Front porch enclosed for two stories and has Roman brick and scalloped shingle siding and multi-paned 8/8 windows. Two-story, gable open porch on the side with modern square posts and picket fence style balustrade. Rock-faced concrete block foundation. 5 X 3 bays. Pyramidal house type. One Contributing building.

JA-0180. (812153.1) 213 HENRIETTA STREET, residential**Chambers House**date: c. 1925

description: Two-story, front gable house with flanking shed roof dormers on the side elevations. Exposed red brick chimney on the front between the dormers. Metal roof. Asbestos shingle siding on gable ends and on dormers; red brick elsewhere. 6/1 windows in gable end. One-story, shed roof, full length, front porch with square brick columns and a slatted balustrade. Small side entrance on the rear. Rock-faced concrete block foundation. 2 X 3 bays. Gable Front house. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 73

JA-0181. (812154) 216 HENRY STREET, residential

Stark House

date: c. 1925

description: Two-story, side gable house with central, end gable dormer on the front. Knee braces in the gable ends. Dormer has square and fish scale shingle siding and paired, 4/1 windows. Asphalt shingle roof. Exposed brick and terra cotta tile chimney on the side. Square wood shingle siding in the gable ends; terra cotta tile façade elsewhere. Vertical 4/1 windows; many are paired. One-story, shed roof, full length, front porch within roof overhang has square brick columns on an enclosed terra cotta tile balustrade with concrete cap and one end of the porch is enclosed with modern windows. One-story, enclosed rear porch. Concrete water table course. Rock-faced concrete block foundation. 4 X 4 bays. Craftsman Bungalow style. One Contributing building.

A.

date: c. 1925

description: One-story, end gable garage. Asphalt shingle roof. Roman brick and red brick façade. Rock-faced concrete block foundation. 1 X 1 bays. One Contributing building.

B.

date: c. 1950

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 2 X 1 bays. One Contributing building.

C.

date: Modern

description: Gazebo. One Non-Contributing building.

D.

date: c. 1925

description: One-story, shed roof outbuilding. Roll roofing. Vertical board siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0182. (812156) 507 MULBERRY STREET, residential

Varney House

date: c. 1900

description: One and one-half-story, front gable house. Asphalt shingle roof. German siding with frieze and corner boards. Vertical 2/1 windows. One-story, shed roof, full length canopy over first floor supported by wrought iron posts. Picture window on front porch. First floor on the front has T-111 siding and faux stone veneer. Block foundation. 2 X 1 bays. Gable-Front house. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 74

JA-0183. (812156(A) 210 HENRY STREET, residential

Varney House

date: c. 1900

description: One-story hip gable roof house with gable dormer. Central interior corbelled red brick chimney. Asphalt shingle roof. Vinyl and clapboard siding. 1/1 and picture windows with leaded glass headers and smaller leaded glass windows. One-story, wraparound porch with Tuscan and square columns and a slatted balustrade. One-story addition on rear. Rock-faced concrete block foundation. 6 X 3 bays. Queen Anne Cottage style. One Contributing building.

JA-0184. (912129) 400 MULBERRY STREET, residential

Floto House

date: c. 1915

description: One-story, rear facing "L" house. Gable dormers on the front with gingerbread with dropped finials in gable ends. Exposed corbelled red brick end chimney. Asphalt shingle roof. Vinyl siding. 1/1 windows with simple surrounds with decorative trim at the top two corners and shutters. One-story, modified hip roof, three-quarter length, front porch with turned posts with scrolled and cut-out brackets. One-story, gable, entrance porch on the side with turned posts with scrolled and cut-out brackets and a spindled balustrade. Rock-faced concrete block foundation. 3 X 5 bays. Gabled-Ell house. One Contributing building.

A.

date: c. 1915

description: One-story, end gable outbuilding. Metal roof. Clapboard siding with corner boards. 6/6 original window. Pier foundation. 1 X 1 bays. One Contributing building.

B.

date: c. 1930

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. Asbestos shingle siding in gable end. 2 X 1 bays. One Contributing building.

JA-0185. (912130) 207 ANN STREET, residential

Floto House

date: c. 1925

description: Two-story, side gable house. Asphalt shingle roof. Partially engaged end corbelled red brick chimney. Knee braces in the gable ends. Clapboard siding with frieze and corner boards. 1/1 windows with simple surrounds. One-story, modified hip roof, full length, front porch with square brick columns and an enclosed brick balustrade with concrete caps. One-story rear porch. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 75**JA-0186. (912131) 205 ANN STREET, residential****Aselson House**date: c. 1920

description: Two-story, side gable house with large central end gable dormer on the front. Knee braces in the dormer and on the gable ends. Asphalt shingle roof. One exposed concrete block end chimney; one engaged corbelled red brick chimney. Red brick façade. 1/1 windows. One-story, shed roof, full length, front porch within roof overhang with square brick columns and square posts on brick piers with an enclosed brick balustrade with concrete cap. One-story, shed roof, rear porch. Rock-faced concrete block foundation with concrete belt course as a cap. Craftsman Bungalow type. One Contributing building.

A.date: Modern

description: One-story, side gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0187. (912132) WALNUT STREET, church**Grace Episcopal Church**date: c. 1900

description: Tall one-story, end gable church building with large square three-story tower on the west side with a cupola with trefoil topped openings in it. Asphalt shingle roof; tower has slate roof. Clapboard siding with frieze and corner boards. Gable ends and tower has roof brackets. Gothic Revival style stained glass windows; metal casement windows on rear most addition. One-story, gable addition on the rear. One-story, double gable wing on the west with a one-story, hip roof, entrance bay with paired square posts. Block foundation. 3 X 8 bays. Gothic Revival style. One Contributing building.

JA-0188. (912133) 208 HENRIETTA STREET, residential**McNeeley House**date: c. 1920

description: Large two-story, hip roof house with hip dormers. Red clay tile roof with cresting. Engaged corbelled red brick end chimney. Clapboard siding with frieze and corner boards; dentiling in frieze. 6/1 windows; paired on the front. Two-story, pedimented portico with paired Ionic columns: spindled balustrade on second floor; first floor has square brick columns flanked by Ionic posts and an enclosed brick balustrade with concrete cap. One-story, hip roof, three-sided, projecting bay on the side. Brick and concrete foundation. Craftsman Four Square type with Colonial Revival style details. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 76

JA-0188. (912133) 208 HENRIETTA STREET, residential (continued)

A.

date: c. 1920

description: One-story, end gable garage. Metal roof. Aluminum siding. Concrete foundation. 1 X 3 bays. One Contributing building.

JA-0189. (912134) 206 HENRIETTA STREET, residential

Pitthan House

date: c. 1920

description: One-story, cross gable house with three-sided, projecting, gable bay on the end. Exposed painted brick end chimney. Asphalt shingle roof. Partial return cornice. Clapboard siding with frieze and corner boards. 6/6, 4/4 and 1/1 windows. Ribbon of tripartite windows on the front with each bay separated by Tuscan pilasters. One-story, flat roof entrance porch with paired square posts. Block foundation. 6 X 2 bays. Colonial Revival style. One Contributing building.

A.

date: c. 1920

description: One-story, gable outbuilding. Asphalt shingle roof. Exposed rafter tails. Horizontal board siding. Six pane windows. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0190. (912136) 202 HENRIETTA STREET, residential

Williams House

date: c. 1910

description: Two-story, front facing "L" house. Asphalt shingle roof. Partial return cornice. First story of front project bay is three-sided and has gingerbread with a dropped finial at each corner. Vinyl siding. Wood 1/1 windows with surrounds with rosette corner blocks. One-story, modified hip roof, front porch in corner of ell with turned posts with scrolled brackets and chisel cut decorative trim with dropped finials. Undivided transom over entrance door. Block foundation. 3 X 2 bays. Folk Victorian style. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 77

JA-0191. (912137) 200 HENRIETTA STREET, residential

Rauh House

date: c. 1873

description: Large two-story, hip roof house. Asphalt shingle roof. Vinyl and clapboard siding with frieze and corner boards. Wood 1/1 windows with shutters. One-story, modified hip roof, full length, front porch: right side projects, is three-sided, is enclosed and has a gable pediment; left side has turned posts with scrolled and cut-out brackets and slatted balustrade. One-story, shed roof wing/addition on the right. Concrete block foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

JA-0192. (912157) 209 HENRIETTA STREET, residential

Clarkson/McKinley/Blake House

date: c. 1895

description: Large two-story, cross hip roof house with attached one and one-half-story, mansard roof wing. Interior corbelled red brick chimney with chimney pots. Asphalt shingle roof. Red brick façade. 1/1 windows with rusticated stone lintels and sills. One-story, modified hip roof front porch with turned posts with scrolled brackets. Rear section of ell has been enclosed for two stories: the second story has fish scale shingles; the first story has non-original brick façade. Attached to this addition is a one-story, modified hip roof, entrance porch/wing with fish scale shingles and a shingled balustrade. Rock-faced concrete block foundation. 3 X 3 bays. Gabled-Ell house. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0193. (912158) 504 MULBERRY STREET, residential

Clarkson House

date: c. 1925

description: Two-story, side gable house with a wall gable on the front. Asphalt shingle roof. Vinyl siding. Original 6/6 and modern 1/1 windows. One-story, end gable entrance porch with square columns on a wood deck. Block foundation. 2 X 2 bays. Colonial Revival style. One Contributing building.

JA-0194. (912159) 207 HENRIETTA STREET, residential

Fox House

date: c. 1885

description: Large two-story, hip roof house with a historic two-story gable shed roof addition on rear with clapboard siding. Asphalt shingle roof. Red brick façade on original portion;

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 78

clapboard siding on addition. Round-headed arched vertical 2/2 windows with shutters on brick portion; vertical 2/2 windows with simple surrounds on addition. One-story, modified hip roof, three-quarter length, front porch with turned posts and pilasters with scroll brackets on a wood deck. Stone foundation. 3 X 3 bays. Italianate style. One Contributing building.

JA-0195. (912160) 205 HENRIETTA STREET, residential

Chaffin House

date: c. 1890

description: Large two-and one-half-story, front facing "L" house with wall gable on the south gable end. Three-sided projecting bays on the south gable end on the upper stories with stepped support below the bay. Dentiled frieze board with brackets. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows with shutters. One-story, modified hip roof, front porch in corner of ell with fat turned posts and a spindled balustrade. One-story, hip roof, three-sided projecting bay on the front gable bay. Stone foundation. 4 X 2 bays. Gabled-Ell house. One Contributing building.

A.

date: c. 1920

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Original paneled garage doors. Concrete foundation. 2 X 1 bays. One Contributing building.

JA-0196. (912162) 208 HENRY STREET, residential

White House

date: c. 1910

description: Two-story, side facing "T" house with large two-story, shed roof addition on rear and a one-story, gable wing on the rear; the wing on the rear has the same details as the front of the house. Asphalt shingle roof. Front gable bay projects and has scrolled brackets with dropped finials at each corner on the second floor; the second floor overhangs the first a little and is flared. Vinyl siding. 1/1 and picture windows with leaded glass headers in the gable bay. One-story, modified hip roof, entrance porch with square posts with cut-out brackets and decorative trim with dropped finials. Rock-faced concrete block foundation. 2 X 4 bays. Folk Victorian style. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 79

JA-0197. (912163) 206 HENRY STREET, residential

Mandrake House

date: c. 1900

description: Large two-story, cross hip roof house with gable pediment on front projecting, three-sided bay and a two-story, shed roof addition on the rear with a one-story, modified hip roof, enclosed entrance addition attached to that. Exposed brick chimney on the rear. Standing seam metal roof. Red brick façade on front; vinyl siding on rear; fish scale shingles on front gable end. 1/1 windows with rusticated stone lintels and smooth stone sills. One-story, modified hip roof, front porch with large square brick columns and an enclosed brick balustrade with concrete cap. Large scrolled brackets on front gable bay with dropped finials. Stone foundation. Gabled-ell house. One Contributing building.

A.

date: c. 1950

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 1 X 1 bays. One Contributing building.

JA-0198. (912164) 202 HENRY STREET, residential

Woodburn House

date: c. 1900

description: Large two-story, hip roof house with a two-story, round bay on south corner with pyramidal roof. Interior corbelled red brick chimney. Dentiled frieze board with brackets. Asphalt shingle roof. Red brick façade. 1/1 windows with smooth stone lintels and sills. Openings on the first floor of the corner bay are as tall as doors. One-story, modified hip roof, wraparound front porch curves on corner bay and has turned posts with scrolled and cut-out brackets, decorative trim with dropped finials and a dentiled frieze board and spindled balustrade. Divided transom over entrance door. One-story, enclosed rear porch. Stone foundation. 3 X 2 bays. Queen Anne style. One Contributing building.

A. 204 HENRY STREET, residential

date: c. 1930

description: Two-story, hip roof garage/apartment. Asphalt shingle roof. Asbestos shingle siding on the second floor; concrete block first floor and foundation. Modern and metal casement windows. 3 X 2 bays. One Contributing building.

JA-0199. (912165) 200 HENRY STREET, church

Our Savior Evangelical Lutheran Church

date: c. 1928

description: Tall one-story, end gable church building with stepped parapet on the front with concrete cap and a square tower with pyramidal roof on the front south corner. Cross gable bay

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 80

on the rear. Asphalt shingle roof. Brick basketweave cartouche in front. Blonde brick façade. Gothic Revival style stained glass windows; tripartite round-headed stained glass windows on the front above the entrance. Entrance is a brick arched opening with a stepped parapet with concrete cap and cheek walls of blonde brick with concrete cap. One-story, shed roof entrance bay on the side. Brick water table course. Brick foundation. 3 X 7 bays. Gothic Revival style. One Contributing building.

JA-0200. (1012138) 400 WALNUT STREET, residential

Shingleton House

date: c. 1905

description: Large two-story, hip roof house with one-story, gable addition on the west side. Central interior corbelled red brick chimney. Modern metal roof; similar to batten seam. Clapboard siding. Modern 1/1 windows with shutters. One-story, modified hip roof front porch with Tuscan and square posts. Rock-faced concrete block foundation. 4 X 2 bays. Craftsman Four Square type. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Metal roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0201. (1012139) 109 ANN STREET, residential

McKay House

date: c. 1910

description: Two-story, side gable house with rear, two-story, gable addition. Asphalt shingle roof. Vinyl siding. Modern slider and multi-paned windows. One-story, modified hip roof, three-quarter length, front porch with wrought iron posts and lattice panels. Block foundation. 3 X 2 bays. Side Gable house. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Metal roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

JA-0202. (1012140) 107 ANN STREET, residential

West/George House

date: c. 1915

description: Large two-story, hip roof house with two-story, three-sided, projecting gable bay on the end and a large two-story, gable addition/wing on the rear. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, modified hip roof, three-quarter length, front porch

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 81

with square posts with brackets and decorative trim. Rock-faced concrete block foundation. 4 X 4 bays. Queen Anne style. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable shed. Asphalt shingle roof. T-111 siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0203. (1012141) 105 ANN STREET, residential

HMB Inc.

date: c. 1920

description: Two-story, hip roof house with two-story, shed roof addition on the north side. Asphalt shingle roof. Aluminum siding. Wood 6/6 windows with shutters. One-story, end gable, entrance porch with paired Tuscan columns. Concrete block foundation. 5 X 1 bays. Colonial Revival style. One Non-Contributing building.

JA-0204. (1012143) 405 SAND STREET, commercial

Gorman Building

date: c. 1910

description: One-story, front gable commercial building with a stepped parapet wall with a concrete cap on the front. Asphalt shingle roof. Molded concrete block on the front; rock-faced concrete block elsewhere including the foundation. Central garage bay on the front flanked by display windows. Man door with undivided transom on the front. 4 X 7 bays. Commercial style. One Contributing building.

JA-0205. (1012144) 112 HENRIETTA STREET, residential

Dixon House

date: c. 1915

description: Large two-story, hip gable roof house. Asphalt shingle roof. Stucco façade and foundation. Modern 1/1 and picture windows with leaded glass headers in gable bay. One-story, modified hip roof, front porch with stucco square columns on a concrete/stucco deck. Two-story addition on rear. One-story, enclosed rear porch. 2 X 4 bays. Queen Anne style. Modified. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. T-111 siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 82

JA-0206. (1012145) 110 HENRIETTA STREET, residential

Ruben House

date: c. 1910

description: Large two-story, truncated hip roof house. Two interior red brick chimneys. Standing seam metal roof. Vinyl siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with square rock-faced concrete block posts on an enclosed rock-faced concrete block balustrade. Door on second floor above porch. Entrance door has divided transom. Covered foundation. 3 X 2 bays. Craftsman Four Square type. One Contributing building.

JA-0207. (1012146) 108 HENRIETTA STREET, residential

Bever House

date: c. 1925

description: One and one-half-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows with shutters. One-story, shed roof, three-quarter length, front porch with square posts with scrolled brackets and an enclosed balustrade. One-story, gable addition on rear with shed roof, entrance porch with turned posts. Rock-faced concrete block foundation. 3 X 3 bays. Gable-Front house. One Contributing building.

A.

date: Modern

description: One-story, end gable garage/outbuilding. Metal roof; roll roofing. Metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0208. (1012147) 104 HENRIETTA STREET, residential

Hamilton House

date: c. 1920

description: One-story, side gable house with gable dormers on the front and a rear gable addition. Interior painted brick chimney. Asphalt shingle roof. Weatherboard siding. Modern multi-paned windows. One-story, shed roof, full length, front porch with Tuscan columns on an enclosed rock-faced concrete block balustrade. Rear enclosed porch. Rock-faced concrete block foundation. 3 X 2 bays. Center Passage house type. One Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, end gable shed. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 83

JA-0209. (1012148) 407 SAND STREET, residential

Rexroat House

date: c. 1910

description: One and one-half-story, mansard roof house with shed roof dormers. Metal roof. Interior brick chimney. Mansard has asbestos shingle siding. Rock-faced concrete block façade and foundation. Wood 1/1 windows. One-story, shed roof, three-quarter length, front porch with square posts on an enclosed rock-faced concrete block balustrade. 3 X 1 bays. Second Empire style. One Contributing building.

A.

date: c. 1930

description: One-story, end gable outbuilding. Corrugated metal roof. Concrete block façade and foundation. Asbestos shingle siding in gable ends. 1 X 1 bays. One Contributing building.

B.

date: Modern

description: One-story, shed roof outbuilding. "V" seam metal roof. Pressed board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0210. (1012150) 415 SAND STREET, commercial

Cedar Building

date: c. 1887

description: Two-story, flat roof, commercial building. Stepped parapet on the sides. Primary cornice with brackets, recessed panels and corbels. Painted brick façade. Modern 1/1 windows: openings downsized on the front and infilled. The original front window openings have decorative pedimented hoods with end brackets. Secondary cornice has end brackets. Central recessed storefront with central entrance door flanked by bricked-in display windows. End pilasters. Stone foundation. 3 X 2 bays. Italianate style. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Asphalt shingle roof. Concrete block façade and foundation. 1 X 1 bays. One Non-Contributing building.

JA-0211. (1012166) 113 HENRIETTA STREET, residential

Whyte House

date: c. 1890

description: Two-story, front gable house. Asphalt shingle roof. Partial return cornice. Wide frieze board in gable end with paired brackets with dropped finials. Round-headed louver in gable end with smooth stone sill. Red brick façade. Vertical 2/2 round-headed windows with round-headed brick hoods and smooth stone sills and shutters. One-story, shed roof, full length, front porch with decorative wrought iron roof balustrade and wrought iron posts and railing. Rear,

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 84

double gable, one-story, entrance addition on rear. Stone foundation. 3 X 3 bays. Italianate style. One Contributing building.

JA-0212. (1012167) 504 WALNUT STREET, commercial Kidder Building/Barber Shop

date: c. 1915

description: One-story, end gable, commercial building. Asphalt shingle roof. German siding on the front; vinyl siding elsewhere. Vertical 3/1 windows. Vertical 3/1 and paneled entrance door. Stone foundation. 1 X 2 bays. Gable-Front building. One Contributing building.

JA-0213. (1012168) 109 HENRIETTA STREET, residential

Sundin House

date: c. 1915

description: One-story, hip gable roof house. Asphalt shingle roof. Vinyl siding. 9/9 and picture windows with leaded glass headers with simple surrounds and decorative hoods. One-story, modified hip roof, entrance porch with Tuscan columns and slatted balustrade. One-story, shed roof, enclosed rear porch. One-story, three-sided square, projecting bay on the side. Rock-faced concrete block foundation. 2 X 2 bays. Queen Anne Cottage style. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Asphalt shingle roof. T-111 siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0214. (1012169) 107 HENRIETTA STREET, residential

Pursley House

date: c. 1915

description: Two-story, hip roof house. Asphalt shingle roof. Clapboard siding with wide frieze and corner boards. Wood 1/1 windows. One-story, shed roof canopy/entrance with wrought iron posts on a concrete deck. One-story, shed roof, enclosed rear porch. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

JA-0215. (1012170) 105 HENRIETTA STREET, residential

Knotts House

date: c. 1915

description: One-story, side gable house with small shed roof dormer on the front. Interior corbelled red brick chimney. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows. One-story, shed roof, full length, front porch has been fully enclosed and incorporated into the main body of the house and has a one-story, entrance porch with modern Doric columns. One-story, gable addition on rear. One-story, modified hip roof, three-sided, projecting bay on the

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 85

side. Rock-faced concrete block foundation. 3 X 4 bays. Center Passage house type. Modified. One Non-Contributing building.

JA-0216. (1012171) 501 SAND STREET, residential

Lurz House

date: c. 1910

description: One-story, hip roof house. Coated asbestos shingle roof?? Vinyl siding. Modern 1/1 windows with shutters. One-story, modified hip roof, three-quarter length, front porch with square posts on an enclosed concrete block balustrade. One-story, enclosed rear porch. Stone foundation. One-story Cube. Modified. One Non-Contributing building.

A.

date: c. 1930

description: One-story, end gable outbuilding. Metal roof. Terra cotta block façade and foundation. 1 X 2 bays. One Non-Contributing building.

JA-0217. (1012172) 505 SAND STREET, residential

Landis House

date: c. 1915

description: Two-story, hip roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows with shutters. One-story, modified hip roof, full length, front porch with turned posts. One-story, gable, enclosed rear porch. Modern deck on the side. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. Modified. One Non-Contributing building.

JA-0218. (1012173) 507 SAND STREET, commercial

Chiropractic Center

date: c. 1915

description: Tall one-story, flat roof, commercial building. Vinyl roof cap. Rock-faced concrete block façade and foundation. Central recessed entrance flanked by display windows. Transom infilled and used as signage area. 1 X 1 bays. Commercial style. One Contributing building.

JA-0219. (1012174) 506-510 WALNUT STREET, commercial

Bradley Building

date: c. 1925

description: One-story, flat roof, commercial building. Terra cotta tile roof cap. Stepped parapet on the side. Terra cotta tile block façade and foundation; painted on the front. Three flush storefronts; each with a central entrance flanked by display windows. Transom areas have been painted on all the storefronts. 3 X 2 bays. Commercial style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 86

JA-0220. (1012175) 112 HENRY STREET, residential

Miller House

date: c. 1890

description: Two-story, mansard roof house with shed dormers. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows with shutters; vertical 2/2 windows in dormers. One-story, shed roof, entrance porch with square posts and slatted balustrade. Block foundation. 2 X 1 bays. Second Empire style. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding with attached, shed roof, enclosed wing. Asphalt shingle roof. Painted plywood siding. Pier foundation. 2 X 1 bays. One Non-Contributing building.

JA-0221. (1012176) 110 HENRY STREET, residential

Taylor House

date: c. 1920

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Vertical 2/2 and 1/1 windows. One-story, shed roof, full length, front porch with Tuscan columns on an enclosed rock-faced concrete block balustrade. One-story, shed roof, full length, enclosed rear porch. Rock-faced concrete block foundation. 3 X 2 bays. Side Gable Cottage type. One Contributing building.

JA-0222. (1012177) 108 HENRY STREET, residential

Williams House

date: c. 1920

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, flat roof, front porch with non-original square posts on a wood deck. One-story, gable addition on the rear. One-story addition on the north side. Pier and concrete block foundation. 4 X 3 bays. Gable-Front house. Modified. One Non-Contributing building.

JA-0223. (1012178) 106 HENRY STREET, residential

Cozart House

date: c. 1920

description: Two-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows with shutters. One-story, shed roof, three-quarter length, front porch with large square columns and a slatted balustrade. One-story, shed roof, enclosed rear porch attaches to a one-story, shed roof, enclosed addition. Block foundation. 3 X 4 bays. Gable-Front house. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 87

JA-0224. (1012179) 104 HENRY STREET, residential

Hicks/Durnati/Suck House

date: c. 1920

description: Two-story, side gable house. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows. One-story, modified hip roof, three-quarter length, front porch with square columns on an enclosed balustrade – columns and balustrade are covered with fish scale shingles. One-story, modified hip roof, three-sided, projecting bay on the side with novelty window and vertical 3/1 windows. One-story, rear porch with turned posts. Rock-faced concrete block foundation. 3 X 2 bays. "I" house. One Contributing building.

A.

date: c. 1920

description: One-story, shed roof outbuilding. Roll roofing. German siding. Concrete block foundation. 2 X 1 bays. One Contributing building.

B.

date: c. 1920

description: Large one-story, side gable barn/garage. Metal roof. Metal siding. Pier foundation. 1 X 1 bays. One Contributing building.

JA-0225. (1012180) 511 SAND STREET, residential

Polcawich Apartments

date: c. 1920

description: Two-story, front gable apartment building. Metal roof. Asbestos shingle siding. Combination of modern window types. Two-story, shed roof, entrance and porch wing on the side with lattice, parged concrete and molded concrete block siding. Attached to this entrance way in the rear is a two-story addition with metal siding. Molded concrete block foundation. 2 X 3 bays. Gable Front building. Modified. One Non-Contributing building.

JA-0226. (101218) 102 HENRY STREET, commercial

Day Care Center

date: c. 1950

description: Tall one-story, front gable building. May have once been a church; now a day care center. Asphalt shingle roof. Stucco façade and foundation. Metal casement windows. One-story, end gable, entrance bay with Tuscan columns on a concrete deck with attached ADA ramp. One-story, end gable, enclosed, entrance bay on the side. Double entrance doors. 1 X 4 bays. Gable Front building. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 88

JA-0227. (1012182.1) SAND STREET, residential

date: c. 1915

description: Large two-story, hip roof house. Standing seam metal roof. Three interior corbelled brick chimneys: one blonde brick, two red brick. Vinyl siding. Wood 6/6 windows. One-story, modified hip roof, three-quarter length, front porch with square rock-faced concrete block columns on an enclosed rock-faced concrete block balustrade. Rock-faced concrete block foundation. 3 X 4 bays. Craftsman Four Square type. One Contributing building.

JA-0228. (111441) 216 SAND STREET, residential

Carroll House

date: c. 1900

description: One-story, end gable house. Central interior corbelled red brick chimney. Metal roof. Partial return cornice. Vinyl siding; asbestos shingle siding in gable end. Vertical 2/2 windows. Recessed entrance door. Stone foundation. 3 X 3 bays. Gable-Front house. One Contributing building.

JA-0229. (111442) 222 SAND STREET, residential

Bird/Clonch House

date: c. 1940

description: One-story, side gable house. Asphalt shingle roof. Partial return cornice. Vinyl siding. Painted metal casement windows. One-story, shed roof, metal canopy supported by wrought iron posts; small enclosed red brick balustrade with stone cap at entrance. One-story, shed roof, enclosed wing on the rear. Concrete block foundation. 5 X 2 bays. Side Gable type. One Contributing building.

A.

date: c. 1940

description: One-story, flat roof garage building. Painted terra cotta block façade and foundation. 2 X 1 bays. Once a Dry Cleaners. One Contributing building.

JA-0230. (111443) 230 SAND STREET, residential

Twiggs House

date: c. 1900

description: One-story, side gable house. Central interior corbelled brick chimney. Coated metal roof. Partial return cornice. Aluminum siding. Vertical 2/2 windows. One-story, barrel vault entrance canopy supported by square posts and wrought iron railing. One-story, shed roof, enclosed rear porch. Pier foundation. 3 X 2 bays. Side Gable Cottage. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 89

JA-0231. (111444) 234 SAND STREET, commercial

Tucker Building

date: c. 1920

description: Large two-story, flat roof, commercial building. Corbeled brick primary cornice with recessed brick panels. Painted brick façade. Window openings have been downsized and infilled with brick and board and smaller windows; openings have concrete lintels and sills. First floor storefront has been infilled and two man doors installed. 4 X 4 bays. Brick foundation. Commercial style. Modified. One Non-Contributing building.

JA-0232. (111445) 300 SAND STREET, residential

Gurtis House

date: c. 1930

description: Two-story, side gable house. Exposed painted brick end chimney. Asphalt shingle roof. Weatherboard siding. Original multi-paned windows with shutters. One-story, flat roof, entrance bay with roof balustrade, square columns and wrought iron railing. One-story, shed roof, side porch with paired square posts. Two-story addition on rear. Concrete block foundation. 3 X 3 bays. Colonial Revival style. One Contributing building.

A.

date: c. 1930

description: One-story, end gable garage. Asphalt shingle roof. Weatherboard siding. Concrete block foundation. 1 X 1 bays. One Contributing building.

JA-0233. (111446) 304 SAND STREET, residential

Lore House

date: c. 1920

description: One-story, hip roof house with small, shallow hip roof dormer on the front. Asphalt shingle roof. Vinyl siding. Picture windows with leaded glass headers. Roof overhangs front porch and is supported by wrought iron posts on a concrete deck. Rock-faced concrete block foundation. 3 X 2 bays. One-story Cube. One Contributing building.

JA-0234. (111447) 306 SAND STREET, residential

Speer House

date: c. 1915

description: Very large, two-story, hip roof house with hip dormers and a raised water table. Asphalt shingle roof. Bull-nosed fish scale shingles on dormer cheek walls. Clapboard siding with wide frieze and corner boards. Wood 1/1 windows. Simple recessed entrance. Rock-faced concrete block foundation. 3 X 4 bays. Craftsman Four Square type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 90

JA-0235. (111450) 400 SAND STREET, commercial

Dill Building

date: c. 1915

description: One-story, flat roof, commercial building with stepped parapet on the front and sides. Concrete roof cap. Parged concrete block façade with brick veneer and stucco on the front. Decorative brick cartouche on the front. Central recessed storefront entrance flanked by display windows with T-111 sided canopies. Garage/freight bay on the left. Parged concrete block foundation. 4 bays wide. Commercial style. One Contributing building.

JA-0236. (111452) 402 SAND STREET, commercial

Raspberry Restaurant/Old Opera House

date: c. 1890

description: Two-story, flat roof, commercial building with stepped parapet on the sides. Front has non-original tall parapet wall with original paired brackets below. Painted brick façade. Original 1/1 round-headed windows with brick sills on the side. Exterior stair leads to the second floor on the side; wraps to the front and creates a second story porch with 2X4 posts and horizontal rail balustrade; first floor has "Y" 2X4 posts supporting the porch. Central recessed entrance flanked by non-original multi-paned windows. Brick foundation. 4 X 4 bays. Italianate Commercial style. Modified. One Non-Contributing building.

JA-0237. (111454) 410 SAND STREET, residential

Carmichael House

date: c. 1925

description: One-story, side gable house. Asphalt shingle roof. Asbestos shingle siding. 1/1 windows with shutters and metal canopies. Small end gable bay entrance bay with wrought iron posts on a concrete deck. Rock-faced concrete block foundation. 3 X 2 bays. Side Gable Cottage. One Contributing building.

JA-0238. (111455) 408 SAND STREET, residential

Milhoan House

date: c. 1925

description: Twin to 410 Sand Street. One-story, side gable house. Asphalt shingle roof. Asbestos shingle siding. Vertical 3/1 windows with shutters. Metal shed roof canopy over entrance door with wrought iron railing on concrete deck. Rock-faced concrete block foundation. 3 X 2 bays. Side Gable Cottage. One Contributing building.

JA-0239. (111456) 406 SAND STREET, residential

Blankenship/Milhoan House

date: c. 1930

description: Twin to the previous two houses: 408 and 410 Sand Street. One-story, side gable house. Asphalt shingle roof. Partial return cornice. Asbestos shingle siding. 1/1 windows with

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 91

shutters and metal canopies. One-story, shed roof, entrance porch with square posts and slatted balustrade and slatted decorative trim. Rock-faced concrete block foundation. 3 X 2 bays. Side Gable Cottage. One Contributing building.

A.

date: c. 1930

description: One-story, end gable garage. Corrugated metal roof and siding. Pier siding. 1 X 1 bays. One Contributing building.

JA-0240. (111457) 412 SAND STREET, residential

Lane Building

date: c. 1920

description: Two-story, flat roof, commercial building converted to residential use. Stepped parapet on the side. Two louvers on the front in the cornice area. Rock-faced concrete block façade and foundation. Modern windows on the second floor have infilled the original openings; openings have smooth concrete lintels and sills. First floor converted to residential entrances. 3 X 3 bays. Commercial style. One Contributing building.

JA-0241. (111460) 502 SAND STREET, residential

McComas House

date: c. 1920

description: One-story, side gable house with rear gable addition. "V" seam metal roof. Vinyl siding. 1/1 windows; narrow and paired on the front. One-story, modified hip roof, three-quarter length, front porch with turned posts and enclosed balustrade. One-story, shed roof, enclosed rear porch. Rock-faced concrete block foundation. 3 X 1 bays. Side Gable Cottage. One Contributing building.

A.

date: c. 1920

description: One-story, end gable garage. Metal roof. Painted concrete block façade and foundation. Wood shingles in the gable ends. 1 X 1 bays. One Contributing building.

JA-0242. (111461) 504 SAND STREET, residential

Price House

date: c. 1915

description: One-story, hip roof house with hip dormers. Asphalt shingle roof. Red brick façade. Picture windows with leaded glass headers and concrete lintels and sills. One-story, full length, front porch within roof overhang with square brick columns and an enclosed brick balustrade with concrete cap. Rock-faced concrete block foundation. 3 X 2 bays. Craftsman Bungalow type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 92

JA-0243. (111462) 506 SAND STREET, residential

Burdette House

date: c. 1915

description: Two-story, hip roof house with central hip dormer on the front and shed roof dormer on the sides. Asphalt shingle roof. Central interior corbelled brick chimney. Brick façade. Modern 1/1 windows with shutters and smooth concrete sills. One-story, modified hip roof, three-quarter length front porch with square brick columns on an enclosed brick balustrade; porch screened in. Concrete water table course. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman Four Square type. One Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Metal roof. Metal siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

JA-0244. (111464) 406 ASHTON LANE, residential

Bennett House

date: c. 1945

description: One-story, side gable house. Asphalt shingle roof. Aluminum siding. 1/1 windows. One-story, end gable, projecting entrance bay with square columns. One-story, shed roof, enclosed, rear entrance porch. Concrete block foundation. 3 X 1 bays. Side Gable Cottage. Modified. One Non-Contributing building.

JA-0245. (111466) 410 ASHTON LANE, residential

Milhoan/Blankenship House

date: c. 1930

description: One and one-half-story, side gable house. Asphalt shingle roof. Weatherboard siding. 6/6 and metal windows. One-story, end gable, projecting, entrance porch with square columns and a spindled balustrade. One-story, gable wing on rear. Parged and rock-faced concrete block foundation. 3 X 4 bays. Side Gable Cottage. One Non-Contributing building.

A.

date: Modern

description: One-story, side gable outbuilding with smaller side gable, enclosed wing on the left. Metal roof. Metal siding. 1/1 and multi-paned windows. Pier foundation. 4 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 93

JA-0246. (111467) 412 ASHTON LANE, residential

Saltsman House

date: c. 1930

description: One-story, end gable house. Asphalt shingle roof. Asbestos shingle siding. 1/1 windows with simple surrounds. One-story, end gable, projecting, entrance bay with slightly battered square columns on an enclosed balustrade. One-story, shed roof, car port on the side supported by thin metal posts. Rear gable addition with modern siding. Concrete block foundation. 3 X 3 bay. Gable-Front house. One Contributing building.

A.

date: c. 1930

description: One-story, end gable outbuilding. Roll roofing. Board siding. Pier foundation. 2 X 1 bays. One Contributing building.

JA-0247. (111468) 414 ASHTON LANE, residential

Cedar House

date: c. 1950

description: One-story, end gable duplex. Asphalt shingle roof. Concrete block façade and foundation. Metal casement and one slider window with smooth concrete sills. Shed roof, metal canopy over entrance stoop. 4 X 4 bays. Gable-Front house. One Contributing building.

JA-0248. (111469) ASHTON LANE, residential

Lestitan/Howard House

date: c. 1945

description: One-story, end gable house. Asphalt shingle roof. Asbestos shingle siding. 1/1 windows. Two small entrance stoops. Concrete block foundation. 2 X 2 bays. Gable-Front house. One Contributing building.

A.

date: c. 1945

description: Small one-story, end gable outbuilding. Asphalt shingle roof. German siding. Concrete block foundation. 1 X 1 bays. One Contributing building.

JA-0249. (111469.2) 4 HENRY STREET, residential

Lestitan/Howard House

date: c. 1915

description: Two-story, hip gable roof house. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows and original picture windows with leaded glass headers. Large one-story, wraparound porch with square columns on an enclosed shingled balustrade. Modern deck on rear. Terra cotta block foundation. 2 X 3 bays. Queen Anne style. Modified. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 94

JA-0249. (111469.2) 4 HENRY STREET, residential (continued)

A.

date: Modern

description: One-story, end gable outbuilding with attached, shed roof, enclosed wing on the left. Metal roof. T-111 and vertical board siding. Pier foundation. 3 X 1 bays. One Non-Contributing building.

JA-0250. (111470) 6 HENRY STREET, residential

Howard House

date: c. 1915

description: Two-story, hip roof house with hip dormers. Exposed brick chimney on the rear; interior brick end chimney. Asphalt shingle roof. Blonde brick façade. 1/1 windows with brick sills. One-story, modified hip roof, three-quarter length, front porch with square brick columns on an enclosed brick balustrade with concrete caps. One-story, enclosed rear porch. Concrete water table course. Rock-faced concrete block foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

JA-0251. (1112183) 512 SAND STREET, residential

Johnson House

date: c. 1915

description: Two-story, front facing "L" house with hip roof. Asphalt shingle roof. Wide frieze board with paired brackets and dentiling. Vinyl siding. Modern 1/1 windows. One-story, hip roof, three-sided, projecting bay on the front with frieze board with brackets and dentiling. One-story, modified hip roof, front porch with chamfered posts and pilasters with brackets, Eastlake vergework and dentiled frieze. One-story, enclosed, rear porch. Rear porch attaches to a one-story, hip roof addition. Rock-faced concrete block foundation. 4 X 1 bays. Folk Victorian style. One Contributing building.

A.

date: c. 1930

description: Two-story, clipped end gable garage. Metal roof. Terra cotta block façade and foundation. Horizontal board siding on the second floor of the front. Glazed and paneled garage doors. 2 X 1 bays. One Contributing building.

JA-0252. (121256) 240 VIRGINIA STREET, residential

Nicholas House

date: c. 1895

description: Two-story, cross hip roof house. Front bay of house is three-sided and projects and has brick dogtooth corners. Interior corbelled red brick chimney. Decorative slate shingle roof. Red brick façade. 1/1 windows with rusticated stone lintels and sills. One-story, shed roof,

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 95

entrance porch with square posts with scroll brackets and cut-out decorative trim. One-story, enclosed rear porch. Brick foundation. Queen Anne style. One Contributing building.

JA-0253. (121257) 221 MULBERRY STREET, residential **Clarkson House**date: c. 1855description: Small one-story, side gable house. Asphalt shingle roof. Vinyl siding. Horizontal 2/2 windows. One-story, shed roof, entrance porch with square posts – non-original. One-story, shed roof, enclosed rear porch. Covered foundation. 3 X 1 bays. Side Gable Cottage. Modified. One Non-Contributing building.**JA-0254. (121295) 302 SYCAMORE STREET, residential** **Wright House**date: c. 1910description: One-story, side gable house with central shed roof dormer on the front. Standing seam metal roof. Vinyl siding. Modern multi-paned windows. Non-original one-story, shed roof, entrance porch with square posts and “criss cross” rail balustrade. Stone foundation. 3 X 1 bays. Side Gable Cottage. Modified. One Non-Contributing building.**JA-0255. (121297) 301 MULBERRY STREET, residential** **Vanderlaan House**date: c. 1900description: Tall two and one-half-story, side gable house with front gable wall dormer and two-story, three-sided, projecting bay on the front. Wall gable contains fish scale and diagonal shingles and a Palladian window with keystone. Hip dormer on the front. Asphalt shingle roof. Painted brick façade. Original 1/1 windows with rusticated stone lintels and sills. One-story, modified hip roof, wraparound porch with gable pediment and slightly battered square columns on a wood deck. Gable pediment has garland decoration. Entrance door has undivided transom. Stone foundation. 4 X 2 bays. Queen Anne style. One Contributing building.**A.**date: c. 1900description: One-story, hip roof garage with attached, shed roof car port. Decorative slate shingle roof. Painted brick façade and foundation. 2 X 2 bays. One Contributing building.**JA-0256. (121299) 308 SYCAMORE STREET, residential** **Bush House**date: c. 1920description: One-story, side gable house. Asphalt shingle roof. Vinyl siding over clapboard siding. Modern 1/1 windows. One-story, end gable, projecting, entrance bay with square posts

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 96

on a concrete deck. One-story, enclosed rear porch. Covered foundation. 3 X 2 bays. Side Gable Cottage. Modified. One Non-Contributing building.

JA-0257. (1212100) 312 SYCAMORE STREET, residential

Bush House

date: c. 1940

description: Two-story, gable on hip roof house. Asphalt shingle roof. Asbestos shingle siding. Metal casement windows. Small entrance stoop with metal canopy and wrought iron railing. Exterior stair on the rear to the second floor. Painted block foundation. 3 X 2 bays. Modern style. One Contributing building.

JA-0258. (1212101) 214 ANN STREET, residential

Bush House

date: c. 1900

description: Large two-story, rear facing "L" house. Asphalt shingle roof. Vinyl siding. Modern multi-paned windows with shutters. Two-story, gable entrance portico with two-story tall square columns on a concrete deck. Colonial Revival entrance door surround. Parged foundation. 3 X 3 bays. Gabled-Ell house. Modified. One Non-Contributing building.

A.

date: Modern

description: Two-story, gambrel roof garage. Asphalt shingle roof. T-111 siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0259. (1212102) 309 MULBERRY STREET, residential

Roush House

date: c. 1905

description: Two-story, cross gable house. Asphalt shingle roof; porch has metal roof. Asbestos shingle siding. Vertical 2/2 and 1/1 windows. One-story, modified hip roof, wraparound porch: enclosed with a hip roof addition on the left; remainder has square posts with scroll brackets and an enclosed balustrade. One-story, shed roof, enclosed rear porch. Rock-faced concrete block foundation. 4 X 2 bays. Queen Anne Cottage style. One Contributing building.

A.

date: c. 1940

description: Two-story, end gable garage. Metal roof. Concrete block façade and foundation. 1 X 1 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 97

JA-0260. (1212103) 313 MULBERRY STREET, residential

Roush House

date: c. 1910

description: One-story, hip roof house. Asphalt shingle roof. Vinyl siding. Vertical 2/2, 6/6 and 1/1 windows. One-story, modified hip roof, three-quarter length front porch with turned posts with spindled brackets and an enclosed balustrade. One-story, shed roof, enclosed rear porch. Concrete block foundation. 3 X 4 bays. One-story Cube. One Contributing building.

JA-0261. (131262) 229 WASHINGTON STREET, commercial

Tetrick's Jeweler

date: c. 1950

description: One-story, flat roof, commercial building – also very small. Same as the storefront to the left. Metal panel with signage in transom area. Flush center entrance storefront of aluminum. Brick foundation. 1 bay wide. Modern style. One Contributing building.

JA-0262. (131271) 222 MULBERRY STREET, commercial

Jailhouse Fitness

date: c. 1915

description: Two-story jail building with a non-original front gable roof added. Originally had a hip roof. Asphalt shingle roof. Rock-faced concrete block façade and foundation; vinyl siding in the gable ends. 1/1 windows with shutters and smooth concrete lintels and sills. Two entrance doors on the front. Greenhouse wing added to the left side. 2 X 2 bays. Gable Front building. One Non-Contributing building.

JA-0263. (131277) 221 WALNUT STREET, commercial

Sport Center

date: c. 1950

description: Two-story, flat roof, commercial building. Concrete roof cap. Red brick façade. Modern multi-paned windows on the second floor with smooth concrete sills and metal canopies. Central display window on first floor flanked by end man doors. Metal canopy over first floor. Concrete foundation. 3 bays wide. Two-part commercial block. One Contributing building.

JA-0264. (1312104) 209 VIRGINIA STREET, residential

Winebrenner House

date: c. 1890

description: Very large three-story, gambrel roof house with gable bays on the front and side and a three-story, five-sided tower on the corner with pyramidal roof. Asphalt shingle roof. Gable ends have decorative wood shingles and Palladian windows with bull-nosed cheek walls. Porthole windows above Palladian windows. Two engage red brick chimneys. Red brick façade; front gable bay has German siding on the second floor and wood shingles on the third floor. Original 1/1 windows with rusticated stone lintels and smooth sills. One-story, modified

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 98

hip roof, wraparound porch with Tuscan columns on brick piers with stone caps and dentiled cornice. Second floor recessed balcony above entrance door with square posts and solid corner brackets. Porte cochere on the side with the same cornice and columns. One-story, modified hip roof, enclosed rear porch. Gable bay on the side projects and has a second floor open balcony with brick balustrade with stone cap. Stone foundation. 3 X 4 bays. Queen Anne style with Shingle style details. One Contributing building.

JA-0265. (1312105) 205 VIRGINIA STREET, residential**August House**date: c. 1875

description: Two-story, cross gable house with wall dormers on the front. Wood shingle roof. Interior corbelled red brick chimney. Vergework in the gable bays. German siding with frieze and corner boards. Vertical 3/1 windows. Front gable bay has paired vertical 3/1 windows with simple hood with paired end brackets and shutters; same window detailing on the dormer door and window. First floor of front gable bay has a one-story, four-sided projecting bay with vertical 3/1 windows with divided transoms. Entrance door has sidelights and transom. One-story, shed roof, front porch with square posts on an enclosed balustrade. Cut stone foundation. 4 X 3 bays. Folk Victorian style. One Contributing building.

A.date: c. 1915

description: Two-story, side gable garage with clipped corner that forms a garage bay. "V" seam metal roof. Molded concrete block façade and foundation. Wood shingles over open garage bay. 2 X 1 bays. One Contributing building.

JA-0266. (1312106) 301 WALNUT STREET, residential**Lemley/Wood/Sayre/Benford House**date: 1872

description: Large two-story, hip gable roof house. Two interior corbelled red brick chimneys. Standing seam metal roof. Overhanging roof eave with scroll brackets. Painted brick façade. 1/1 arched windows with arched hoods with keystones and smooth sills; lintels and sills painted. One-story, flat roof, entrance porch with roof balustrade and decorative posts and pilasters with scrolled brackets. Porch has cut-out balustrade and frieze with brackets and modillions and a cut-out roof balustrade. One-story, side porch and three-sided, projecting bay on the front with all the same details. Two-story, rear addition. Stone foundation. 2 X 2 bays. Italianate style. One building on the National Register.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 99

JA-0266. (1312106) 301 WALNUT STREET, residential (continued)

A.

date: c. 1920

description: One-story, shed roof outbuilding. Corrugated metal roof. Board siding. Rock-faced concrete block foundation. 1 X 1 bays. One building on the National Register.

B.

date: c. 1880

description: Two-story, hip roof garage/outbuilding. Decorative slate roof. Painted brick façade and foundation. Vertical 2/2 windows on the second floor with rusticated lintels and sills. Garage bay on first floor with divided transom. 1 X 3 bays. One building on the National Register.

C.

date: c. 1880

description: One-story, hip roof outbuilding. Standing seam metal roof. Painted brick façade and foundation. 1 X 1 bays. One building on the National Register.

JA-0267. (1312108) 206 ANN STREET, residential

King House

date: c. 1910

description: Large two-story, hip roof house with two-story, rear addition; one-story, concrete block rear addition; and one-story, shed roof bay on the side. Rolled asphalt roof. Vinyl siding. Vertical 2/2 windows; metal casements on two-story rear addition; picture window installed on side elevation. One-story, modified hip roof, three-quarter length, front porch with turned posts and an enclosed shingled balustrade. Covered foundation. 3 X 3 bays. Craftsman Four Square type. One Contributing building.

JA-0268. (1312111) 313 WALNUT STREET, residential

Gore House

date: c. 1900

description: Large two-story, hip gable roof house. Two interior corbelled red brick chimney. Asphalt shingle and standing seam metal roof. Roof eave brackets. Vinyl siding. 1/1 windows. One-story, modified hip roof, enclosed front porch. One-story, shed roof, enclosed rear porch. Stone foundation. 4 X 3 bays. Queen Anne style. One Contributing building.

JA-0269. (1312112) 309 WALNUT STREET, residential

Williams House

date: c. 1930

description: Small one-story, flat roof building converted to residential use. Stepped parapet on the sides. Terra cotta tile roof cap. Terra cotta block on the front; parged elsewhere. Vertical

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 100

2/2 windows. Terra cotta block foundation. 2 X 1 bays. Commercial style building converted to residential use. One Contributing building.

JA-0270. (1312113) 307 WALNUT STREET, residential

Williams House

date: c. 1920

description: One and one-half-story, end gable house with gable dormer on the side. Asphalt shingle roof. German siding with frieze and corner boards. Wood 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with modern turned posts and spindled balustrade. One-story, shed roof, enclosed rear porch. Entrance door with decorative glazing. Rock-faced concrete block foundation. 3 X 3 bays. Gable-Front house. One Contributing building.

JA-0271. (141287) 130 VIRGINIA STREET, residential

Cannon House

date: c. 1915

description: Two-story, side gable house. Asphalt shingle roof. Exposed corbelled red brick end chimneys. Asbestos shingle siding with frieze and corner boards. 1/1 windows with shutters. One-story, modified hip roof, front porch with square squat brick columns on an enclosed rock-faced concrete block balustrade. Rock-faced concrete block foundation. 5 X 2 bays. "T" house. One Contributing building.

A.

date: c. 1930

description: One-story, end gable outbuilding. Roll roofing. Exposed rafter tails. Board and batten, brick, and terra cotta block façade. Rock-faced concrete block foundation. 1 X 1 bays. One Contributing building.

JA-0272. (141430) 211 SAND STREET, residential

Givens House

date: c. 1915

description: One-story, hip roof house with hip dormers. Asphalt shingle roof. Chisel point shingles on cheek walls of dormers. Interior corbelled brick parged chimney. Molded concrete block façade. Vertical 4/1 and 1/1 windows. One-story, hip roof, three-quarter length, enclosed front porch. Rock-faced concrete block foundation. 3 X 5 bays. Craftsman Bungalow type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 101

JA-0273. (141434) VIRGINIA STREET, commercial

Drake/Roush Building

date: c. 1930

description: Large two-story, flat roof, commercial building with concrete roof cap. Corbelled brick primary cornice. Red brick veneer and wood shingles on the front; terra cotta block façade elsewhere. Modern multi-paned windows with shutters on the first and second floors; original openings made smaller and infilled with modern windows and wood shingles. Mansard roof canopy with wood shingles runs the length of the first floor. One garage bay on the front. Terra cotta block foundation. 5 X 5 bays. Two-part commercial block type. One Contributing building.

JA-0274. (141435) 101 VIRGINIA STREET, residential

Burlinghame House

date: c. 1840/moved c. 1915

description: Large two-story, side gable house. Two interior corbelled brick end chimneys. Asphalt shingle roof. Partial return cornice. Asbestos shingle siding. Original 6/6 windows with shutters. Two-story, entrance portico with square columns: slatted balustrade on the second floor; columns sided with asbestos shingles. Entrance door has divided sidelights. One-story, shed roof, enclosed rear porch. Concrete block foundation. 5 X 1 bays. Early Colonial Revival style. One Contributing building.

A.

date: c. 1930

description: Two-story, hip roof garage/apartment. Asphalt shingle roof. Asbestos shingle siding. Metal casement and modern 1/1 windows with shutters. Two garage bays. Concrete block foundation. 3 X 2 bays. One Contributing building.

JA-0275. (1412117) 107 VIRGINIA STREET, residential

Rymer House

date: c. 1880

description: Small one and one-half-story, mansard roof house with gable dormers on the front. Asphalt shingle roof. Dormers have arched vertical 2/2 windows with end brackets and a rosette block in the gable end. Paired roof brackets and rosette blocks. One-story, hip roof wing on the left. Clapboard siding with frieze and corner boards. 1/1 and multi-paned windows; windows on the front have elephant ear hoods and simple surrounds. Entrance porch with roof balustrade and chamfered posts with decorative trim and paired brackets and rosette block in the frieze. Brick foundation. 4 X 2 bays. Second Empire style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 102

JA-0276. (1412118) 105 VIRGINIA STREET, residential

Belcher House

date: c. 1915

description: Two-story, hip roof house with central shed roof dormer on front. Interior corbelled red brick chimney. Asphalt shingle roof. Molded concrete block façade. Novelty windows with smooth concrete lintels and sills. One-story, modified hip roof, wraparound porch with square molded concrete block columns on an enclosed molded concrete block balustrade with concrete cap. One-story, modified hip roof, enclosed rear porch. Molded concrete block foundation. 2 X 2 bays. Craftsman Four Square type. One Contributing building.

JA-0277. (1412119) 308 WALNUT STREET, commercial/ residential

Curves Shop

date: c. 1900

description: Two-story, side gable house converted to commercial use. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, shed roof, enclosed front porch converted to commercial entrance with glazing and a end gable projecting entrance bay with barrel vault in the gable end, square paneled posts and a slatted balustrade. Two-story addition on the rear. Parged foundation. 2 X 3 bays. "I" house. Modified. One Non-Contributing building.

A.

date: c. 1900

description: One-story, side gable outbuilding with gable pediment over entrance door. Asphalt shingle roof. Vinyl siding. 1/1 windows. 2 X 1 bays. One Non-Contributing building.

JA-0278. (1412120) 312 WALNUT STREET, residential

Gorman House

date: c. 1900

description: Two-story, hip gable roof house. Two interior corbelled red brick chimney. Slate roof. Herringbone shingles in gable ends. Brackets in frieze area. Red brick façade. Original 1/1 windows with rusticated stone lintels and smooth stone sills; some picture windows with leaded glass headers. One-story, wraparound porch with gable pediment over entrance and a pyramidal roof at the curved corner; Tuscan columns with caps and plinths and paired brackets in the frieze area. Stone foundation. 2 X 3 bays. Queen Anne style. One Contributing building.

A.

date: c. 1900

description: One-story, hip roof garage. Standing seam metal roof. German siding with corner boards. Pier foundation. 1 X 1 bays. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 103**JA-0279. (1412121) 106 ANN STREET, residential****Alderfer House**date: c. 1915

description: Large two-story, front facing "T" house. Asphalt shingle roof. Fish scale shingles in the gable ends. Exposed corbelled brick chimney on front end of enclosed portion of front porch. Brick façade. Original 1/1 windows with brick lintels and smooth concrete sills. One-story, modified hip roof, wraparound porch with the front left and side portion enclosed with multi-paned windows; remainder has square brick columns on an enclosed brick balustrade with concrete cap. Second story open porch on the rear with square brick posts. Concrete water table course. Rock-faced concrete block foundation. 2 X 3 bays. Gabled-Ell house. One Contributing building.

A.date: c. 1915

description: Two-story, end gable garage/apartment. Asphalt shingle roof. Terra cotta tile on the second floor; molded concrete block and concrete block first floor and foundation. 2 X 1 bays. One Contributing building.

JA-0280. (1412122) 104 ANN STREET, residential**Bowen House**date: c. 1915

description: One-story, hip roof house with central wall dormer on the front. Asphalt shingle roof. Weatherboard siding. 1/1 windows. Undivided transom over entrance door. One-story, modified hip roof, three-quarter length, front porch with square posts. One-story, gable, enclosed rear porch. Concrete block foundation. 3 X 4 bays. Queen Anne Cottage style. One Contributing building.

JA-0281. (1412124) 309 SAND STREET, residential**Carter House**date: c. 1900

description: Two-story, side gable house with rear, two-story gable addition. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, shed roof, full length front porch with modern square posts and slatted balustrade. Covered foundation. 3 X 2 bays. Side Gable house. Modified. One Non-Contributing building.

JA-0282. (1412125) 313 SAND STREET, residential**Tidd House**date: c. 1900

description: Tall two-story, side gable house. Asphalt shingle roof. Partial return cornice. Clapboard siding with frieze and corner boards. Vertical 2/2 windows and one vertical 3/1 window. One-story, modified hip roof, three-quarter length, front porch with squat Tuscan

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 104

columns on an enclosed rock-faced concrete block balustrade with cap. One-story, shed roof, enclosed rear porch. Parged foundation. 3 X 2 bays. "I" house. One Contributing building.

JA-0283. (151232) 101 MULBERRY STREET, commercial

Mulberry's

date: c. 1925

description: Two-story, flat roof, commercial building. Terra cotta tile roof cap. Stepped parapet on the sides. Rock-faced concrete block façade and foundation. Modern 1/1 windows with rusticated concrete lintels and sills. Storefronts modified. 5 X 3 bays. Two-part commercial block type. One Contributing building.

JA-0284. (151234) WASHINGTON STREET, residential

Suck House

date: c. 1915

description: One-story, hip gable roof house with central, shed roof dormer on the front. Asphalt shingle roof. Asbestos shingle siding. Wood 1/1 windows with metal shed roof canopies. Metal shed roof canopy over entrance door with wrought iron posts and railing. Rock-faced concrete block foundation. 4 X 3 bays. One-story Cube house type. One Contributing building.

A.

date: c. 1915

description: One-story, end gable garage. Asphalt shingle roof. Rock-faced concrete block façade. Vertical 2/1 windows. Concrete block foundation. 2 X 3 bays. One Contributing building.

JA-0285. (161237) 237 RACE STREET, residential

Moore House

date: c. 1920

description: One-story, front gable house. Interior corbelled red brick chimney. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. Front porch within roof overhang and is enclosed on the right side with novelty windows and siding; remainder has square columns on an enclosed balustrade. Rock-faced concrete block foundation. 3 X 2 bays. Gable-Front house. Modified. One Non-Contributing building.

A.

date: c. 1920

description: One-story, side gable outbuilding. Asphalt shingle roof. German siding. Pier foundation. 2 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 105

JA-0286. (161238) 109 MULBERRY STREET, residential

Moore House

date: c. 1930

description: One-story, front gable house. Asphalt shingle roof. Terra cotta block façade. Wood shingles in gable ends. Vertical 3/1 windows. Entrance door on side and on end; entrance door on end has gable pediment supported by knee braces. Rock-faced concrete block foundation. 1 X 2 bays. Gable-Front house. One Contributing building.

JA-0287. (161239) 225 RACE STREET, residential

Stevenson House

date: c. 1920

description: One-story, hip gable roof house with one-story, shed roof addition on the side. Asphalt shingle roof. Partial return cornice. Weatherboard and wood shingle siding. Modern multi-paned windows with shutters. One-story, front gable, front porch with wrought iron posts on a concrete deck. Block foundation. 4 X 3 bays. One-story Cube house type. Modified. One Non-Contributing building.

JA-0288. (161245) 226-228 WASHINGTON STREET, commercial

Merle Norman Cosmetics

date: c. 1915

description: Two-story, flat roof, commercial building. Simple primary cornice with flat unadorned frieze area. Two-story wing on the right with flush modern entrance. 1/1 and multi-paned windows – modern. Vinyl siding on second floor. First floor has mansard canopy and modern brick veneer entrance. Original entrance door is recessed. 4 bays wide. Brick foundation. Italianate Commercial style. Modified. One Non-Contributing building.

JA-0289. (171427) 104-108 WASHINGTON STREET, commercial

Hupp Sewing Center

date: c. 1945

description: One-story, flat roof, commercial building. Terra cotta tile roof cap. Terra cotta block primary cornice. Concrete belt course. Red brick façade. Two flush aluminum framing storefronts. Concrete foundation. 2 bays wide. One-part commercial block type. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 106

JA-0290. (171427.2(B) 119 RACE STREET, residential

Mullins/Queen House

date: c. 1920

description: Twin to 115 Race Street. Two-story, front gable house. Asphalt shingle roof. Knee braces in gable ends. Glazed terra cotta block façade. Rock-faced concrete block belt course separates floors. Modern multi-paned windows; paired 4/4 windows in gable end. One-story, end gable, three-quarter length front porch with square brick columns and wrought iron railing. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman style. One Contributing building.

JA-0291. (171427.2(C) 123 RACE STREET, residential

Mullins/Queen House

date: c. 1920

description: Twin to 115 and 119 Race Street. Two-story, front gable house. Asphalt shingle roof. Knee braces in gable ends. Glazed terra cotta block façade. Rock-faced concrete block belt course separates floors. Modern multi-paned windows; paired 4/4 windows in gable end. One-story, end gable, three-quarter length front porch with square brick columns and wrought iron railing. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman style. One Contributing building.

JA-0292. (171427.2(D) 127 RACE STREET, residential

Mullins/Queen House

date: c. 1920

description: Twin to 115, 119 & 123 Race Street; block is slightly smaller and porch is slightly different than the others. Two-story, front gable house. Asphalt shingle roof. Knee braces in gable ends. Glazed terra cotta block façade. Modern multi-paned windows; paired 4/4 windows in gable end with rusticated concrete lintels. One-story, hip roof, three-quarter length front porch with square brick columns and wrought iron railing. Rock-faced concrete block foundation. 2 X 2 bays. Craftsman style. One Contributing building.

JA-0293. STATE ROUTE 68, bridge

date: 1953

description: Concrete bridge on State Route 68 over Sandy Creek. The bridge has large concrete pillars supporting the concrete deck and concrete balusters. Metal infills the area between the balusters. There is at least one historic light post on a corner. There is also a metal plaque on one corner post with the bridge date and number on it.
1 contributing structure to a potential historic district One Contributing structure.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 7Page 107**JA-0294. 401 RACE STREET, residential****Mullins House/Fleming Homestead**date: c. 1841

description: Large two-story, side gable house with central wall gable on the front and wall gables on each end. Standing seam metal roof. Two, interior, corbelled brick chimneys. Clapboard siding. Vertical 2/2 windows. One-story, gable wing on the rear. One-story, three-sided, projecting bay on the side. One-story, flat roof addition on the front and side with brick veneer on the front and concrete block elsewhere. Brick foundation. 3 X 5 bays. "I" house. Modified. One Non-Contributing building.

JA-0295. 409 SAND STREET, residentialdate: c. 1890

description: Two-story, front gable, commercial building with a tall parapet wall on the front. "V" seam metal roof. Asbestos shingle siding. Vertical 2/2 windows. Central entrance door on first floor flanked by small windows. Brick foundation. 3 X 1 bays. Commercial building converted to residential use. One Contributing building.

JA-0296. 415 SAND STREET, residential**Cedar Building**date: c. 1930

description: Two-story, front gable apartment building. Asphalt shingle roof. Partial return cornice. Asbestos shingle siding on the second floor; painted brick façade on the first floor. Modern 1/1 and fixed pane windows. Brick foundation. 2 X 5 bays. Commercial style. One Contributing building.

JA-0297. MULBERRY STREET, commercial**Ibrahim Building**date: c. 1900

description: Two-story, flat roof, commercial building. Stepped parapet on side. Metal primary cornice with large end brackets (one is missing) and garland and swag decoration in the frieze area. Red brick façade. Original 1/1 wood windows on the second floor with rusticated lintels and sills; some of the windows have been boarded up on the rear and side. Simple secondary metal storefront. Three storefronts on first floor; the center one has been infilled and covered over with modern siding; the east storefront has been partially infilled with siding and the openings downsized and modern entrance door and small window installed in opening; the west central recessed storefront has been covered with modern siding except for a central entrance door. Secondary entrance door to upper floors on eastern half of front. Terra cotta block projecting, two-story addition on the rear. Stone and brick foundation. 6 bays wide. Commercial style. One Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 108

JA-0298. 304 WALNUT STREET, residential

date: c. 1893

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, end gable, projecting, entrance bay with square posts on an enclosed concrete block balustrade. Concrete block foundation. 4 X 1 bays. Side Gable house type. One Non-Contributing building.

A.

date: c. 1940

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 109

“Not Eligible” Resources within the District

These buildings are currently Non-Contributing because of their age. That is, these are the “modern” buildings (constructed post 1957) within the bounds of the district. Outbuildings are denoted “A”, “B”, “C” etc. and are also classified as non-contributing because the principle structure is Non-Contributing, because they have been modified or because, like the principle structure, they were constructed post 1957.

(11378) M1. 716 SYCAMORE, residential

date: Modern

description: Two-story, side gable house. Asphalt shingle roof. Red brick façade. Modern slider windows with rusticated concrete sills. Double entrance doors with large fixed pane window above it. Small, shed roof, entrance porch on one end of the building supported by a modern Doric column and a concrete pad. Concrete steps lead to double entrance doors. Shed roof entrance porch on rear. Concrete block foundation. 6 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Painted concrete block façade. 1/1 windows. Concrete block foundation. 2 X 2 bays. One Non-Contributing building.

(11382.1) M2. 211 WILSON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Modern 6/6 windows with shutters. One-story, entrance porch within roof overhang with square posts with spoked brackets and spindled balustrade. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Asphalt shingle roof. T-111 wood siding. Unknown foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 110

(11389) M3. 204 BEDFORD STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. 1/1 and other modern windows. Front porch is within roof overhang and has wrought iron posts and railing. Concrete foundation. 3 X 3 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, side gable garage with two bays on the front. Asphalt shingle roof. Vinyl siding. Concrete foundation. 2 X 1 bays. One Non-Contributing building.

(11392) M4. 210 BEDFORD STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Large, interior concrete block chimney. Vinyl siding. Modern windows. Gable canopy supported by round metal posts on a concrete deck over entrance. Small projecting bow window on side. Attached, shed roof car port on left. Concrete block foundation. 2 X 4 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, shed roof outbuilding with attached, gable car port. Asphalt shingle roof. Vinyl siding. Concrete and concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(11393) M5. 214 BEDFORD STREET, residential

date: c. 1960

description: One-story, side gable house. Asphalt shingle roof. Exposed, red brick chimney on end. Aluminum siding. 1/1 windows. Recessed entrance. Gable hyphen attaches one-story, end gable, one bay garage to house on left. Concrete block foundation. 5 X 2 bays. One Non-Contributing building.

A.

date: c. 1960

description: Tall, one-story, shed roof, horse barn. Metal roof. Board and batten siding. Pier foundation. 4 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 111

(11396) M6. 720 SYCAMORE, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Modern 6/6 and picture windows. Ramp to front and side entrance. Concrete block foundation. 4 X 2 bays. One Non-Contributing building.

(113101) M7. 215 BEDFORD STREET, residential

date: Modern

description: Duplex. One-story, side gable duplex. Asphalt shingle roof. Vinyl siding. Modern 6/6 and 4/4 windows. Small, end gable, entrance porches on each end with square posts on a concrete deck. Concrete block foundation. 5 X 3 bays. One Non-Contributing building.

(113102.1) M8. 211 BEDFORD STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows. Concrete block foundation. 4 X 1 bays. One Non-Contributing building.

(113102.2) M9. 209 BEDFORD STREET, residential

date: Modern

description: One-story, side gable house. Metal roof. Vinyl siding. Variety of modern windows. Small, shed roof canopy over entrance door. Concrete block foundation. 3 X 1 bays. One Non-Contributing building.

(113103) M10. 205 BEDFORD STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows. Small, end gable, entrance porch with square posts on a wood deck supported by concrete block pier foundation. Concrete block foundation. 4 X 2 bays. One Non-Contributing building.

A.

date: c. 1920

description: One-story, end gable garage/outbuilding. Asphalt shingle roof. Exposed rafter tails. German and vinyl siding. Pier foundation. 1 X 2 bays. (NC)

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 112

(31522) M11. 17 WILSON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Faux 6/6 windows. Concrete entrance stoop. Metal canopies over windows on the front. Concrete block foundation. 3 X 3 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, side gable outbuilding. Asphalt shingle roof. Vinyl siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

(31527.1) M12. 721 ASHTON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Slider windows. One-story, modified hip roof, full length, enclosed, front porch has been incorporated into the main body of the house. One-story, shed roof, one bay garage attached on the rear. Concrete block foundation. 3 X 5 bays. One Non-Contributing building.

(313157) M13. 23 WILSON STREET, residential

date: Modern

description: One-story, end gable house with one-story, shed roof converted garage attached on the right. Asphalt shingle roof. Vinyl siding. 1/1 windows. Concrete block foundation. 5 X 1 bays. One Non-Contributing building.

(313158) M14. 21 WILSON STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. 6/6 windows with shutters. Concrete pad entrance. Concrete block foundation. 4 X 1 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. 1/1 windows. Concrete block foundation. 1 X 2 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, end gable outbuilding. Asphalt shingle roof. Aluminum siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 113

(313160) M15. 35 PRESTON STREET, residential

date: Modern

description: One-story, side gable house with below grade basement. Corrugated metal roof. Aluminum siding. Metal slider windows. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(313166) M16. 23 PRESTON STREET, residential

date: Modern

description: Two-story, end gable house with one-story, gable wing on the left. Asphalt shingle roof. Exposed, brick chimney on the side. Vinyl siding. Slider windows. One-story, end gable, entrance porch with wrought iron posts and railing. Entrance porch on the side with wrought iron posts. Deck with ramp on the front. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable outbuilding. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

(313167.1) M17. 21 PRESTON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Exposed, concrete block chimney on the side. Vinyl siding. 1/1 windows with shutters. One-story, end gable, entrance porch with round metal poles on a concrete deck. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, gable outbuilding with attached, enclosed wing. Roll roofing. Board and batten and T-111 siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(313169) M18. 15 PRESTON STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. T-111 siding; wood shingles in the gable ends. Faux 6/6 windows. One-story, shed roof, full length, rear porch with square posts. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 114

(41371) M19. 208 WILSON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows. Front corner porch within roof overhang has square columns on a concrete deck. Concrete block foundation. 4 X 3 bays. One Non-Contributing building.

A.

date: c. 1940

description: One-story, end gable garage. Asphalt shingle roof. Exposed rafter tails. Weatherboard siding. Concrete block foundation. 1 X 2 bays. (NC)

B.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

(41376) M20. WILSON STREET, commercial

Gas Shack

date: Modern

description: One-story, flat roof, gas shack. Concrete block façade and foundation. 1 X 1 bays. One Non-Contributing building.

(41377) M21. 218 WILSON STREET, residential

date: Modern

description: Long one-story, hip roof house. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, shed roof, three-quarter length, front porch with decorative block columns and a decorative block enclosed balustrade. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete foundation. 2 X 2 bays. One Non-Contributing building.

(412225) M22. 602 SYCAMORE STREET, commercial

Ravenswood Annex

date: Modern

description: One-story, end gable, commercial building. Rolled asphalt roof. Stucco façade. Two entrance doors and fixed pane windows. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 115

(412225) M22. 602 SYCAMORE STREET, commercial (continued)

A.

date: Modern

description: One-story, side gable outbuilding. Asphalt shingle roof. T-111 siding. Wood pier foundation. 1 X 1 bays. One Non-Contributing building.

(412225.1) M23. 209 HENRY STREET, commercial

Head Start

date: Modern

description: Trailer. One Non-Contributing building.

A.

date: Modern

description: Trailer. One Non-Contributing building.

(412228) M24. 203 HENRY STREET, residential

date: Modern

description: One-story, side gable house. Corrugated metal roof. Vinyl siding. One-story, shed roof addition on front. One-story, gable addition on rear. One-story, shed roof, entrance porch with square posts and slatted balustrade. Concrete block foundation. 2 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, side gable outbuilding. Roll roofing. T-111 siding. Pier foundation. 3 X 1 bays. One Non-Contributing building.

(412232) M25. 216 GALLATIN STREET, residential

date: Modern

description: One-story, cross gable house. Asphalt shingle roof. Vinyl siding. Faux 8/8 and 6/6 windows. Entrance porch within roof recess with wrought iron posts and railing. One-story, gable porch on end of house with wrought iron posts and railing. Concrete block foundation. 3 X 1 bays. One Non-Contributing building.

(512247) M26. 601 SAND STREET, residential

date: Modern

description: Two-story, side gable house with one bay garage incorporated into the body of the house on the left. Asphalt shingle roof. Red brick façade. 1/1 windows with shutters. Metal

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 116

canopy over recessed entrance. Concrete foundation. 4 X 2 bays. One Non-Contributing building.

(512248) M27. 605 SAND STREET, residential

date: Modern

description: Large two-story, shallow hip roof house. Asphalt shingle roof. Vinyl siding. Slider windows with shutters. Metal canopy over entrance. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: Car port. One Non-Contributing building.

(513118) M28. 106 WILSON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Faux 6/6 windows with shutters. Entrance porch on corner within roof overhang with Doric column on a concrete deck. One-story, shed roof porch on the side with square wood posts and a slatted balustrade. Concrete block foundation. 3 X 3 bays. One Non-Contributing building.

A.

date: Modern

description: Two-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(513129) M29. 110 GALLATIN STREET, residential

date: Modern

description: One-story, side gable house with central, end gable, entrance pediment supported by round posts on a concrete deck. Asphalt shingle roof. Vinyl siding. Faux 6/6 windows with shutters. Gable entrance porch on the side with square posts on a concrete deck; double atrium doors here. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

(513131) M30. 106 GALLATIN STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. Faux 6/6 windows with shutters. End gable entrance porch with square posts and slatted balustrade. One-story, shed roof addition on side. Concrete block foundation. 4 X 4 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 117

(513131) M30. 106 GALLATIN STREET, residential (continued)

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(6152) M31. 3 HENRY STREET, residential

date: Modern

description: One-story, end gable house with one-story, shed roof addition on the left front. Asphalt shingle roof. Vinyl siding. 1/1 windows. French doors in the front on the addition. Deck added to front as entrance. Concrete block foundation. 4 X 1 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

B.

date: Modern

description: One-story, end gable outbuilding. Asphalt shingle roof. T-111 siding. Can not see foundation. 1 X 1 bays. One Non-Contributing building.

(61514) M32. 705 ASHTON STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Multi-paned windows. Small entrance stoop/deck. Concrete block foundation. 4 X 1 bays. One Non-Contributing building.

(61515) M33. 707 ASHTON STREET, residential

date: Modern

description: One-story, rear facing "L" house. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, gable entrance porch with modern turned posts on a concrete deck. Concrete block foundation. 4 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 118

(61517) M34. 8 WILSON STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Multi-paned windows. Small deck/entrance stoop. Concrete block foundation. 4 X 1 bays. One Non-Contributing building.

(61519) M35. 14 WILSON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, end gable entrance porch with wrought iron posts on a concrete deck. Side entrance as well as front entrance. Concrete block foundation. 3 X 3 bays. One Non-Contributing building.

(71543) M36. 702 ASHTON STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. 1/1 and fixed pane windows. One-story, end gable, entrance porch with modern Doric columns on a concrete deck. Small entrance on the side. Concrete block foundation. 3 X 3 bays. One Non-Contributing building.

(71544) M37. 704 ASHTON STREET, residential

date: Modern

description: Two-story, side gable, split-level house with one-story, side gable wings flanking center section. Right wing is a one bay garage; left wing is entrance bay. Asphalt shingle roof. Brick and aluminum siding façade. Slider windows with shutters. Metal shed roof canopy over entrance supported by wrought iron posts. Concrete foundation. 5 X 1 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, shed roof outbuilding. Asphalt shingle roof. T-111 siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(71547) M38. 714 ASHTON STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Multi-paned windows with shutters. Entrance within roof overhang: left side is enclosed; right side is just a

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 119

concrete pad. ADA ramp on the left side to the rear porch. Rear porch has wrought iron posts. Concrete block foundation. 4 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, pyramidal hip roof outbuilding. Corrugated metal roof and siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(71548) M39. 716 ASHTON STREET, residential

date: Modern

description: One-story, side gable house with one-story, side gable wing on the left. Exposed red brick end chimney. Asphalt shingle roof. Vinyl siding. Multi-paned windows with shutters. Concrete deck/pad serves as entrance. Concrete block foundation. 4 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Aluminum siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

(71557.1) M40. 816D ASHTON STREET, residential

date: Modern

description: One-story, side gable house with raised basement that houses two garage bays. Asphalt shingle roof. Stucco façade and foundation. 1/1 windows. Metal canopy over entrance door. Two-story tall shed roof canopy on the rear. 2 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, shed roof outbuilding. Metal roof. T-111 siding. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

(1012142) M41. 101 ANN STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Aluminum and metal board and batten siding. Metal slider windows. One-story, shed roof metal canopy entrance with wrought iron posts and railing. Concrete block foundation. 4 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 120

(1012142) M41. 101 ANN STREET, residential (*continued*)

A.

date: Modern

description: One-story, end gable garage. Asphalt shingle roof. Aluminum siding. Concrete block foundation. 2 X 1 bays. One Non-Contributing building.

(111448) M42. 308 SAND STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Multi-paned windows with shutters. Small entrance stoop/deck. Concrete block foundation. 5 X 2 bays. One Non-Contributing building.

(111449) M43. 310 SAND STREET, residential

Mulberry Place Apartments

date: Modern

description: One-story, side gable, apartment building units. Asphalt shingle roof. Red brick and vinyl siding façade. Slider windows. Small entrance stoops. Garage bay in the gable end. Concrete foundation. 10 X 2 bays. One Non-Contributing building.

(111463) M44. 508 SAND STREET, residential

date: Modern

description: One-story, end gable house. Asphalt shingle roof. Vinyl siding. 1/1 windows with shutters. One-story, end gable, entrance bay with Doric columns. One-story, shed roof, car port on the side with square posts on a concrete deck. Concrete block foundation. 3 X 3 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(111469.1) M45. 416 ASHTON LANE, residential

date: Modern

description: Two-story, side gable house. Asphalt shingle roof. Vinyl siding. Slider windows. One-story, end gable, projecting entrance bay with Doric columns on a concrete deck. Concrete block foundation. 2 X 2 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 121

(111469.1) M45. 416 ASHTON LANE, residential (*continued*)

A.

date: Modern

description: One-story, shed roof outbuilding. Corrugated metal roof. Vinyl siding. Pier foundation. 1 X 1 bays. One Non-Contributing building.

(111472) M46. 600 ASHTON STREET, residential

date: Modern

description: One-story, side gable house. Asphalt shingle roof. Wood siding façade with faux stone veneer below. 1/1 windows. Small entrance stoop on the front and on the side. Faux stone veneer foundation. 4 X 2 bays. One Non-Contributing building.

(121254) M47. SYCAMORE STREET, commercial

Gary's Beverage & Video Inc.

date: Modern

description: One-story, end gable commercial building with central cupola. Asphalt shingle roof. Brick and glass façade. Concrete block foundation. 1 X 1 bays. One Non-Contributing building.

JA-0010-0046. (121258.1 & 2) M48. 257 WASHINGTON STREET, commercial

date: c. 1980

description: Long, one-story, side gable commercial building. Asphalt shingle roof. T-111 siding. Multi-paned windows with shutters. Recessed entrance bay. Concrete block foundation. 5 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: Two-story, cross gable garage/apartment. Asphalt shingle roof. Red brick façade. 1/1 windows. Garage bays infilled with siding and windows. Brick foundation. 2 X 1 bays. One Non-Contributing building.

(121294) M49. 300 SYCAMORE STREET, residential

date: Modern

description: One-story, hip roof house. Central interior chimney. Asphalt shingle roof. Vinyl siding. Slider windows. Small entrance porch with shed roof metal canopy with wrought iron railing. Concrete block foundation. 4 X 3 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 122

(1312107) M50. 308 MULBERRY STREET, residential

date: Modern

description: One-story, side gable, apartment units. Asphalt shingle roof. Brick and vinyl siding façade. Slider windows. Concrete block foundation. 9 X 2 bays. One Non-Contributing building.

M51. NUMBER SKIPPED.

(141284) M52. 226 WALNUT STREET, commercial

Angell Accounting

date: 2005

description: One-story, end gable, commercial building. Asphalt shingle roof. Vinyl siding. Multi-paned windows. Small entrance deck with slatted balustrade. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

(1412114) M53. SKIPPED NUMBER.

(15127.1) M54. WATER STREET, commercial

B&B Mini Storage

date: Modern

description: One-story, flat roof, commercial storage building. Metal roof. Metal siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

(15127.2) M55. 229 WATER STREET, residential

date: Modern

description: One and one-half-story, hip roof house with hip dormers on the front. Interior corbelled brick chimney. Asphalt shingle roof. Brick façade. Multi-paned windows. One-story, front porch within roof overhang with Doric columns on an enclosed brick balustrade. Concrete foundation. 6 X 2 bays. Large solid brick fence with brick columns surrounds house. One Non-Contributing building.

A.

date: Modern

description: One-story, gambrel roof garage/apartment. Asphalt shingle roof. Brick façade. One garage bay has been converted to a bow window for residential use. Concrete foundation. 2 X 1 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 123

(151229) M56. SYCAMORE STREET, municipal

Utility Shed

date: Modern

description: One-story, flat roof, utility building. Concrete block façade and foundation. 1 X 1 bays. One Non-Contributing building.

(151233) M57. 117 MULBERRY STREET, commercial

date: Modern

description: Two-story, flat roof, commercial building. Metal roof cap. Brick façade. Large garage bay on the left. Large display windows and man doors on the right. Concrete foundation. 6 bays wide. One Non-Contributing building.

(151235) M58. WASHINGTON STREET, commercial

Speedway Gas Station

date: c. 1960

description: One-story, flat roof, commercial building. T-111 siding and concrete block façade and foundation. Aluminum framed storefront. Gas pumps with canopy. One Non-Contributing building.

(16148) M59. 1 WALNUT STREET, residential

date: Modern

description: Two-story, end gable house with greenhouse/glazed sunroom on the left. Asphalt shingle roof. T-111 siding and brick façade. 1/1 windows. Large wraparound deck/porch with spindled balustrade and newel posts. Attached two bay garage on the end. Concrete block foundation. 2 bays wide. One Non-Contributing building.

(171413) M60. 117 WATER STREET, residential

date: Modern

description: Large two-story, side gable house. Asphalt shingle roof. Painted concrete block façade and foundation. Two garage bays in front. Squat and multi-paned windows; most with shutters. 4 X 2 bays. One Non-Contributing building.

(171416) M61. 115 WATER STREET, residential

date: Modern

description: One-story, cross gable house. Exposed red brick end chimney. Asphalt shingle roof. Red brick façade. 1/1 windows. Concrete foundation. 3 X 3 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 124

(171416) M61. 115 WATER STREET, residential (continued)

A.

date: Modern

description: One-story, cross gable garage with two garage bays. Asphalt shingle roof. Vinyl siding. Concrete foundation. 2 X 2 bays. One Non-Contributing building.

(171417) M62. 111 WATER STREET, residential

date: Modern

description: Two-story, shallow end gable house with two bay garage on first floor. Asphalt shingle roof. Concrete block façade with faux stone veneer on the front. 1/1 windows. Two-story, open porch faces the river and has wrought iron posts and railing. Concrete block foundation. 3 X 2 bays. One Non-Contributing building.

(171421) M63. 15 SAND STREET, residential

date: Modern

description: Two-story, hip on gable roof garage/apartment. Asphalt shingle roof. Vinyl siding on second floor; concrete block first floor and foundation. 1/1 and vertical 2/2 windows. Small shed roof porch and deck on the side. 3 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, gambrel roof outbuilding. Asphalt shingle roof. Vinyl siding in gable ends; concrete block façade and foundation. 1 X 1 bays. One Non-Contributing building.

JA-0010-0047. (171427(G) M64. WASHINGTON STREET, commercial
Nationwide Insurance

date: c. 1970

description: One-story, modified hip roof, commercial building. Wood shingle roof/canopy. Brick façade and foundation. Slider windows. Central flush entrance door. 3 X 2 bays. One Non-Contributing building.

JA-0010-0010. (171427.1) M65. 100 WALNUT STREET, residential

date: c. 1970

description: One-story, side gable house with attached, side gable two bay garage on one end. Interior red brick chimney. Asphalt shingle roof. Red brick façade. 6/6 windows. One garage bay has been converted to man door entrance. Concrete foundation. 6 X 4 bays. Ranch style. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 7

Page 125

(18142) M66. 30 SAND STREET, residential

date: Modern

description: Tall one-story, side gable house with loft. Metal roof. Exposed end chimney covered in siding. Wood T-111 siding. 1/1 windows. Two-story, end gable, projecting, entrance bay with recessed entrance area. Deck on one end and on the rear. Concrete block foundation. 2 X 2 bays. One Non-Contributing building.

A.

date: Modern

description: One-story, end gable car port/patio. Metal roof supported by square posts on a concrete deck. One Non-Contributing building.

B.

date: Modern

description: One-story, side gable outbuilding. Asphalt shingle roof. T-111 siding. Concrete foundation. 1 X 1 bays. One Non-Contributing building.

C.

date: Modern

description: Tall two-story, end gable garage. Metal roof. Painted T-111 siding. Two garage bays. Concrete foundation. 2 X 3 bays. One Non-Contributing building.

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 8Page 126**Statement of Significance**

The "Old Town" Historic District is locally significant under the National Register *Criterion A* for *Community Planning and Development* and for *Commerce* through its association with the transportation modes of the river, the railroad and the roads. The district also qualifies under the National Register *Criterion C* for *Architecture* through its association with many of the architectural styles of the mid to later 19th and early and mid 20th centuries. The recommended period of significance would be from c. 1830, the construction date of the Fitzhugh/Merritt House (JA-0010-0011) and up to 1957, the construction date of the Miller Building (JA-0010-0052).

Early History

As a reward for service in the French and Indian War, Lieutenant Colonel George Washington and many of his Virginia Regiment militiamen were promised land patents in the Ohio River Valley. In 1770, a party including Washington and a Pennsylvania surveyor, Colonel William Crawford, began an expedition by canoe from Fort Pitt to explore possible sites for the bounty lands due them. The party traveled down the Ohio as far downstream as present-day Point Pleasant.

In 1771, Crawford began to survey the tracts he and Washington had identified on the expedition, including the land on which present-day Ravenswood rests. In a letter penned some twenty years later, Washington would describe his Ohio River holdings as "the cream of the Country in which they are; that they were the first choice of it." Present-day Ravenswood was laid out on a portion of a 2,448-acre tract surveyed for Washington by Crawford in 1771.

On his death, Washington's Ohio River holdings, including present-day Ravenswood, totaled 9,744 acres. Washington willed that many of his holdings should be sold on his death and the proceeds divided into 23 equal lots that then would be passed on to certain named heirs. Among these were the heirs of Ann Ashton, who would share a portion of one share of the estate and Martha Parke Peter, who was given a share. In October of 1804, the 2,448 acres of land around, and on which, present-day Ravenswood sits was surveyed for the purpose of division among the entitled heirs. The actual division was completed in 1805. At that time, the uppermost half of the tract was allotted to Thomas Peter (as agent for his wife Martha Parke Peter) and the lower half was allotted to the heirs of Anne Ashton. When the 1804 survey was completed, it was determined that the actual size of the entire tract was 2,850 acres, not 2,448. Thus, each of the two allotments was for 1,425 acres.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8


Page 127

Among Ann Ashton's heirs were members of the Fitzhugh family. Circa 1950, Norman Fitzhugh, son of Nicholas Fitzhugh and grandson of Henry and Henrietta S. Fitzhugh, began documenting some of his family's history and that of Ravenswood. The quoted excerpt below is taken from those notes:

The Thomas Peter allotment was sold in 1836, and in 1866, Judge Brown acquired that part bordering on the upper line of Ravenswood.

The heirs of Anne Ashton were, Burditt Ashton, Jr., Anne Ashton and Sarah Ashton Fitzhugh. This property was assessed to the heirs of Anne Ashton until 1810 (I have a receipted tax bill for that year). In 1810, Judge Nicholas Fitzhugh acquired the interest of Burditt Ashton and the interest of Anne Ashton and took title to his wife's interest (I have original deeds). For the year 1811 and subsequently the land was assessed to "Nicholas Fitzhugh Esq." (I have tax tickets 1811-12).

In 1815, the property was divided among five female heirs of Nicholas Fitzhugh – Henry Fitzhugh and his wife Henrietta acquired the interests (except one). The town of Ravenswood is laid out on the Mary Conway Mason Fitzhugh Division.



(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 8Page 128

Henry Fitzhugh purchased the land that Ravenswood rests on in July 1836 from Mary Conway Mason (Fitzhugh) Payne. The deed is recorded in Jackson County in Deed Book 1 at page 497. The sketch on the preceding page is the work of Norman Fitzhugh. It depicts the parcels as they were to be divided between the daughters of Judge Nicholas Fitzhugh.

Ultimately members of the Fitzhugh family laid out the original town, all of which was within the Historic District. Settlement in the district, by the Fitzhughs, and others, had begun in earnest by the 1830s. The Fitzhugh home (JA-0010-0011) still stands and it is believed to be the oldest surviving building in Ravenswood.

The community that would become the town of Ravenswood continued to grow through the 1830s and 1840. As the 1850's began, the local citizens began to organize efforts to incorporate the community. By 1850, Jackson County's population had grown to 6,544. Of that total, 276 souls called present-day Ravenswood home. On March 10, 1852, the town of Ravenswood was chartered by an act of the Virginia General Assembly.

The Ohio River marked the southern boundary of the Northwest Territory. As such, it would become the border between the slave states in the south and the free states and territories to the north and west. In 1860, Ravenswood was home to 362 white residents and an unknown, but relatively small number of slaves. Most of the town's residents would have considered themselves northern sympathizers; however, at least 13 families were known southern sympathizers.

Among the southern sympathizers were the Fitzhughs and Flemings and their extended families. Given their sympathies, the Fitzhugh home (JA-0010-0011) and gardens were repeatedly commandeered by Union forces. In 1862, the Fitzhugh home briefly hosted Confederate General Albert Gallatin Jenkins and his troops, including Nicholas Fitzhugh, before they continued their pursuit of fleeing Union forces and moved on into Ohio. In July of 1863, the crew of the Union Naval Vessel *Moose* commandeered a meal and provisions from the Fitzhughs before sailing upstream to engage the forces of General John Hunt Morgan at the battle of Buffington Island.

All of this is well documented in the diary of Henrietta Fitzhugh Barre. Ms. Barre's diary and anecdotal evidence suggests that the homes and improvements of the extended Fleming and Fitzhugh families (JA-0294, Fleming family; JA 0010-0005 and JA-0274, Fitzhugh family homes) were subject to similar Union actions.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 129

After the Civil War, the charter of Ravenswood was amended and reenacted by an act of the Legislature of West Virginia, passed February 25, 1868. It described the corporate limits thusly:

The corporate limits of the Town of Ravenswood shall be as follows, to-wit: Beginning at the mouth of Sand Creek, at low water mark, and running thence with said creek to the foot of Gallatin Street; thence with the line of said street to the line of R. S. Brown's farm; thence with the line of said farm to the Ohio River; thence down the Ohio River, at low water mark, to the place of beginning."

In addition to all of what was considered the town of Ravenswood in 1868, the "Old Town" Historic District also includes the properties between the current eastern city limits and Gallatin Street; thus, the corporate bounds described in 1868 account for approximately 75% of the ground within the "Old Town" Historic District.

Aside from access via the river, Ravenswood was a relatively isolated community through the 1850s, 1860s and 1870s. Roads, or what passed for roads, were often little more than improved trails running along the river and creek bottoms.

Prior to the Civil War, the roads of western Virginia were few in number and generally poor in quality, and the quality of the roads deteriorated further as the war progressed. After the war, the lack of infrastructure proved beneficial to Ravenswood and other river towns. Like many other similarly-situated towns, Ravenswood became a commercial hub for the residents of outlying communities and farms. Even with its proclivity for periodic flooding or low-water events, the Ohio River was the surest and most economical means for transporting goods in the 1860s through the 1880s. Several early roads were constructed; they included the Ohio River Hills Road, the Charleston, Ripley and Ravenswood Turnpike and the Ravenswood and Reedy Creek Turnpike

The first Ravenswood resident to take advantage of the river for commerce was Bartholomew Fleming. Born in Pennsylvania in 1801 or 1804, he made his way to Ravenswood by way of a flatboat while still a teenager and was a permanent settler at Ravenswood by 1820. He and his family would, among other endeavors, be involved in the delivery of mail by way of riverboat. He also kept a fuel yard to supply the steamboats that plied the river. By 1831, he was in the business of ferrying passengers and goods across the Ohio River. In 1877, Bartholomew Fleming owned Town Lots 7 and 8. These lots adjoined each other and were located just northeast of the intersection of Walnut and Water Streets. Fleming and his family operated the ferry from the landing at the end of Walnut Street to their property in Meigs County, Ohio. The

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 130

Fleming family would also engage in the milling business. One of the original, Fleming-family homes (JA-0294) is located at the intersection of Sycamore and Race Streets.

In addition to commercial goods, the river was also the surest and fastest means of travel between north and south, thus from its earliest days, Ravenswood would serve as a stopping point for travelers. A number of restaurants, hotels, boarding houses, taverns and opera houses would be constructed in the historic district to meet the entertainment, lodging and boarding needs of transients, laborers and salesmen.



Victoria Inn in the 1920s? (JA-0010-0031)

Facilities for lodging and dining have been a part of the town since at least 1839. According to one source, a hotel was then in operation in Ravenswood, probably near the confluence of Sandy Creek and the river. By 1877, at least three hotels were in operation. One of these may have been the St. Charles Hotel, which was located on Broadway Street. Other hotels and boarding houses would follow through the years. Of these buildings, only the Victoria Inn (JA-0010-0031) survives.

Ravenswood also experienced growth due to the opening of several railroad lines. On June 16, 1884, the Ohio River Rail Road opened its line for traffic between Wheeling and Parkersburg. The line was extended to Huntington by 1888.

In a 1901 agreement, the Baltimore & Ohio Railroad assumed operation of the Ohio River Railroad and by 1912 it became the Ohio River Division of the Baltimore & Ohio Railroad. Passenger service on the Ohio River Division was discontinued on January 31, 1957.

The ticket on the following page provides a glimpse of the extent of service available in the Ravenswood area on the Ohio River Rail Road, before 1912. Note that, from Belleville to Letart, a roughly 30-mile long stretch with Ravenswood at the center, the rail road had 15 stops. For the farmers and citizens of the small communities served by the rail line, this allowed ready access to Ravenswood's marketplace and the goods and services that the town had to offer.


(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 131



The Ohio River Rail Road included two branch lines. The Ravenswood, Spencer & Glenville Railroad met the ORRR near Ravenswood's Washington's Land Park, while the Ripley and Mill Creek Valley Railroad ran from Cottageville to Ripley.

While passenger service was offered, travelers arrived in town and embarked from a terminal that was located on the east side of the tracks, diagonally opposite from the Victoria Inn. That is, it stood on the northeast corner of the intersection of Mulberry and Broadway Streets.

Unfortunately, the passenger terminal that the Ohio River Rail Road built in Ravenswood has been lost. However, the baggage pavilion was saved. This structure was moved to the Veteran Memorial City Park and has been used as a picnic shelter for years.



Freight Terminal

The Ravenswood freight terminal building still exists. It lies just outside of the Old Town Historic District on the northeast corner of the intersection of Sycamore and Broadway Streets.


(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 132



The figure on the left is excerpted from the 1909 Sanborn Map[®] and depicts the “industrial” part of the historic district.

Served by the river, the railroad, and passable surface roads, Ravenswood also played host to a number of wholesale and retail grocers, department stores, hardware and house ware stores, pharmacies, banking institutions and professional offices. Many of the buildings that these enterprises were located in were built above Broadway Street and the railroad, and thus, beyond the reach of river flooding.

Notable among these surviving buildings are the former Ravenswood Grocery Company

(JA-0010-0001), A.P. Fisher’s Grocery (JA-0219) and the J. A. McMurray Grocery Store (JA-0010-0029) buildings. Surviving buildings that housed department stores include the K. M. Click & Company building (JA-0010-0051), the building that housed the Slaven Store Company (JA-0010-0040) and the Craigo Building (Ravenswood Cash Store, JA-0010-0038). Stores buildings that housed hardware, house wares and department stores included the Harpold Brothers (McIntosh) building (JA-0010-0058) and the W. G. Watts & Son (JA-0210) building. Various professional and banking services were housed in the Fleming–Polsene–White–Staats building (JA-0010-0060), the J.B Shockey’s Jewelry Store building (JA-0010-0039), and the Jackson County Bank (JA-0010-0062), First Federal Savings and Loan Association (JA-0010-0055) and Farmers Building and Loan Association (now City of Ravenswood Town Hall, JA-0010-0059) buildings. Buildings that hosted medical, dental and pharmaceutical concerns include the Starkey Hospital (JA-0234) and Priddy Hospital (JA-0010-0045) buildings, Dr. H.C. Wagner’s office (JA-0010-0062), the E.H. Nowell (JA-0010-0063) building and Brown’s Drugstore (JA-0010-0050).

The majority of these buildings were constructed during the period between 1890 and 1925, a period when Ravenswood saw its greatest growth and wealth. Ravenswood’s fortunes began to wane in the late 1920s. From then until the mid-1950s, Ravenswood would be isolated from many of the changes that the rest of the nation would see. River traffic was diminishing and

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEETSection number 8Page 133

passenger traffic by rail was also in decline. Improved highways and use of the automobile and trucking were changing the landscape of the nation. But the main state road through the county, State Route 21, bypassed Ravenswood. State Route 2 ran along the banks of the Ohio River, but its paving stopped 30 miles above and 30 miles below Ravenswood. The unpaved stretch would not be completed through Ravenswood until 1954. Without access to the most popular modes of transportation, Ravenswood's growth stagnated.

As the 1950s rolled along, Ravenswood and the surrounding area were about to be transformed by events unlike any other in the past. The text below was originally presented in an article entitled "Look Homeward Angel" in the Summer 1958, Kaiser Aluminum News.

In 1911, state geologist I. C. White of West Virginia sat down in his office in Wheeling and wrote the following description of Ravenswood.

Ravenswood, the largest town in Jackson County, is located on the Ohio River at the mouth of Sandy Creek, 36 miles south of Parkersburg and 85 miles north of Huntington. It is situated mainly on the second terrace of the Ohio River and is therefore above high water. The land where the town is located was once owned by George Washington. The town had a population in 1900 of 1074 and in 1910 of 1081.

There are located here an excellent high school, six churches, a canning factory, fifteen stores, three banks, and two building and loan associations...it derives a portion of its support from the railways, but the larger portion is derived from the agricultural districts.

The *Kaiser Aluminum News* article went on to say:

As late as 1951 - forty years that transformed most of the rest of the United States - the only item that would need to have been changed was that the population had grown to 1,175.

Since the 1920s, Ravenswood struggled along on the services it could render as a shopping center and rail-shipping point for those of the county's 2,000 farm families who did not find Ripley more convenient. As is the case today, the population of Ravenswood was made up primarily of older, semi-retired or retired people. Most of the youth had left for better prospects in Wheeling and Charleston and the industrial cities of the North.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 134

The *Kaiser Aluminum News* article continues:

By mid-summer 1954, the town's main street might well have been a movie set for turn-of-the-century motion pictures. Two blocks of red brick and painted metal buildings stretched down either side of Route 2 (Washington Street, now State Route 68). A single movie house and two taverns offered the town's "night life" entertainment. There were no intersection traffic lights, no parking meters, few intact sidewalks or curbing. The residential section of the town was characterized by old homes, some of them graceful reminders of a more prosperous era, stately trees lining both sides of the unpaved streets. The most outstanding features in town were the church spires and the high school.

All of this changed in August of 1954 when Kaiser Aluminum announced that it planned to build a new sheet and foil rolling mill seven miles south of Ravenswood. Before the shock of this announcement had worn off, it was followed by announcements in October and December that the plant would be expanded to include a hot rolling line, more cold rolling and finishing equipment and a reduction plant. When all was said and done, the plant would be the largest integrated aluminum plant in the world and it would employ more than 4,000 production workers and its construction would employ 7,000 construction workers.

In the early 1900s, what would become known as "North Ravenswood" had begun to develop. As the name suggests, it was a residential/commercial area north of the corporate limits. This area, although unincorporated, began to rival Ravenswood in size and population. In addition to housing growth, North Ravenswood also hosted several small factories, including a marble works and a pottery factory.

North Ravenswood, and Ravenswood proper were separated by a large farm that ran from the Ravenswood corporate limits northward for nearly two miles until it met the North Ravenswood development. This farm also extended from the river several miles to the east.

After the Kaiser Aluminum plant located in Jackson County, the farmland that was between the original town of Ravenswood and North Ravenswood was subdivided and developed with homes and businesses and the entire area brought within the Ravenswood corporate limits. From the late 1950s on to the present, this former farm area was referred to locally as the "new part of town" and the original town became known as the "old part of town" or the "Old Town."

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 135

Criterion A: Community Planning and Development

Beginning at the point where Washington's Ravenswood-area holdings were surveyed and divided among his heirs to the Fitzhugh's platting of the town and beyond, Ravenswood was a "planned" community. The original town consisted of blocks divided by streets that ran parallel with the river and streets that ran perpendicular to it. From the river moving east the streets were Water, Broadway, Race, Washington and Virginia. The perpendicular streets, from north to south, were Sycamore, Mulberry, Walnut and Sand. Beyond these boundaries, the Fitzhugh's continued to subdivide their holdings such that aforementioned street pattern would be repeated as the town expanded away from the river, to the east.

Criterion A: Commerce

Recognizing the value of access to the River, the Fitzhugh's prohibited any obstructions whatsoever "on the bank aforesaid [Ohio River] within the limits aforesaid but shall leave the same free for the ingress egress and regress of the said Bartholomew Flemming¹ and others owning lots in said Town to make roads and landings from the margin of the Ohio river up the bank to Water Street."

The town would grow around the river lots and Fleming's ferry landing through the latter half of the 19th century. In the late 1880s, the Ohio River Rail Road was constructed through the Ravenswood area. The coming of the railroad would lead to one of the town's most prosperous periods and would lead to a 20-year period of population growth. For the next half century, Ravenswood would serve as a commercial center and river/rail-shipping point for many of Jackson County's 2,000 farm families.

Criterion C: Architecture

The "Old Town" Historic District is significant for its varied and well-maintained homes and businesses representing a wide range of architectural styles, among them: Greek Revival, Gothic Revival, Italianate, Second Empire, Queen Anne, Colonial Revival, Classical, Neo-Classical Revival, Tudor Revival, the Commercial Style, Craftsman Four Square, Craftsman, Bungalow, the Ranch Style, Moderne and Art Deco.

¹ The Fleming name is misspelled "Flemming" throughout the deed that this was quoted from.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 8

Page 136

Summary

In a 1794 correspondence to James Ross, Washington described his Ohio and Kanawha River holdings, including the land on which the propose historic district rests as “the cream of the country in which they lye, being the first choice of it.” Owing to the foresight of Washington’s heirs, the Fitzhughs, the town was laid out in an organized grid pattern and developed as a well-planned community. Its location on the banks of the Ohio and the later arrival of the railroad through town ensured the commercial health and stability of the community. The well-maintained homes and businesses in the district are excellent representatives of the architectural styles for the period c. 1830 through 1957.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 9

Page 137

Bibliography

Barr, Henrietta. The Civil War Diary of Mrs. Henrietta Fitzhugh Barr (Barre), 1862-1863, Ravenswood, Virginia (West Virginia). Edited by Sallie Kiger Winn. Marietta: Marietta College, 1963.

Carley, Rachel. The Visual Dictionary of American Domestic Architecture. Henry Holt and Company, Inc. 115 West 18th Street, New York, New York 10011. 1994.

Elliott and Nye. Elliott and Nye's Virginia Directory and Business Register for 1852. Richmond, VA., 1852.

Freeman, Douglas Southall. R. E. Lee: A Biography. Charles Scribner's Sons, New York and London, 1934

Harris, Cyril M. Illustrated Dictionary of Historic Architecture. Dover Publications, Inc. 1977.

Hayes, Eli. Illustrated Atlas of the Upper Ohio River and Valley From Pittsburgh, PA To Cincinnati, Ohio. 1877.

House, John A. Pioneers of Jackson County, West Virginia; History of Mill Creek and Sandy Valley and Its Early Settlement. Self Published, 1906

INDEPENDENT, 1992. Picking up the bills. *Independent*, 4 June, p.28a.

Jackson County History Book Committee. Jackson County West Virginia, Past And Present. Walsworth Publishing Co., 1990

Kaiser Aluminum News. Look Homeward Angel. Summer 1958.

Longstreth, Richard. The Buildings of Main Street A Guide to American Commercial Architecture. The Preservation Press, National Trust for Historic Preservation. 1987.

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 9

Page 138

McAlester, Virginia & Lee. A Field Guide to American Houses. Alfred A. Knopf, Inc. 1984.

Moore, Dean W. Washington's Woods, A History of Ravenswood and Jackson County, W Va. McClain Printing Company, Parsons, WV, 1971.

Noble, Allen G. Wood, Brick & Stone The North American Settlement Landscape Volume 1: Houses. The University of Massachusetts Press, Amherst. 1984.

Ravenswood and its People The "Old Town" Historic District. Prepared by the Ravenswood Historic Landmarks Commission. May 2006. Unpublished manuscript.

Sanborn Fire Insurance Maps from 1893; 1898; 1904; 1909; and 1927.

Sims, Edgar B. Making A State. Published by the State of West Virginia. Mathews Printing and Lithographing Company, Charleston, West Virginia, 1956.

Thompson, Ali. Sandyville native's love of marble collecting stems from old Ravenswood plant. *The Jackson Herald*.

<http://webroots.org/library/usahist/pojc0000.html>

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number 10

Page 139

Verbal Boundary Description

Bounded by Sandy Creek to the south, the Ohio River to the west, Sycamore Street and adjoining properties to the north and the Ravenswood corporate limits to the east.

Boundary Justification

The original town consisted of blocks divided by streets that ran parallel with the river and streets that ran perpendicular to it. From the river moving east the streets were Water, Broadway, Race, Washington and Virginia. The perpendicular streets, from north to south, were Sycamore, Mulberry, Walnut and Sand. The town would grow and streets were added, primarily to the east, but several would also be added between Sand Street and Sand Creek.

In 1877, Eli Hayes completed the Illustrated Atlas of the Upper Ohio River and Valley from Pittsburgh, Pa. to Cincinnati, Ohio. The Hayes map of town depicts Anne (the "e" was later dropped), Henrietta, Henry and Gallatin Streets to the east of Virginia and a number of large properties, on the south side of Sand Street, owned by the Fitzhughs, the Callisons, B.C. Hutchinson, J.W. Bennett, B.H. Hoyt, John Redman and C.M. Rice. The C.M. Rice property was divided into eight lots. W.D. Williamson owned a "sub-addition" that included the block bounded by Sand, Virginia, Walnut and Anne Streets and the Fitzhughs had an addition comprised of Town Lots No. 105 to 196

Later, Wilson and Bedford would be added to the east of Gallatin and Ashton and Ashton Lane would be added toward Sand Creek. Thus, by 1898, the "Old Town" district had been established.

In the early 1900s, what would become known as "North Ravenswood" began to develop. As the name suggests, it was a residential/commercial area north of the corporate limits. After the Kaiser Aluminum plant located in Jackson County, seven miles from Ravenswood, the farmland that was between the original town of Ravenswood and North Ravenswood was subdivided and developed with homes and businesses. From the late 1950s on to the present, this area was referred to locally as the "new part of town" and the original town became known as the "old part of town" or "Old Town."

(NPS Form 10-900)

United States Department of the Interior
National Park ServiceNATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number

PhotoPage 140

Photographer: **Mark Gorman, Fox Engineering and Michael Gioulis, Historic Preservation Consultant**

Date: **Varies between dates in late 2005 to early in 2006. See back of pictures for specific dates taken.**

Negatives: **Provided to WV SHPO, Charleston, WV, with Intensive Survey.**

Refer to the accompanying map entitled "Ravenswood's 'Old Town' Historic District – Ravenswood, Jackson County, West Virginia" for the locations of photographed buildings and structures in the District. Refer to the Field Survey Number in the descriptions below and on the map. For example, the Ohio River Rail Road bridge, located in the southwest corner of the mapped District, has a Field Survey Number of JA-0010-0004.

STRUCTURES

Photo 1 of 49 JA-0010-0004, The Ohio River Rail Road bridge, looking west

Photo 2 of 49 JA-0293, State Route 68 Bridge, looking west

COMMERCIAL BUILDINGS

Photo 3 of 49 West side of Washington Street, at Mulberry Street intersection, looking northeast

Photo 4 of 49 JA-0010-0045, Family & Cosmetic Dentistry (Old Priddy Hospital), at the northeast corner of Washington and Mulberry Streets, looking northeast

Photo 5 of 49 East side of Washington Street, at Mulberry Street intersection, looking southwest

Photo 6 of 49 JA-0010-0037, McIntosh Building (Old Hardware Store), southeast corner of Washington and Walnut Streets, looking southeast

Photo 7 of 49 JA-0010-0001, Randolph/Caldwell Building (Old Ravenswood Grocery), southwest corner of Walnut and Broadway Streets, looking southwest

Photo 8 of 49 East side of Washington Street, at Mulberry Street intersection, looking southwest

Photo 9 of 49 North side of Walnut Street, at Virginia Street intersection, looking northwest

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number

PhotoPage 141

-
- Photo 10 of 49** South side of Walnut Street, at Virginia Street intersection, looking southwest
- Photo 11 of 49** North side of Mulberry Street, at Washington Street intersection, looking northwest
- Photo 12 of 49** South side of Mulberry Street, looking northwest, midway between Washington and Race Streets.

CHURCHES, WEST TO EAST

- Photo 13 of 49** JA-0010-0068, Frontier Furniture Storage Building(Old Presbyterian Church), looking northwest
- Photo 14 of 49** JA-0176, First Baptist Church, looking northeast
- Photo 15 of 49** JA-0187, Grace Episcopal Church, looking northeast
- Photo 16 of 49** JA-0199, Our Savior Evangelical Lutheran Church (Old Walton Memorial Methodist Church), looking southwest
- Photo 17 of 49** JA-0122, First Christian Church, looking northeast

RESIDENTIAL STREETSCAPES

- Photo 18 of 49** Mulberry Street, looking west, between Washington and Race Streets
- Photo 19 of 49** West side of Virginia Street, looking southwest, near intersection with Sycamore Street
- Photo 20 of 49** East side of Virginia Street, looking northeast, at the intersection with Walnut Street
- Photo 21 of 49** Walnut Street, looking east, midway between Ann and Henrietta Streets
- Photo 22 of 49** West side of Henrietta Street, looking southwest, at the intersection with Mulberry Street
- Photo 23 of 49** East side of Henrietta Street, looking southeast, at the intersection with Mulberry Street
- Photo 24 of 49** East side of Henrietta Street, looking northeast, at the intersection with Walnut Street
- Photo 25 of 49** East side of Henrietta Street, looking southeast, at the intersection with Walnut Street

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number

Photo

Page 142

Photo 26 of 49 West side of Henry Street, looking northwest, at the intersection with Walnut Street

REPRESENTATIVE RESIDENTIAL PROPERTIES

MID-19TH CENTURY: Greek Revival, Gothic Revival

Photo 27 of 49 JA-0010-0011, Merritt House (Fitzhugh/Fleming), looking east

LATE VICTORIAN: Italianate, Second Empire, Queen Anne

Photo 28 of 49 JA-0266, Lemley/Wood/Sayre/Benford House, looking northeast

Photo 29 of 49 JA-0264, Winebrenner House, looking East

Photo 30 of 49 JA-0252, Nicholas House, looking West

Photo 31 of 49 JA-0054, Hicks House, looking southeast

Photo 32 of 49 JA-0278, Gorman House, looking southwest

Photo 33 of 49 JA-0255, Vanderlaan House, looking northeast

Photo 34 of 49 JA-0047, Lacava House, looking southeast

Photo 35 of 49 JA-0183, Varney House, looking northwest

LATE 19th AND 20th CENTURY REVIVALS: Colonial Revival, Classical, Neo-Classical Revival, Tudor Revival

Photo 36 of 49 JA-0274, Burlingame House, looking southeast

Photo 37 of 49 JA-0163, Porter House, looking South

Photo 38 of 49 JA-0108, Shinn House, looking southeast

LATE 19th AND EARLY 20th CENTURY AMERICAN MOVEMENTS: Commercial Style, Craftsman Four Square, Craftsman, Bungalow

Photo 39 of 49 JA-0250, Howard House, looking northwest

Photo 40 of 49 JA-0175, Price House, looking southeast

OTHER (Various Categories and Subcategories and Mixed Styles)

Photo 41 of 49 JA-0010-0005, Quarrier House, looking southeast

Photo 42 of 49 JA-0010-0034, Mace House, looking southeast

Photo 43 of 49 JA-0195, Chaffin House, looking northeast

(NPS Form 10-900)

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
CONTINUATION SHEET

Section number

Photo

Page 143

Photo 44 of 49 JA-0149, Radzyninski/Umpheby House, looking northeast

Photo 45 of 49 JA-0172, Warner House, looking southeast

Photo 46 of 49 JA-0184, Floto House, looking southeast

Photo 47 of 49 JA-0188, McNeely House, looking southwest

Photo 48 of 49 JA-0056, Garrett House, looking East

MODERN MOVEMENT: Ranch Style, Moderne, Art Deco

Photo 49 of 49 JA-0042, Matics House, looking southeast



LEGEND

Contributing building

Non-contributing building

00 = Building Survey #


M1 = Modern Building #

NR = Listed on the National Register

Photograph # and Vantage Point/Direction of Photograph

Building depictions are not to scale. They merely denote the presence of a structure and its approximate scale and location on a parcel of property.

A1 = JA-0000
 A2 = JA-0010-0049
 A3 = JA-0010-0048
 A4 = JA-0010-0048
 A5 = JA-0010-0048
 A6 = JA-0010-0048
 A7 = JA-0010-0048
 A8 = JA-0010-0043
 A9 = JA-0261
 A10 = JA-0010-0042
 A11 = JA-0010-0041
 A12 = JA-0010-0040
 A13 = JA-0010-0039
 A14 = JA-0010-0038
 A15 = JA-0010-0061
 A16 = JA-0010-0062
 A17 = JA-0010-0055
 A18 = JA-0010-0056
 A19 = JA-0269
 A20 = JA-0010-0054
 A21 = JA-0010-0053
 A22 = JA-0010-0052
 A23 = JA-0010-0051
 A24 = JA-0010-0050
 A25 = JA-0010-0050




Ravenswood Architecture & History Intensive Survey
 Jackson County, West Virginia

Dwg. No. **RAVENSWOOD**
 Scale
 Date 5/4/06



CARSON'S CORNER
 PROFESSIONAL BUILDING
 101 NORTH COURT STREET
 RIPLEY, WV 25271
 (304) 372-3705
 www.foxengineering.net



4313

57'30"

4312

4311

UTM
ALL ZONE 17

EASTING NORTHING

	EASTING	NORTHING
1	433689	4311113
2	433863	4311212
3	434840	4311529
4	434802	4311158
5	434914	4310874
6	434837	4310772
7	434382	4310959
8	434121	4310931
9	434167	4310860
10	434065	4310799
11	434029	4310860
12	433963	4310799

(SANDYVILLE)
4661 NW









Family & Cosmetic
Dentistry
THE COMPLETE DENTAL CENTER
273-5301

SIMPSON SIMPSON GUEST DAVIS
D.D.S. D.D.S. D.D.S. D.D.S.









































































NO
PARKING
8:00AM
TO
4:00PM

ANN ST
SYCAMORE ST

217

















